

Manufacturing Model: Simulating Relationships Between Performance, Manufacturing, and Cost of Production SECA Modeling & Simulation Team - Integration Meeting

Hyatt Pittsburgh Airport

October 15, 2002

TIAX LLC Acorn Park Cambridge, Massachusetts 02140-2390

Reference: TIAX LLC -80034 DE-FC26-02NT41568

- 1 Technical Issues
- 2 R&D Objectives and Approach
- 3 Activities for Phase I



Technical Issues

For commercial success, SOFC technologies must ultimately be manufacturable and cost competitive. A number of factors contribute to uncertainty at this time.

- Cell design, stack designs, and production processes are still in early stages of development
- SOFC stacks are radically different in structure from any currently massproduced ceramic products
- Relationships between cell and stack design, design tolerances, and stack performance are not very well established



Technical Issues

Proposed manufacturing processes may be amenable to high-volume production, however, specific processes and sequences must be selected.

Potential Process Flow for Planar Anode-Supported SOFC **Multi-Fired Process Flow Process Flow Assumptions** Interconnect Progressive Paint Braze Shear Rolling of onto Braze Electrical layer Interconnect Interconnect Interconnect powders are made by ball milling and calcining. Anode **Electrolyte** Interconnects are Electrolyte Anode made by metal Small Powder Powder Prep Prep forming **Fabrication** techniques. Vacuum Blanking / Sinter in Air Screen Automated Tape Cast Plasma Sinter in Air Finish Edges 1400C Čheck Print Slicing Sprav inspection of the electrical layers occurs after Vacuum Screen sintering. Plasma Slip Cast Print Spray Slurry Slurry Spray Spray Stack Assembly



Note: Alternative production processes appear in gray to the bottom of actual production processes assumed

Technical Issues

Relationships between cell and stack design, design tolerances, stack performance, and process yields are not very well established.

- Properties of individual layers thickness, physical attributes, conductivity (electrical or ionic), polarization, transport, mechanical
- Manufacturing Options
 - Individual process steps
 - Sequence of steps
- Impact on
 - → Process yield, tolerances, and reproducibility
 - Performance
 - → Thermal cycling and Life
 - Cost



A state-of-the-art SOFC manufacturing model will allow developers and NETL to minimize the uncertainties inherently associated with commercialization of a new technology. The model must be able to:


- Handle all key SOFC stack components, including ceramic cells and interconnects
- Relate manufactured cost to product quality and likely performance, taking into account
 - manufacturing tolerances
 - product yield
 - line speed
- ◆ Address a range of manufacturing volumes, ranging from tens of MW to hundreds of MW per year
- Adapt to individual production processes under development by SECA industrial teams



- 1 Technical Issues
- 2 R&D Objectives and Approach
- 3 Activities for Phase I



The Manufacturing Model Project will develop a tool to provide guidance to the DOE and SECA development teams on system design and manufacturing processes selection.




The primary output of the model will be an activity based manufacturing cost for various SOFC system scenarios.

Our approach to this assignment will leverage analysis models and experience gained through SOFC projects for NETL SECA and other clients.


- Anode-Supported Planar SOFC Detailed Manufacturing Cost Assessment
- Assessment of Status of Residential Fuel Cell Developments (for EPRIsolutions)
- Scale-up Study of 5-kW SECA Solid Oxide Fuel Cell Modules: 250-kW system
- Conceptual Design of POX/SOFC Auxiliary Power Unit (APU) 5kW System
- Technology Assessment of Solid Oxide Fuel Cell Stack Technology (for EPRIsolutions)
- Assessment of Structural Limitations in the Scale-up of Anode Supported SOFCs



The structural model accounts for all the relevant electro-chemo-thermomechanical phenomena, which influence cell performance (hence cost).




The mechanical stress distribution in a planar SOFC is governed by a combination of design parameters and operating conditions.



^{*} necessary for sealing and electrical interconnection in many planar stack designs

The non-linear interactions among these phenomena make purely empirical characterization impractical and one-by-one analysis difficult. To evaluate the impact of cell size, we use a cross-flow configuration.



We are currently developing a similar model for circular cells.


For the base case, we selected operating conditions consistent with previous TIAX studies.

Parameter	Value			
Cell voltageComposition of the reactant streams	 0.7 V Anode: 97 % H₂, 3 % H₂O, Cathode: air 			
Gas inlet temperaturesFuel utilizationCathode stoichiometry	 650 °C at the Anode and Cathode ~ 50 % ~ 5, the cathode flow rate was adjusted such that the temperature at the cell outlet was nominally 800 °C. 			




The structural model calculates the time-dependent current density distribution during cell operation.


Cell voltage = 0.7 V
Steady state current density distribution, average = 1.3 A/cm²






Uncompensated bending stresses lead to warping of the MEA when it is cooled down to room temperature from the sintering temperature.





A confining pressure (0.4 MPa) flattens the MEA and removes the anode bending stress but does not alter the cathode or electrolyte stresses.

Stress in the ceramic MEA layers after 'flattening' between interconnects at room temperature






Applying the steady state temperature profile shows that the stress distribution is much less severe than at room temperature.

Electrolyte temperature varies from 744 °C (blue) to 818 °C (red) for operation at 0.7 V

Electrolyte stress varies from -246 MPa (blue) to -201 MPa (red) for operation at 0.7 V





For a given process flow and production volume, assumptions or data must be developed for each process step.


Assumptions

Process Description	Equipment Description	Equipment Cost	Cycle Time (mins)	Reject & Scrap (%)	Number Laborer s per Station	Tool Cost (\$)
Automated Tape Casting	Tape caster	\$300,000	0.0004	0.0%	0.2	
Tile QC Vacuum Leak Test	Inspection Machine	\$300,000	0.17	20.0%	1	
Vacuum Plasma Spray	Vacuum plasma gun	\$1,200,000	1.00	2.0%	0.25	
Screen Print	Manual station	\$00,000	0.02	1.0%	1	\$100
Diamond Grind Stack Edges	Blanchard grinder	300,000	30.00	5.0%	1	\$2,000
IC Progressive Rolling	Yoder M mill	\$130,000	0.00	3.0%	1	\$12,100
IC Shear	Shear + flying die	\$55,000	0.01	2.0%	1	\$15,000
IC joining paint	Paint gun	\$10,000	0.10	0.0%	0.2	
IC joining heat treat	Brazing furnate	\$400,000	180.00	5.0%	0.2	
Stack Calendar	Press + heated dies	\$20,000	0.50	1.0%	1	\$15,000
Roll Calendar	Roll calendar	\$60,000	0.04	1.0%	0.2	
Blanking / Slicing	Press + heated dies	\$150,000	0.17	1.0%	1	\$30,000
Continuous Sinter in Air 12 hrs	Sintering Furnace	\$500,000	720.00	2.0%	0.2	
Weigh Powders	Weigh Scales	\$5,000	30.00	0.0%	0.2	
Ball Milling	Ball Mills	\$22,000	300.00	2.0%	0.2	
Calcine	Calciner	\$90,000	720.00	15.0%	0.2	
Air Classification	Air Classifier	\$100,000	1.00	5.0%	0.2	

The impact of design decisions, e.g. layer thickness, on these assumptions and cost will be assessed.




The cost implications of different process options will be considered.



The major cost drivers for different processing and design scenarios will be compared.

Sensitivity Chart — Target Forecast: Co-Fired Metal Planar Cost





- 1 Technical Issues
- 2 R&D Objectives and Approach
- 3 Activities for Phase I



Phase I will be conducted in three tasks.

Objectives

- Develop architecture of manufacturing model
- Review architecture with SECA stakeholders
- Revise existing model architecture based on Task 1 workshop
- Demonstrate manufacturing model with baseline SOFC system
- Report project progress
- Prepare Phase I report that summarizes critical manufacturing steps and performance parameters
- Define Phase II development effort

Workshop with SECA stakeholders

- Definition of model framework, user interface with model, and critical issues to be assessed, model assumptions
- Workshop with SECA stakeholders
- Monthly updates
- Phase I final report


Deliverables



In Phase I, we will build on an activity-based cost model developed in an earlier NETL program.

Workshop Discussion Issues:

- Protection of individual SECA team proprietary information
- Security of User Interface
- Access to model
- Access to process and equipment data and specifications






We anticipate that we will provide DOE and industrial teams with some key conclusions and recommendations:

- ◆ Identification of critical manufacturing steps and performance parameters
 - if considerable uncertainty exists about these steps, specific additional SECA R&D objectives may be developed
- Refinement of SECA technology cost and performance estimates
- Definition of desirable next steps



We expect Phase I to be completed in approximately nine months, according to the schedule presented below.





Model Framework Workshop



Model Results Workshop



Final Report Briefing



The TIAX core team consists of five members whose backgrounds are particularly appropriate to this project.

Staff	Project Input	Email	Telephone	
Eric Carlson	Case manager	carlson.e@tiax.biz	617-498-5903	
Chandler Fulton	System modeling	fulton.chandler@tiax.biz	617-498-5926	
Suresh Sriramulu	Fuel cell technology	sriramulu.suresh@tiax.biz	617-498-6242	
Graham Stevens	Manufacturing model	stevens.graham@tiax.biz	617-498-6357	
Jan Thijssen	Director in charge	thijssen.j@tiax.biz	617-498-6084	

