

# DOE 2003 SCR/SNCR Workshop

## Full-Scale Catalyst Regeneration Experience At The Coal-Fired Indiantown Generating Plant

**Douglas W. Bullock, P.E.**  
**National Energy Power Co. LLC**  
**Indiantown Generating Plant**

**Hans Hartenstein**  
**SCR-Tech LLC**

# The Indiantown Generating Plant



**Location:** Indiantown, Florida

**Owner:** ICLP – Indiantown  
Cogeneration  
Limited Partnership

**Operator:** National Energy  
Power Company  
LLC

**Capacity:** 360 MW electricity,  
270 t process steam


**Start-up:** 1995

**Boiler:** Bituminous coal,  
PC-wall-fired

**SCR:** 3 layer reactor,  
~ 55% NOx removal  
efficiency


# Catalyst Addition 1995 – 2000

After start-up on the initial catalyst fill of 2 half-layers in summer 1995, additional half-layers of catalyst were installed as soon as the ammonia concentration in the fly ash exceeded acceptable levels. This led to the following schedule of catalyst addition:



# Catalyst Exchange Plan Since 2002

The transition from a former 3 full-layer SCR operating scheme to the new 4 half-layer SCR operating scheme has been started. This schedule calls for the following future catalyst exchange and regeneration cycles:




spring 02

spring 03

fall 03

1<sup>st</sup> future  
exchange

2<sup>nd</sup> future  
exchange

-  initial fill catalyst
-  addition of new catalyst
-  addition/exchange and regeneration of catalyst

# Catalyst Regeneration – Timeline

- Spring 2002:** Removal of catalyst layer 1, 80 full modules after ~ 57,000 operating hours at a  $K/K_0 \sim 0.4$ .  
Replacement by a new half-layer, 80 half-modules.
- Fall 2002:** Decision to regenerate and split the 80 full modules of layer 1 into 160 half-modules.
- January 2003:** Catalyst regeneration and split of modules by SCR-Tech.
- March 2003:** Delivery of 160 fully regenerated half-modules to Indiantown.
- April 2003:** Installation of the first 80 half-modules of regenerated catalyst as the top half-layer.
- October 2003:** Removal of catalyst layer 2, 80 full modules after ~ 60,000 operating hours.  
Installation of the second 80 half-modules of regenerated catalyst as the third half-layer.

# Catalyst Regeneration – Disassembly



**Modules were disassembled in order to split them and remove major accumulations of ash prior to regeneration.**


# Catalyst Regeneration – Popcorn Ash



**Large popcorn ash particles were found between the two layers of plate boxes within the modules.**


**These were mechanically removed prior to catalyst regeneration.**

# Catalyst Regeneration – Results




# Catalyst Regeneration – Results


catalyst surface analysis before and after regeneration



# Catalyst Regeneration – Results




# Catalyst Regeneration – Results



# Catalyst Regeneration – Results

regeneration result of Indiantown catalyst



# Catalyst Regeneration – Results

The catalyst regeneration results can be summarized as:

1. Catalyst was deactivated as expected ( $K/K_0 \sim 0.4$ )
2. Catalyst poisons were successfully removed
3. Catalyst activity after regeneration was  $K_{reg}/K_0 = 1.03$
4. The  $SO_2/SO_3$ -conversion rate decreased significantly after regeneration to almost half of the manufacturer's original  $SO_2/SO_3$ -conversion rate guarantee for the new catalyst in 1995.

**Conclusion:** Catalyst regeneration was very successful.


# Delivery of Regenerated Catalyst



**Delivery of regenerated half-modules in March 2003.**

**Two half-modules were stacked for transportation.**

# Installation of Regenerated Catalyst



Lifting of regenerated half-modules to the top layer of the SCR reactor for installation in April 2003.

# Installation of Regenerated Catalyst



Transport into the SCR reactor via a roller-conveyor.

# Installation of Regenerated Catalyst




**April 2003:  
Placement of  
the regenerated  
half-modules  
on top of the  
half-layer of  
new catalyst,  
which was  
installed in  
spring 2002.**

# Operation of Regenerated Catalyst

- **No difference observed in overall SCR operation using regenerated versus new catalyst.**
- **SCR performance using regenerated catalyst identical compared to using new catalyst.**
- **Activity of regenerated catalyst about the same as new catalyst.**
- **SO<sub>2</sub>/SO<sub>3</sub>-conversion rate of regenerated catalyst lower than new catalyst.**
- **Pressure drop of regenerated catalyst same as new catalyst.**
- **Deactivation of regenerated catalyst same as new catalyst in the same layer of the same SCR reactor burning the same fuel.**

# Deactivation of Regenerated Catalyst

deactivation new versus regenerated catalyst



# Future Catalyst Management Strategy

The original catalyst management strategy was based on a 3 full-layer operation with a perpetual replacement of 1 full-layer as needed by new catalyst and disposal of spent catalyst.

The new catalyst management strategy is based on 4 half-layers installed with a perpetual exchange of 1 half-layer as needed by a regenerated half-layer kept in stand-by at SCR-Tech.

## Advantages:

- Annual savings of over \$ 330,000 in O&M cost
- Reduced SO<sub>3</sub> load in the system
- No catalyst disposal issues

# Conclusions

- **Catalyst regeneration was very successful.**
- **Operating experience with regenerated catalyst is positive. No difference was observed between operating the SCR with new versus regenerated catalyst.**
- **Catalyst deactivation of the regenerated catalyst is identical to the new catalyst in the same layer of the SCR reactor.**
- **Lower SO<sub>2</sub>/SO<sub>3</sub>-conversion benefits the plant's equipment.**
- **O&M cost savings of about \$ 330,000 per year on average by using regeneration over new catalyst replacement (> \$ 5 million over a 20 year period).**
- **Cost & potential future long term hazardous waste liabilities associated with catalyst disposal were avoided.**

# ?? Questions ??

**Douglas W. Bullock, P.E.**  
National Energy & Gas Transmission  
National Energy Power Company LLC  
Indiantown Generating Plant  
P.O. Box 1799  
13303 SW Silver Fox Lane  
Indiantown, Florida 34956  
E-mail: [douglas.bullock@negt.com](mailto:douglas.bullock@negt.com)  
Phone: 772- 597- 6500 Ext. 15  
Fax: 772-597- 6520

**Hans U. Hartenstein,**  
SCR-Tech LLC  
P.O. Box 280  
11701 Mt. Holly Road  
Charlotte, North Carolina 28214  
E-mail: [h.hartenstein@scr-tech.us](mailto:h.hartenstein@scr-tech.us)  
Phone: 704-827-8933  
Fax: 704-827-8933

