

Sixth Annual Conference on Carbon Capture & Sequestration

Steps Toward Deployment

CCS Economic Analyses

Carbon Dioxide Capture from Existing Pulverized Coal Power Plants

Jared Ciferno, NETL

May 7-10, 2007 • Sheraton at Station Square • Pittsburgh, PA



Disclaimer

This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference therein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed therein do not necessarily state or reflect those of the United States Government or any agency thereof.



Overview

Purpose: To perform a thorough engineering and economic analysis helps answer the following questions:


If carbon constraints are mandated in the U.S. then.....

1. Will retrofit of an **existing** pulverized coal plant at some **modest but non-trivial level** of CO₂ removal ever be a worthwhile option to consider?
2. What level of CO₂ recovery is economically optimal?
3. Is there a way to significantly reduce the cost of CO₂ capture for the **existing** fleet?
4. What actions would need to be taken to address **existing** power plants?



Carbon Sequestration From Existing Power Plants Feasibility Study

December 2005—December 2006



Randall Gas Technologies



Study Scope

1. 30%, 50%, 70%, 90% and CO₂ capture levels
2. Employ scrubbing technology advances
3. Detailed steam turbine analysis
4. CO₂ capture and compression heat integration

Location: AEP Conesville Unit #5


- Total 6 units = 2,080 MWe
- Unit #5:
 - Subcritical steam cycle (2400psia/1005°F/1005°F)*
 - Constructed in 1976
 - 463 MW gross (~430 MW net)
 - ESP and Wet lime FGD (95% removal efficiency, 104 ppmv)

Mid-western bituminous coal


Ultimate Analysis (wt.%)	As Rec'd
Moisture	10.1
Carbon	63.2
Hydrogen	4.3
Nitrogen	1.3
Sulfur	2.7
Ash	11.3
Oxygen	7.1
HHV (Btu/lb)	11,293



Existing Plant Modifications




New Equipment Locations Identified



Modified FGD Process

1. Second stage absorber added to achieve 99.7% SO₂ removal efficiency (6.5 ppmv)
2. Includes an SO₂ Credit equal to \$608/ton in the Variable O&M cost



CO₂ Capture Process Key Parameters


Process Paramater	Units	2006	2001	AES Design
Plant Capacity	Ton/Day	9,350-3,120	9,888	200
CO ₂ Recovery	%	90-30	90	96
CO ₂ in Feed	mol %	12.8	13.9	14.7
SO ₂ in Feed	ppmv	10 (Max)	10 (Max)	10 (Max)
Solvent		MEA	MEA	MEA
Solvent Concentration	Wt. %	30	20	17-18
Lean Loading	mol CO ₂ /mol amine	0.19	0.21	0.10
Rich Loading	mol CO ₂ /mol amine	0.49	0.44	0.41
Steam Use	lbs Steam/lb CO ₂	1.67	2.6	3.45
Stripper Feed Temp	°F	205	210	194
Stripper Bottom Temp	°F	247	250	245
Feed Temp to Absorber	°F	115	105	108

Note: Additional data in “notes pages”

- [Reboiler operated at 45 psia—reduced from 65 psia used in 2000 study](#)
- Absorber contains two beds of structured packing




CO₂ Capture Process



Flue Gas Bypass

Bypass method determined to be least costly method to obtain lower CO₂ recovery levels



CO ₂ (Moles/hr)	Case 1 (90%)	Case 2 (70%)	Case 3 (50%)	Case 4 (30%)
FLUE GAS	19,680	19,680	19,680	19,680
BYPASS	0	4,374	8,746	13,120
ABSORBER FEED	19,680	15,306	10,934	6,560
STACK	1,962	5,924	9,846	13,770
CO ₂ PRODUCT	17,720	13,766	9,822	5,906
# Trains	2	2	2	1

CO₂ Capture Compression, Dehydration and Liquefaction

CO₂ compression to 2,015 psia, EOR specifications

Parameter	Wt %	Vol %	ppmv
Carbon Dioxide	96	94.06	940600
C ₂ + and Hydrocarbons	2	2.87	28700
Hydrogen Sulfide	1	1.27	12700
Nitrogen	0.6	0.92	9200
Methane	0.3	0.81	8100
Oxygen	0.03	0.04	400
Mercaptans and Other Sulfides	0.03	0.02	200
Moisture	0.006	0.01	100

Four Stage Process:

Compression ➡ Drying ➡ Refrigeration ➡ Pumping




CO₂ Capture Compression, Dehydration and Liquefaction

1. Compression to 200 Psi

2. Drying to 100 ppmv H₂O

4. Pump to 2,015 Psia



CO₂ Capture Process Equipment

CO₂ sorbent technology improvements leads to significant decrease in equipment requirements and capital cost!


	2006 Study		2001 Study	
CO ₂ Capture Process	No.	ID/Height (ft)	No.	ID/Height (ft)
Absorber	2	34/126	5	27/126
Stripper	2	22/50	9	16/50
Distance from stack	100 ft		1,500 feet	
Heat Exchangers	No.		No.	
Reboilers	10		9	
Stripper CW Cond.	12		9	
Other Heat Exchangers	36		113	
Total Heat Exchangers	58		131	
CO ₂ Compressor	2		7	
Propane Compressor	2		7	
EPC Cost \$MM	276		500	



Steam Turbine Modifications

New Let Down Turbine


Figure 4: Modified Steam Turbine Cycle



Overall Plant Performance


- **Plant Electrical Output**
- **Plant Auxiliary Power**
- **Plant Thermal Efficiency**
- **Plant CO₂ Emissions**

Power Output Distribution




Base load (Net) Output Impact

Losses to Grid




Plant Thermal Efficiency (HHV Basis)



Note: NEW Sub-critical net efficiency (with 90% CO₂ capture) decreases from 36% to 24%




CO₂ Captured



CO₂ Emissions equal to NGCC without CO₂ Capture at ~ 0.8 lb/kWh



CO₂ Avoided Emissions



Economic Assumptions

Dollars (Constant)	2006
Depreciation (Years)	15
Equity (%)	44
Debt (%)	56
Corporate Tax (%)	20
Discount Rate (%)	7.5
Capital Charge Factor (%)	13.5
Coal (\$/MM Btu)	2.11
Capacity Factor (6,307 hr/yr)	72
CO ₂ transport and Storage Costs not included	

Plant Retrofit Capital Costs

EPC Costs (\$1000's)	2001	2006 Study			
% CO ₂ Capture	96	90	70	50	30
CO ₂ Capture & Compression	500,807	275,938	249,822	186,694	134,509
Flue Gas Desulfurization	20,540	20,540	20,540	20,540	20,540
Letdown Steam Turbine	10,516	9,800	9,400	8,900	8,500
Boiler Modifications	0	0	0	0	0
Total Retrofit Costs	531,863	306,278	279,762	216,134	163,549
New Net Output (kW)	251,634	303,317	333,245	362,945	392,067
\$/kW-New Net Output	2,114	1,010	840	596	417
\$/kW-Original Net Output*	1,226	706	645	498	377


*Original net output = 433,778 kW

52% Reduction in Incremental Capital Costs



Note: Capital costs from 2001 study were escalated to 2006 dollars

Economic Results



Mitigation Costs:

\$/Ton CO₂ Removed = \$30 - \$41

\$/Ton CO₂ Avoided = \$46 - \$60

Note:

Economic results from 2001 study were escalated to 2006 dollars
Variable O&M cost includes SO₂ Credit at \$608/ton



Summary & Conclusions

1. No major technical barriers found
2. Compared to the 2001 study, this study with an advanced amine (90% CO₂ Capture case) showed:
 - Marked improvement in energy penalty and reduction in cost
3. No Sweet Spot—near linear decrease in incremental COE with reduced CO₂ capture level
4. Sufficient results to answer various definitions of “optimal CO₂ capture” from existing plants

Thank You!

Email: Jared.Ciferno@netl.doe.gov

Phone: 412-386-5862

NETL Energy Analysis Link:

www.netl.doe.gov/energy-analyses

