



FutureGen 2.0
Oxy-Coal Carbon Capture Plant
with permanent CO₂ Storage


Steve Moorman
Manager -Business Development
Advanced Technology



Solar Receivers



Biomass Systems



Oxy-combustion



Post-Combustion Capture



Project Participants



Power Generation & CO₂ Capture



CO₂ Transport and Storage

Summary of Funding – Oxy combustion large scale test

Project Cost Projection	\$737,000,000
• DOE Cost Share @ 80% =	\$590,000,000
• Non-Government share @ 20% =	\$147,000,000

Project Schedule


<i>Task</i>	<i>Complete</i>
• Cooperative Agreement -	September 2010
• Project Definition / Pre-FEED -	September 2011
• FEED, NEPA, Permitting -	October 2012
• Detail Engineering, Procurement, Construction, Start-up -	April 2016
• Testing -	December 2018

Project Objectives

Prove the Oxy-combustion process at commercial scale

- **Establish a cost and schedule baseline for the technology**
- **Equipment Designs – Primarily Boiler**
 - **Reliability – component design, materials of construction**
 - **Maintainability – erosion, corrosion, outage cycles**
 - **Not designed for high efficiency – designed for flexibility & learning**
 - **Basic process and heat transfer data – can move to high efficiency, larger capacity w/o incremental steps**
- **Process Designs**
 - **Safety, Functionality, Operability**
- **Integrated operation of ASU – Boiler & AQCS – CPU – Storage**
 - **Start-up, Shutdown, Load Swing, Capacity Factor, System Dynamics**

Oxy-combustion Development Path




Small pilot 1.5 MWth



Large pilot 30 MWth




Oxy-coal Combustion Development

- **Multiple Oxy Eng Studies, including ASU / CPU Optimization & Process Heat Integration completed**
- **Small & Large Scale Oxy Pilot testing, completed, Lacq Oxy-Gas & CPU test, Callide CPU test in progress**
- **Reference plant design complete at 680/450 MWe net SCPC**
- **Next step - FutureGen 2.0**




FutureGen 2.0 - 200MWe gross

Oxy-Coal Combustion Principles




Conventional Combustion



Oxy-Coal Combustion

Oxy-Combustion Process




FutureGen 2.0 – Oxy-Combustion Project

Meredosia Plant

- **Meredosia, IL:
Owned/operated by AER**
- **3-coal fired units
(2 retired)**
- **Unit 4, 200 MWe oil-fired
boiler built in 1975
2400 psig 1000 / 1000F
Steam Cycle**
- **3500 TPD CO₂ to Storage**




FG2.0 Oxy-Coal Capture Plant



Not the optimal equipment arrangement for a new plant but the best possible in this case due to site space limitations. Will be a common occurrence with existing plant retrofits and repowerings

Steam & Water Flow Path



Oxy-Combustion Pros

- **Boiler and AQCS equipment utilize conventional designs, materials of construction and arrangements. Combination of equipment and processes that are known to industry users**
- **The oxy system will look and operate like a conventional power plant. Pilot Testing indicated minimal impact to boiler combustion and little change to thermal performance. AQCS performance is unchanged**
 - **Furnace and Heating surface**
 - **Pulverizers**
 - **Burners**
 - **FGD Systems**
 - **Baghouse and ESP**
 - **Basic Process Controls unchanged**

Oxy-Combustion Pros Cont'd

- **Oxy process can utilize a wide variety of coals including lignite, sub-bituminous and bituminous fuels**
- **For retrofit or repowering less complex integration into the existing plant energy balance than PCC**
- **No new chemicals or waste streams introduced into the plant process. Bottom ash, fly ash, FGD waste streams unchanged.**
- **No major change to the plant water balance. For low rank fuels may be a positive water balance from condensation of water from the flue gas stream**

Oxy-Combustion Challenges

- **Cost – CAPEX and OPEX but no different than the other CCS technologies**
- **Auxiliary Power – same here Oxygen making and CO₂ Compression are still energy intensive**
- **Not a partial capture technology – all or nothing**
- **Need to prove the integrated operation of a large scale ASU – Boiler /AQCS – CPU Start-up, Shut-down, Load Swings, Upsets**

FG 2.0 Project Status– Pre-FEED Accomplishments to Date



- Owner's Engineer selected – URS
- Integrated Project Schedule, DOR, WBS, Project Cost Estimate
- Existing Plant Assessment
- Project LCOE model
- Federal and State government affairs, Illinois EPA efforts on-going
- Draft Phase 1 Decision Application in progress



- Boiler / GQCS design and performance
- GA's, plot plans
- Quotes for 85 % of major equipment
- Specifications and bid packages for BOP
- Preliminary P&ID's, PFD's, I&C architecture
- High level construction plan



- ASU and CPU design, GAs, plot plans
- Quotes for 70% of major equipment
- Specifications and bid packages for BOP
- PFDs, Control architecture, interface list
- High level construction plan



“We are passionate about innovation and technology leadership”



Steve Moorman
*Manager -Business Development
Advanced Technology*