

3A.3

Power Systems Development Facility: High Temperature, High Pressure Filter System Operations in a Combustion Gas

Matthew D. Davidson (mddavids@southernco.com; 205-670-5872)

Edwin N. Galloway (engallow@southernco.com; 205-670-5961)

Xiaofeng Guan (xguan@southernco.com; 205-670-5891)

Howard L. Hendrix (hlhendri@southernco.com; 205-670-5876)

Patrick T. Scarborough (ptscarbo@southernco.com; 205-670-5926)

Southern Company Services, Inc.

P.O. Box 1069

Wilsonville, AL 35186

Robert S. Dahlin (rsdahlin@southernco.com; 205-670-5068)

E. Carl Landham (eclandha@southernco.com; 205-670-5990)

Southern Research Institute

P.O. Box 1069

Wilsonville, AL 35186

Jack D. Spain (spain@sri.org; 205-581-2323)

Southern Research Institute

757 Tom Martin Drive

Birmingham, AL 35211

Abstract

The Power Systems Development Facility* (PSDF) is an engineering scale demonstration of two advanced coal-fired power systems and several High-Temperature, High-Pressure gas filtration systems. The PSDF was designed at sufficient scale so that advanced power systems and components could be tested in an integrated fashion to provide confidence and data for commercial scale-up. This paper provides an operations summary of a Westinghouse Particulate Control Device (PCD) filtering combustion gas from a M.W. Kellogg Transport reactor located at the PSDF.

The Transport reactor is an advanced circulating fluidized bed reactor designed to operate as either a combustor or a gasifier. Particulate cleanup is achieved by using one of two PCDs, located downstream of the Transport reactor. As of April 1998, the Transport reactor has operated on coal as a combustor for over 2600 hours. Operationally, the PCD has worked well, with few mechanical problems. To date filter elements from 3M, Blasch, Coors, Dupont, IF&P,

* The PSDF is supported by the U.S. Department of Energy's Federal Energy Technology Center (FETC), under Contract DE-FC21-90MC25140 with Southern Company Services, Inc., P.O. Box 1069, Wilsonville, AL 35186-1069, telefax: 205-670-5843. The FETC Contracting Officer's Representative is James Longanbach.

McDermott, Pall, Schumacher and Specific Surface have been tested up to 1400 °F. Silicon carbide filter elements have been exposed for over 2300 hours on coal with no steady-state failures.

The Southern Research Institute's *in-situ* sampling systems on the PCD inlet and outlet have operated successfully. Isokinetic samples using a batch sampler, a cascade impactor, and a cyclone manifold have provided valuable data to support the operation of the transport reactor and the PCD. Southern Research Institute has also supported the PSDF by conducting filter element materials testing.

Power Systems Development Facility: High Temperature, High Pressure Filter System Operations in a Combustion Gas

Matt Davidson, Edwin Galloway, Xiaofeng Guan, Howard Hendrix, and
Patrick Scarborough
Southern Company Services

Robert S. Dahlin, Carl E. Landham, and Jack D. Spain
Southern Research Institute

PSDF

Power Systems Development Facility



Presentation Outline

- Description of Westinghouse Advanced Particle Filter (APF)
- Combustion operations with the Westinghouse APF
- Filter element testing
- Current and future activities

PSDF

Power Systems Development Facility



Will be updated

M.W. Kellogg Transport Reactor


- Can be operated in either combustion or gasification mode
- Over 3000 hours on coal in combustion mode since start-up in August 1996
- Operated to date on two types of coals and sorbents

PSDF

Power Systems Development Facility



Westinghouse Advanced Particle Filter




- 91 candle filter elements on two plenums
- Top and bottom plenums are back-pulsed separately
- Tangential inlet
- Cylindrical shroud

PSDF

Power Systems Development Facility

Typical Operating Conditions




- Temperature 1375°F
- Pressure 200 psig
- Face velocity 5 ft/min
- Baseline DP 75 inwg
- DP rise 30 inwg
- Pulse pressure 450 psig
- Pulse duration 0.2 sec
- Pulse frequency 40 minutes
- Inlet loading 10,000 ppmw
- Particle MMD 20 micron

PSDF

Power Systems Development Facility

Will be updated

Cumulative Hours on Coal Since Start-up




PSDF

Power Systems Development Facility



Will be updated

Temperature vs. Hours Since Start-up



PSDF

Power Systems Development Facility



General Observations



- No ash bridging has been observed since start-up in 8/96
- Mechanically the filter unit is in good condition

PSDF

Power Systems Development Facility



update

Filter Elements Tested

<u>Manufacturer</u>	<u>Type</u>	<u>Material</u>	<u>Hours on Coal</u>
3M	Oxide	Composite	283+
	Type 203	Composite	1251
Blasch		Alumina/mullite	54
Coors	P-100A-1	Alumina/mullite	810
Dupont	PRD66C	Composite	283+
IF&P	REECER	Recrystallized SiC	283+
McDermott		Composite	283+
Pall	326	SiC	2150+
	442T	SiC	2150+
	FeAl	Iron Aluminide	283+
Schumacher	F40	SiC	616
	TF20	SiC	822+
	T10-20	SiC	1522+
Specific Surface	CC-4001	Cordierite	54

PSDF

Power Systems Development Facility



Filter Element Losses



- Commissioning
- Thermal transients

PSDF

Power Systems Development Facility

Commissioning

- SiC filter elements broken due to
 - Transport reactor particulate carry-over problems
 - inexperience in measuring filter vessel ash level
 - inadvertent coal feed
- No SiC filter elements broken since commissioning

PSDF

Power Systems Development Facility



Thermal Transients


- Oxide-based monolithic filter elements broken due to local combustion on surface of elements during transition to coal
- System temperature prior to coal feed raised to ensure complete combustion in reactor

PSDF

Power Systems Development Facility




Instrumented Filter Elements



PSDF

Power Systems Development Facility

Thermal Gradient Across Filter Element During Transition to Coal



PSDF

Power Systems Development Facility



Monolithic SiC Filter Element Growth Measurements

- The length of 24 monolithic SiC elements measured before and after exposure
- No growth detected after 1000 hours of exposure at 1400°F

PSDF

Power Systems Development Facility



Monolithic Filter Element Strength Testing

- Coors P-100A-1 filter elements tested by SRI
- Ultimate strength of filter elements measured using a hydrostatic O-ring test
- SiC filter element testing ongoing
- Non-destructive testing with Roger Chen of WVU ongoing

PSDF

Power Systems Development Facility



Operational Developments


- Outlet loadings have been consistently demonstrated below 1 ppm
- Ash level in the solids outlet cone of the filter vessel has been reliably monitored using thermocouples
- Pulse valve performance has been characterized and improved

PSDF

Power Systems Development Facility



Back-pulse Valve Testing Results



Current and Future Testing

- Characterize the effects of the back-pulse on the filter system
- Evaluate the effects of higher face velocity
- Evaluate the thermal loads on filter elements
- Characterize the differences in filter cakes generated with different coals and sorbents
- Assess the long-term durability of filter elements

PSDF

Power Systems Development Facility

