

Evaluation of Sorbent Injection for Mercury Control

Quarterly Technical Report
Reporting Period: January 1, 2005–March 31, 2005

Principal Author:
Sharon Sjostrom

ADA-ES, Inc.
8100 SouthPark Way, Unit B
Littleton, Colorado 80120

Submitted: April 29, 2005

DOE Cooperative Agreement No.: DE-FC26-03NT41986

Report No. 41986R06

DISCLAIMER

This technical report was prepared with the support of the U.S. Department of Energy, under Award No. DE-FC26-03NT41986. However, any opinions, findings, conclusions, or recommendations expressed herein are those of the author(s) and do not necessarily reflect the views of the DOE.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ABSTRACT

The power industry in the U.S. is faced with meeting new regulations to reduce the emissions of mercury compounds from coal-fired plants. These regulations are directed at the existing fleet of nearly 1,100 boilers. These plants are relatively old with an average age of over 40 years. Although most of these units are capable of operating for many additional years, there is a desire to minimize large capital expenditures because of the reduced (and unknown) remaining life of the plant to amortize the project. Injecting a sorbent such as powdered activated carbon into the flue gas represents one of the simplest and most mature approaches to controlling mercury emissions from coal-fired boilers.

The overall objective of the test program described in this quarterly report is to evaluate the capabilities of activated carbon injection at five plants with configurations that together represent 78% of the existing coal-fired generation plants. This technology was successfully evaluated in NETL's Phase I tests at scales up to 150 MW, on plants burning subbituminous and bituminous coals and with ESPs and fabric filters. The tests also identified issues that still need to be addressed, such as evaluating performance on other configurations, optimizing sorbent usage (costs), and gathering longer-term operating data to address concerns about the impact of activated carbon on plant equipment and operations. The four sites identified for testing are Sunflower Electric's Holcomb Station, AmerenUE's Meramec Station, AEP's Conesville Station, and Detroit Edison's Monroe Power Plant. In addition to tests identified for the four main sites, parametric testing at Missouri Basin Power Project's Laramie River Station Unit 3 was made possible through additional cost-share participation targeted by team members specifically for tests at Holcomb or a similar plant.

This is the sixth quarterly report for this project. Parametric testing at Laramie River Station was completed during this reporting period. Preliminary results from these tests are included in this report. Planning information for the other three sites is also included. In general, quarterly reports will be used to provide project overviews, project status, and technology transfer information. Topical reports will be prepared for each test site and these will include detailed technical information.

TABLE OF CONTENTS

| | |
|--|-----------|
| INTRODUCTION..... | 1 |
| EXECUTIVE SUMMARY | 3 |
| EXPERIMENTAL..... | 5 |
| Task 1. Design and Fabrication of Sorbent Injection System..... | 5 |
| Task 2. Site-Specific Activities Including Field-Testing..... | 5 |
| Subtask 2.1. Host Site Planning and Coordination..... | 7 |
| Subtask 2.2. Design, Fabricate, and Install Equipment | 7 |
| Subtask 2.3. Field-Testing | 8 |
| Subtask 2.4. Data Analysis | 10 |
| Subtask 2.5. Coal and Byproduct Evaluation | 10 |
| Subtask 2.6. Economic Analysis | 10 |
| Subtask 2.7. Site Report | 10 |
| Task 3. Technology Transfer | 10 |
| Task 4. Program Management and Reporting..... | 10 |
| RESULTS AND DISCUSSION | 14 |
| Task 1. Design and Fabrication of Sorbent Injection System..... | 14 |
| Task 2. Site-Specific Activities Including Field-Testing..... | 14 |
| Subtask 2.3. Field-Testing | 14 |
| Subtask 2.4. Data Analysis | 19 |
| Subtask 2.5. Coal and Byproduct Evaluation | 19 |
| CONCLUSIONS | 20 |

LIST OF TABLES

| | |
|--|-----------|
| Table 1. Host Site Key Descriptive Information. | 2 |
| Table 2. Host Sites Participating in the Sorbent Injection Demonstration Project..... | 3 |
| Table 3. Task 2 Subtasks (to be repeated at each test site). | 5 |
| Table 4. Descriptions of Screened Sorbents. | 8 |
| Table 5. Project Schedule and Milestones. | 11 |
| Table 6. Field-Testing Schedule..... | 13 |
| Table 7. Sorbent Screening Test Results from Meramec..... | 15 |

LIST OF FIGURES

| | |
|--|-----------|
| Figure 1. Sketch of Flue Gas Flow from APH to Stack (LRS3) | 6 |
| Figure 2. Summary of DARCO Hg Results on Cold-Side ESPs..... | 17 |
| Figure 3. Results from Sorbent Injection Tests at Laramie River. | 17 |
| Figure 4. Mercury Speciation Results during KNX Testing..... | 18 |
| Figure 5. Impact of Coal Additive on DARCO Hg Performance..... | 19 |

INTRODUCTION

The overall objective of this test program is to evaluate the capabilities of activated carbon injection at four plants with configurations that together represent 78% of the existing coal-fired generation plants. Activated carbon injection was successfully evaluated in NETL's Phase I tests at scales up to 150 MW, on plants burning subbituminous and bituminous coals and with ESPs and fabric filters. The tests also identified issues that still need to be addressed, such as evaluating performance on other configurations, optimizing sorbent usage (costs), and gathering longer-term operating data to address concerns about the impact of activated carbon on plant equipment and operations. A summary of the key descriptive parameters for the host sites can be found in Table 1. Laramie River Station was added as the fifth site in the program during 4Q04.

The technical approach that is being followed during this program allows the team to: 1) effectively evaluate activated carbon and other viable sorbents on a variety of coals and plant configurations, and 2) perform long-term testing at the optimum condition for at least one month. These technical objectives will be accomplished by following a series of technical tasks:

- Task 1. Design and Fabrication of Sorbent Injection System

- Task 2. Site-Specific Activities including Field-Testing

- Task 3. Technology Transfer

- Task 4. Program Management and Reporting

Tasks 1, 3, and 4 are intended to support the overall direction, implementation, technology transfer, and management of the program. Task 2 will be repeated for each test site with subtasks designed to address the specific configurations, needs, and challenges of that site. Task 2 is the heart of the program and contains subtasks to address each important component of the testing. A summary of the Field-Testing subtasks (Task 2) is presented in Table 3.

Table 1. Host Site Key Descriptive Information.

| | Holcomb | Meramec | Laramie River | Monroe | Conesville |
|--|---------------------------------|-------------------------|----------------------|-----------------|--------------------------|
| Test Period | 3/04–8/04 | 8/04–11/04 | 2/05–3/05 | 3/05–6/05 | 2/06–5/06 |
| Unit | 1 | 1 or 2 | 3 | 4 | 5 or 6 |
| Size (MW) | 360 | 140 | 550 | 785 | 400 |
| Coal | PRB | PRB | PRB | PRB/Bit blend | Bituminous |
| Particulate Control | Joy Western Fabric Filter | American Air Filter ESP | ESP | ESP | Research-Cottrell ESP |
| SCA (ft ² /kacfm) | NA | 320 | 599 | 258 | 301 |
| Sulfur Control | Spray Dryer Niro Joy Western | Compliance Coal | Spray Dryer | Compliance Coal | Wet Lime FGD |
| Ash Reuse | Disposal | Sold for concrete | Disposal | Disposal | FGD Sludge Stabilization |
| Test Portion (MWe) | 180 and 360 | 70 | 140 | 196 | 400 |
| Typical Inlet Mercury (µg/dNm ³) | 10–12 | 10–12 | 10–12 | 8–10 | 15–20 |
| Typical Native Mercury Removal | 0–13% | 15–30% | <20% | 10–30% | 50% |

A detailed topical report will be prepared for tests conducted at each test site. Quarterly reports will be used to provide project overviews, status, and technology transfer information.

EXECUTIVE SUMMARY

This five-site project is part of an overall program funded by the Department of Energy's National Energy Technology Laboratory (NETL) and industry partners to obtain the necessary information to assess the feasibility and costs of controlling mercury from coal-fired utility plants. Host sites that will be tested as part of this program are shown in Tables 1 and 2. These host sites reflect a combination of coals and existing air pollution control configurations representing 78% of existing coal-fired generating plants and, potentially, a significant portion of new plants. These host sites will allow documentation of sorbent performance on the following configurations:

Table 2. Host Sites Participating in the Sorbent Injection Demonstration Project.

| | Coal / Options | APC | Capacity MW / Test Portion | Current Hg Removal (%) |
|---|------------------|---------------------|----------------------------|------------------------|
| Sunflower Electric's Holcomb Station | PRB and Blend | SDA – Fabric Filter | 360 / 180 and 360 / 360 | <15 |
| AmerenUE's Meramec Station | PRB | ESP | 140 / 70 | 15–30 |
| American Electric Power's (AEP) Conesville Station | Bituminous Blend | ESP + Wet FGD | 400 / 400 | 50 |
| Detroit Edison's Monroe Power Plant | PRB/Bit Blend | SCR + ESP | 785/196 | 10-30 |
| Missouri Basin Power Project's Laramie River Station | PRB | SDA – ESP | 550/140 | <20 |

During the sixth reporting quarter, January through March 2005, progress on the project was made in the following areas:

Sunflower Electric Power Corporation, Holcomb Station

- Holcomb Draft Topical Report completed and in review process
- Presented results at Electric Power Conference and the Institute of Clean Air Companies (ICAC) Conference

AmerenUE, Meramec

- Ongoing sample and data analysis
- Completed Economic Analysis
- Preparing Meramec Draft Topical Report
- Presented results at Electric Power Conference and the Institute of Clean Air Companies (ICAC) Conference

MBPP, Laramie River Station

- Completed testing
- Ongoing sample and data analysis
- Preparing Laramie River Draft Topical Report

Detroit Edison, Monroe

- Completed installation activities
- Completed baseline (SCR Off) tests
- Started SCR Off parametric testing

AEP, Conesville

- Working with AEP to finalize location of sampling ports, silo, etc.
- Working with AEP and REI for flow modeling

EXPERIMENTAL

The overall objective of this test program is to evaluate the capabilities of activated carbon injection at five plants with configurations that together represent 78% of the existing coal-fired generation plants. ADA-ES and the project team will evaluate activated carbon and other viable sorbents on a variety of coals and plant configurations, and perform long-term testing at the optimum condition for up to six weeks. The technical approach is outlined in a series of four technical tasks.

Task 1. Design and Fabrication of Sorbent Injection System

ADA-ES, the primary test contractor, will provide the majority of the process equipment that will travel from site to site. This equipment is sized and designed to cover the expected range of plant sizes (70–500 MW) and flue gas conditions, and has the flexibility for both baghouse and ESP applications.

Task 2. Site-Specific Activities Including Field-Testing

This task has seven subtasks that will be repeated for the four host sites. A summary of these subtasks is presented in Table 3. The five sites identified for testing are Sunflower Electric's Holcomb Station, AmerenUE's Meramec Station, Missouri Basin Power Project's Laramie River Station, Detroit Edison's Monroe Power Plant, and AEP's Conesville Station. Testing at Laramie River Station was limited to baseline and a short-term series of parametric tests. Testing during this quarter was conducted at Laramie River and Monroe Stations. Descriptions of Holcomb and Meramec were included in a previous quarterly report. A description of Laramie River Station is included in this report. Descriptions of Monroe Power Plant and Conesville Station will be included when results are presented.

Table 3. Task 2 Subtasks (to be repeated at each test site).

| Subtask | Description |
|---------|---|
| 2.1 | Host site kickoff meeting, Test Plan, and QA/QC plan |
| 2.2 | Design and install site-specific equipment |
| 2.3 | Field-tests |
| 2.3.1 | Sorbent selection |
| 2.3.2 | Sample and data coordination |
| 2.3.3 | Baseline tests |
| 2.3.4 | Parametric tests |
| 2.3.5 | Long-term tests <i>(no long-term tests conducted at Laramie River)</i> |
| 2.4 | Data analysis |
| 2.5 | Sample evaluation |
| 2.6 | Economic analysis |
| 2.7 | Site report |

Missouri Basin Power Project's Laramie River Station

Missouri Basin Power Project's Laramie River Station, located near Wheatland, Wyoming, is one of the largest consumer-operated, regional, joint power supply ventures in the United States. Laramie River Station, which is operated by Basin Electric's Power Cooperation, has three units, each with 550 MW of generating capacity. The test unit (Unit 3) utilizes an SDA + ESP for their air pollution control. For sorbent injection testing with injection upstream of the SDA, only one-quarter of the 550-MW flue gas stream was treated, nominally 138 MW. A sketch showing flue gas flow from the air preheater (APH) to the stack on Unit 3 is shown in Figure 1. Key operating parameters for Laramie River Unit 3 are included in Table 1.




Figure 1. Sketch of Flue Gas Flow from APH to Stack (LRS3)

Subtask 2.1. Host Site Planning and Coordination

Efforts within this subtask include planning the site-specific tests with the host site utility, DOE/NETL, and contributing team members. The planning process includes meeting with plant personnel, corporate, and environmental personnel to discuss and agree upon the overall scope of the program, the potential impact on plant equipment and operation, and to gather preliminary information necessary to develop a detailed draft Test Plan and scope of work. Efforts include identifying any permit requirements, developing a quality assurance/quality control plan, finalizing the site-specific scope for each of the team members, and putting subcontracts in place for manual flue gas measurements, including Ontario Hydro mercury measurement services.

Field-testing was completed at Laramie River during this reporting period and testing is underway at Monroe. Although testing at Conesville has been delayed until spring 2006, planning activities are underway. Specific planning activities during this reporting period are listed below.

- ADA-ES personnel worked with Laramie River, Monroe, and Conesville personnel to identify site-specific requirements.
- Site specific test plans and plant procurement documents were developed and presented to the plant during the site kickoff meetings
 - January 11, 2005, Monroe Power Plant
 - January 20, 2005, Laramie River Station
 - March 1, 2005, Conesville
- Installation activities were completed at Laramie River Station and Monroe Power Plant

Subtask 2.2. Design, Fabricate, and Install Equipment

During this subtask, equipment will be identified, designed, fabricated when necessary, and installed at the host site. Some components are site-specific such as the sorbent distribution manifold and sorbent injectors (if possible, these components will be reused at multiple sites). This equipment must be sized, designed, and fabricated for the specific plant arrangements and ductwork configurations. Required site support includes installation of the injection and sampling ports (if not available), installation of required platforms and scaffolding, compressed air, electrical power, wiring plant signals including boiler load to the injection skid and control trailer, and the balance of plant engineering. The host utility will be responsible for all permitting and any variance requirements.

Subtask 2.3. Field-Testing

Field-tests are accomplished through a series of five (5) steps. A summary of these steps is presented below.

2.3.1 Sorbent Selection

A key component of the planning process for these evaluations is identifying potential sorbents for testing. To assist in the sorbent selection process, a sorbent screening device (SSD) designed by ADA-ES may be used at the site to compare the performance of candidate sorbents. A description of the device was included in the 2Q04 quarterly report. In support of upcoming tests at Laramie River and Monroe, a short series of sorbent screening tests was also conducted at Meramec during the last reporting period (4Q04).

In an effort to advance the state of the art, ADA-ES invited sorbent developers and manufacturers to provide material designed for effective mercury removal in PRB flue gas for screening at Meramec regardless of the availability of the material in large quantities. Ten sorbents from seven manufacturers were evaluated at Meramec. Short descriptions of these sorbents are included in Table 4.

Table 4. Descriptions of Screened Sorbents.

| Sorbent | Manufacturer | Description |
|-----------------|--|--|
| DARCO Hg | NORIT Americas | Lignite activated carbon |
| DARCO Hg-LH | NORIT Americas | Bromine treated, lignite activated carbon |
| DARCO Hg-LH Low | NORIT Americas | Bromine treated, lignite activated carbon |
| PACarb FGC | Cal-Pacific Carbon | Blend of bituminous coal and coconut-based activated carbon. |
| 39.MK-2 | Northeastern Energies & Environmental Technologies, Ltd. | Non-carbon, mineral-based sorbent treated with halides |
| BGHHM | Calgon Carbon, Inc. | Wood-based activated carbon |
| ZN-01 | Zinkan Enterprises, Inc. | Non-carbon-based zeolite-based sorbent, treated with halides |
| Nano1&2 | NanoScale Materials Inc. | Carbon Nano tubes |
| CDEM | CDEM Holland BV | Non-carbon-based sorbent |

2.3.2 Sample and Data Coordination

ADA-ES engineers coordinate with plant personnel to retrieve the necessary plant operating data files and determine appropriate samples to collect during baseline, parametric, and long-term testing periods. Samples are collected based upon a Sample and Data Management Plan developed for the sites. An example of the sampling schedule for Meramec and additional descriptions of the sample management protocol were included in the 2Q04 quarterly report.

2.3.3 Baseline Testing

Baseline mercury measurements, consisting of Ontario Hydro testing in conjunction with SCEM measurement, are typically made at each site for at least one week prior to beginning parametric mercury control tests. Baseline measurements were conducted at Holcomb, Meramec, and Monroe, and are planned for Conesville. During testing at Laramie River Station, sorbent traps were used for comparison tests with the SCEMs. Additional tests, such as EPA M26a or EPA M29 measurements have also been conducted at Holcomb, Meramec, and Monroe, and are planned for Conesville.

2.3.4 Parametric Testing

A series of parametric tests is conducted at each site to determine the optimum operating conditions for several levels of mercury control. Evaluations of NORIT's DARCO Hg and other sorbents chosen by the test team are typically included. Additional tests, such as coal blending or the introduction of additives onto the coal, may also be included. A summary of parametric tests conducted or planned at each site is shown below.

Sorbent Injection

(descriptions of most sorbents tested are included in the previous quarterly reports)

- DARCO Hg (formerly known as FGD): All sites
- DARCO Hg-LH (formerly known as FGD-E3): Holcomb, Meramec, Laramie River, Monroe
- Calgon 208CP: Holcomb
- NORIT XTR: Low-activity, lignite-based activated carbon
- NEST PHg-1: Non-carbon-based material from Northeastern Energy and Environmental Technologies; chosen based on positive results from tests at Meramec.
- Sorbent(s) to be finalized: Conesville

Coal Blending

- PRB and Western Bituminous: Holcomb, Laramie River
- PRB and Eastern Bituminous: Monroe

Coal Additives

- ALSTOM's KNX: Holcomb, Meramec, Laramie River
- EERC's SEA2: Meramec (conducted with AmerenUE funds)

2.3.5 Long-Term Testing

Thirty-day "long-term" testing has been completed at Holcomb and Meramec and is planned for Monroe and Conesville. The sorbents used during the long-term test period are chosen by the test team based upon performance during parametric testing and a review of the material costs and availability. The goal of the 30-day test phase is to obtain operational data on mercury removal efficiency, the effects on the particulate control device, effects on byproducts and impacts to the balance of plant equipment, to prove viability of the process, and determine the economics. During these tests, Ontario Hydro measurements are conducted at the inlet and outlet of the particulate control device at least once.

Subtask 2.4. Data Analysis

Data collection and analysis for this program are designed to measure the effect of sorbent injection on mercury control and the impact on the existing pollution control equipment. The mercury levels and plant operation are characterized without sorbent injection, during coal blending or coal additive testing and with various injection rates and possible combustion modifications, as defined by the final Site Test Plan.

Subtask 2.5. Coal and Byproduct Evaluation

Coal and combustion byproduct samples collected throughout the program are analyzed in this task. During all field test phases, samples of coal and fly ash are collected. At a minimum, ultimate and proximate analyses will be performed and mercury, chlorine, and sulfur levels will be determined in a representative set of the coal samples. Activated carbon injection will result in the fly ash and scrubber materials being mixed with a certain amount of the mercury-containing sorbent. The ash samples will be analyzed at a minimum for mercury and LOI. It is expected that more than 100 samples will be collected at each site. A subset of these samples will be analyzed.

Subtask 2.6. Economic Analysis

After completion of testing and analysis of the data at each plant, the requirements and costs for full-scale permanent commercial implementation of the selected mercury control technology will be determined. The program team will meet with the host utility plant and engineering personnel to develop plant-specific design criteria. Process equipment will be sized and designed based on test results and the plant-specific requirements (reagent storage capacity, plant arrangement, retrofit issues, winterization, controls interface, etc.). A conceptual design document will be developed. Finally, a budget cost estimate will be developed to implement the control technology.

Subtask 2.7. Site Report

A site report will be prepared documenting measurements, test procedures, analyses, and results obtained in Task 2. This report is intended to be a stand-alone document providing a comprehensive review of the testing that will be submitted to the host utility.

Task 3. Technology Transfer

Technology transfer activities include participation in DOE/NETL-sponsored meetings, presentations at conferences, and publication of technical papers. A paper is planned for the DOE Contractors Review meeting in July 2005.

Task 4. Program Management and Reporting

The final task provides time for overall program management and time to complete DOE's reporting requirements. This task will also support periodic meetings with DOE to discuss progress and obtain overall direction of the program from the DOE project manager. In addition to the standard financial and technical reports, additional deliverables will include topical reports for each site tested. The Project Schedule and Milestones are presented in Table 5.

Table 5. Project Schedule and Milestones.

| Activity | Target Date | Actual Date |
|---|-------------|-------------|
| Holcomb | | |
| Site Kickoff Meeting | 12/16/03 | 12/16/03 |
| Complete Sorbent Screening Tests | 3/4/04 | 3/2/04 |
| Complete Equipment Installation | 5/21/04 | 4/21/04 |
| Complete Baseline Testing | 5/21/04 | 5/20/04 |
| Initiate Parametric Testing | 5/24/04 | 5/22/04 |
| Complete Parametric Testing | 6/11/04 | 6/11/04 |
| Initiate Long-Term Testing | 7/7/04 | 7/7/04 |
| Complete Team Meeting and Site Tour | 7/21/04 | 7/21/04 |
| Complete Long-Term Test | 8/6/04 | 8/6/04 |
| Complete Economic Analysis | 5/31/05 | 2/28/05 |
| Complete Byproduct Analysis Evaluations | 5/31/05 | |
| Complete Site Report | 6/30/05 | |
| Meramec | | |
| Site Kickoff Meeting | 4/20/04 | 4/20/04 |
| Complete Pre-Baseline Testing | 6/25/04 | 6/23/04 |
| Complete Sorbent Screening Tests | 10/18/04 | 10/08/04 |
| Complete Equipment Installation | 9/5/04 | 8/23/04 |
| Complete Baseline Testing | 9/5/04 | 8/27/04 |
| Initiate Parametric Testing | 9/6/04 | 8/30/04 |
| Complete Parametric Testing | 10/17/04 | 9/27/04 |
| Complete Team Meeting and Site Tour | 12/17/04 | 10/27/04 |
| Initiate Long-Term Testing | 10/18/04 | 10/14/04 |
| Complete Long-Term Test | 12/17/04 | 11/17/04 |
| Complete Economic Analysis | 8/31/05 | |
| Complete Byproduct Analysis Evaluations | 8/31/05 | |
| Complete Site Report | 9/30/05 | |
| Laramie River | | |
| Site Kickoff Meeting | 1Q05 | 1/20/05 |
| Initiate Field-Testing | 2Q05 | 2/21/05 |
| Complete Field-Testing | 2Q05 | 3/8/05 |
| Monroe | | |
| Site Kickoff Meeting | 4Q04 | 1/11/05 |
| Initiate Field-Testing | 3Q05 | 3/22/05 |
| Complete Field-Testing | 4Q05 | |
| Conesville | | |
| Site Kickoff Meeting | 2Q05 | 3/1/05 |
| Initiate Field-Testing | 1Q06 | |
| Complete Field-Testing | 1Q06 | |

There are more than 100 individual team members from 27 organizations participating in this program. Current project co-funding is provided by:

- ADA-ES, Inc.
- ALSTOM
- AmerenUE*
- American Electric Power*
- Arch Coal
- Detroit Edison*
- Dynegy Generation
- EPRI
- Kennecott Coal
- MidAmerican
- NORIT Americas
- Ontario Power Generation and partners
 - EPCOR
 - Babcock & Wilcox
- Peabody Coal
- Southern Company
- Sunflower Electric Power Corporation* and partners
 - Associated Electric Coop
 - City of Sikeston
 - Empire District Electric Company
 - Kansas City Board of Public Utilities (KCKBPU)
 - Kansas City Power and Light
 - Missouri Basin Power Project*
 - Nebraska Public Power District
 - PacifiCorp
 - Southern Minnesota Municipal Power Agency
 - Tri-State Generation & Transmission
 - TransAlta Utilities
 - TransAlta Energy.
 - Westar Energy
 - Western Fuels Association
 - Wisconsin Public Service
- Tennessee Valley Authority

* indicates host site

Key members of the test team include:

- ADA-ES, Inc.
- ALSTOM
- EPRI
- NORIT Americas
- Reaction Engineering International
- Tetra Tech, Inc.
- Others
 - Stack test firms
 - Analytical laboratories

To facilitate information sharing, a project Web site is maintained for the project. The project Web site is password protected and available only to project participants. Information available through the Web site includes all presentations, papers, reports, planning documents, schedules, and other information related to the project.

A schedule showing field-tests planned and completed at each test site is shown in Table 6.

Table 6. Field-Testing Schedule.

| | 2004 | | | | 2005 | | | | | |
|--------------------------|------|-----|-----|-----|------|-----|-----|-----|-----|-----|
| Site | May | Jul | Sep | Nov | Jan | Mar | May | Jul | Sep | Nov |
| Holcomb | | | | | | | | | | |
| Meramec | | | | | | | | | | |
| Laramie River | | | | | | | | | | |
| Monroe | | | | | | | | | | |
| Conesville Spring '06 | | | | | | | | | | |

RESULTS AND DISCUSSION

Task 1. Design and Fabrication of Sorbent Injection System

Design and fabrication of the sorbent injection system was completed for Laramie River Station and Monroe Power Plant during the second reporting period—January through March 2004.

Task 2. Site-Specific Activities Including Field-Testing

Baseline and parametric testing was completed at Laramie River Station and baseline parametric tests were completed at Monroe during the sixth reporting period—January through March 2005. Results from testing at Laramie River are included under this task heading. Key activities at other sites are also presented.

Subtask 2.3. Field-Testing

2.3.1 Sorbent Selection – Meramec

In support of upcoming tests at Laramie River and Monroe, a short series of sorbent screening tests was conducted at Meramec during the last reporting period (4Q04). Tests were conducted to evaluate the mercury removal performance of various sorbents under operating conditions designed to predict the performance of the sorbents when injected into a full-scale ESP. This test utilized the sorbent screening device described in the 2Q04 quarterly report. The sorbent screening tests were conducted October 4–8, 2004.

The DARCO Hg and DARCO Hg-LH sorbents were used as the benchmark sorbents since they were also tested full-scale at the Meramec Station prior to the screening tests. The best performance was obtained with the DARCO Hg-LH, closely followed by sorbent A. Sorbent B also showed significant mercury capture at 76%. The best non-carbon sorbent was sorbent C, which captured 47% of the mercury at a loading of 6 lb/MMacf. These results are included in the test summary on Table 7.

Table 7. Sorbent Screening Test Results from Meramec.

| Sorbent | Equivalent Loading (lb/MMacf) | Average Hg Removal % |
|----------------|----------------------------------|-------------------------|
| DARCO Hg | 1 | 67 |
| DARCO Hg-LH | 1 | 90 |
| A ¹ | 1 | 89 |
| B ¹ | 1 | 76 |
| C ² | 6 | 47 |
| D ¹ | 1 | 31 |
| E ² | 6 | 19 |
| F ² | 6 | 9 |

¹ Carbon-based sorbent

² Non-carbon-based sorbent

2.3.2 Sample and Data Coordination

Data analysis, coal, and byproduct evaluation is ongoing for all sites where field-testing was conducted. Details will be included in the site reports.

2.3.3 Baseline Testing – Laramie River Station

Field-testing at Laramie River Station began February 24, 2005. Baseline mercury measurements were made during the first two days of testing. During this period, Unit 3 was held steady at full-load conditions firing 100% PRB coal. The average vapor-phase mercury (Hg) removal efficiency was approximately 12%. Average total mercury concentrations at the inlet to the spray dryer and the outlet of the ESP were 9.9 and 8.7 µg/Nm³ respectively. The vapor-phase mercury was >90% elemental mercury at both the inlet of the SDA and the outlet of the ESP. The average particulate mercury concentration at the SDA inlet during baseline testing was low at 0.3 µg/Nm³. To measure the particulate fraction of mercury at the SDA inlet, an in-situ particulate sample was collected just upstream of the Unit 3 “B” Reactor. The particulate sample was analyzed for mercury content, and the particulate-phase fraction of mercury present at the inlet to the SDA was calculated.

2.3.4 Parametric Testing – Laramie River Station

Following the baseline test period, a series of parametric tests were conducted to evaluate various Hg control technologies. The parametric tests were conducted at full-load conditions to document performance of coal blending, sorbent injection, and coal additive addition (with and without ACI) for control of mercury in stack emissions. This task was completed at Laramie River Station during the sixth reporting period and preliminary results are included in this quarterly report.

Coal Blending

During the coal blending tests, two types of western bituminous coals were evaluated. The plant typically fires 100% PRB coal; however, during the coal blend tests, a blend of approximately 80% PRB and 20% western bituminous was used.

Western Bituminous Blend 1

The first western bituminous coal was tested at two different blend ratios: 80/20 and 75/25. While testing at the 80/20 ratio, the average total vapor-phase mercury concentrations at the SDA inlet and ESP outlet were 9.2 and 9.3 $\mu\text{g}/\text{Nm}^3$ respectively. Mercury speciation at both locations was consistent with baseline measurements, where approximately 2% of the vapor-phase mercury at the SDA inlet and 8% at the ESP outlet was oxidized.

Coal samples were collected at the mine and sent to ADA-ES. A composite sample was sent to an outside lab for analysis. Results from the coal analyses will be included in the Topical Report.

Immediately following the 80/20 blend test, the amount of western bituminous coal added to the Unit 3 boiler was increased to 25%. Average vapor-phase mercury concentrations at the SDA inlet and ESP outlet for this blend were 8.6 and 8.2 $\mu\text{g}/\text{Nm}^3$ respectively. During both blends, total vapor-phase mercury removal was less than 10%.

Western Bituminous Blend 2

On March 7, a second coal blend test was conducted with a different western bituminous coal, at a coal blend ratio of approximately 84% PRB and 16% western bituminous. The new western bituminous coal appeared to enter the boiler around 7:00 a.m. on March 7. During this transition, total coal flow into the boiler decreased while the gross generation increased. This is likely due to the higher heating value of the western bituminous coal.

Coal samples were collected at the mine and sent to ADA-ES. A composite sample was sent to an outside lab for analysis and to help calculate an expected coal quality for the blended coal. Results from the coal analyses will be included in the Topical Report.

A few hours prior to the second coal blend test, the total vapor-phase mercury removal across the system was approximately 22%. This is higher than during baseline testing and may be attributed to the residual effects of sorbent injection conducted before the coal blending tests. During coal blend tests, total vapor-phase mercury removal efficiency increased up to 30%, indicating a slight improvement in mercury removal with coal blending.

Sorbent Injection Testing

Sorbent injection tests began on February 28, 2005. Two sorbents were evaluated at Laramie River: the non-treated benchmark sorbent, DARCO Hg, and the bromine-treated sorbent, DARCO Hg-LH.

The vapor-phase mercury removal efficiency with DARCO Hg appeared to be limited to nominally 50% at injection concentrations up to 6.2 lb/MMacf. Data from other cold-side ESP sites burning low-rank coals (PRB or North Dakota lignite) also show limitations in mercury capture when injecting DARCO Hg, as shown in Figure 2. Halogens, such as HCl, must be present for effective mercury capture by untreated activated carbon. It is speculated that activated carbon injection rates of 3 to 10 lb/MMacf are sufficient to absorb the available halogens so that subsequent increases in injection rates are ineffective.




Figure 2. Summary of DARCO Hg Results on Cold-Side ESPs.

When the halogen concentration in the flue gas is low, an activated carbon treated with a halogen can be used for higher mercury capture. When DARCO Hg-LH sorbent was injected upstream of the SDA, 79% mercury removal was achieved at an injection concentration of 2.7 lb/MMacf, and 92% removal was achieved at 4.5 lb/MMacf. The results of DARCO Hg and DARCO Hg-LH sorbent injection are presented in Figure 3.




Figure 3. Results from Sorbent Injection Tests at Laramie River.

The in-situ fly ash sampler was used to evaluate in-flight mercury capture (by measuring mercury that ended up in the particulate phase). At baseline conditions, (no sorbent injection) the particulate-phase mercury was found to be less than 10% of the total mercury present at the inlet of the SDA. At sorbent injection concentrations of up to 6.3 lb/MMacf, a

vapor-phase mercury removal rate of up to 40% was measured for DARCO Hg and DARCO Hg-LH.

Coal Additive Testing

Another option for introducing halogens into the flue gas stream is to treat the coal before it enters the boiler rather than injecting treated carbons. The coal additive tested was KNX, a proprietary mercury control technology from ALSTOM Power.

Unit 3 is equipped with a wall-fired boiler fed by seven coal feeders. KNX was applied to the coal at feeders 3B and 3C, which supply the lower burner elevations on each side of the boiler. At this chemical injection location, the treated coal reached the burner within seconds. The KNX additive was applied to the coal at injection rates up to 2.7 gph.

Prior to the start of KNX testing, the fraction of oxidized mercury at the SDA inlet was 2.4%. Injecting the KNX additive onto the coal at a rate of 0.7 gph resulted in a 2% increase in oxidized mercury at the SDA inlet. It should be noted that due to the pump's flow capacity, chemical flow less than 1 gph was unsteady and may have slightly deviated from the target set point. Increasing the KNX flow rate to 2.7 gph resulted in a 14% increase in speciation from baseline levels at the SDA inlet. Mercury speciation data from KNX testing are presented in Figure 4.




Figure 4. Mercury Speciation Results during KNX Testing.

Although the fraction of oxidized mercury at the inlet of the SDA increased, mercury removal across the system was limited to less than 20%, and the fraction of oxidized mercury at the outlet of the ESP was lower than at the SDA inlet. These data suggest that either the KNX addition resulted in a sampling artifact that biased the elemental mercury measurement at the SDA inlet, or the SDA-ESP configuration was reducing oxidized mercury back to the

elemental form. This same phenomenon has been seen on other PRB/SDA units during KNX testing.

The final day of KNX testing included the injection of the DARCO Hg sorbent at the SDA inlet at 4.5 lb/MMacf in conjunction with KNX addition at 1.6 gph. The resulting total mercury capture across the system was 94% compared to 50% with DARCO Hg alone (no KNX). These data, shown in Figure 5, clearly indicate the improved performance of DARCO Hg when halogens are added to the flue gas stream.




Figure 5. Impact of Coal Additive on DARCO Hg Performance.

2.3.5 Long-Term Testing

No long-term tests were conducted at Laramie River Station.

Subtask 2.4. Data Analysis

Data collected from Meramec Station, Laramie River Station, and Monroe Power Plant are currently being reviewed.

Subtask 2.5. Coal and Byproduct Evaluation

Hundreds of samples are typically collected from each test site. Most of the ash samples, several coal samples, and at least one of all other sample types will be analyzed for mercury. Additional analyses, including coal ultimate and proximate analyses, and coal and ash chlorine analyses, are being conducted. Results from these tests are being reviewed and will be summarized in the Topical Report for the site.

CONCLUSIONS

Field-testing has been completed at Holcomb, Meramec, and Laramie River Station. Preliminary results from Laramie River tests were reported in this quarterly report.

Results from Holcomb, Meramec, and Laramie River provide information about options for mercury control at plants firing PRB coals. Options evaluated include coal-blending, introduction of additives onto the coal, and sorbent injection. General conclusions and observations from these tests include:

- Coal Blending
 - Testing at Laramie River Station (SDA + ESP) indicates no significant increase in mercury removal was achieved with two different western bituminous coals at blend ratios up to 80/20 (PRB/bituminous).
 - Up to 80% mercury removal was achieved during short-term testing at Holcomb (SDA + FF) at blend ratios up to 76/14 (PRB/bituminous).
 - Additional tests are required to confirm this result.
 - Blending tests are planned at Monroe (ESP).
- Coal Additives
 - >80% mercury removal was achieved at Holcomb and Laramie River using a combination of DARCO Hg injection and coal additive.
 - >80% removal was achieved at Meramec without carbon injection (plant configuration and high LOI may have contributed to removal).
- Treated Activated Carbon Injection (DARCO Hg-LH)
 - High removal (>90%) was achieved at Holcomb and Meramec during the long-term test periods and at Holcomb, Meramec, and Laramie River during parametric testing (no long-term tests were conducted at Laramie River).
 - No adverse balance-of-plant impacts were noted at either site.
 - Treated sorbents will be considered for testing at the remaining test sites.
- Other Balance-of-Plant Concerns
 - SGLP analyses from ash collected during the long-term test periods at Holcomb and Meramec were below the detection limit for mercury. Historical data suggest that no measurable mercury will leach from collected ash.
 - Flue-gas bromine measurements were made at Holcomb and Meramec during long-term testing of DARCO Hg-LH. No levels of bromine in excess of those expected for plants firing PRB coals were measured.
 - Trace amounts of activated carbon can be detrimental to ash quality for cement use. Options to protect ash for sales include TOXECON™ and TOXECON II™. TOXECON II™ tests are scheduled to begin this fall on a separate DOE contract.

Specific Conclusions and Observations from Testing at Laramie River include:

- Two technologies were demonstrated to enhance the performance of standard activated carbon:
 1. Chemical Addition to the Coal: Mercury removal of 94% was measured at a carbon feed rate of 4.5 lb/MMacf and a KNX injection rate of 1.6 gph. (KNX is a proprietary chemical developed by ALSTOM Power.)
 2. Chemically Enhanced Sorbent: Mercury removal in excess of 90% was achieved at DARCO Hg-LH injection concentrations of 4.5 lb/MMacf. (DARCO Hg-LH is a proprietary product of NORIT Americas.)
- Co-firing PRB and up to 20% western bituminous coals was ineffective at significantly increasing the native mercury capture. Two different western bituminous coals were evaluated. No change in the baseline mercury removal was noted with the first western bituminous coal tested, and the increase in mercury capture was limited to 10% with the second western bituminous coal.
- No measurable increase in stack opacity was observed during parametric testing.
- No change in ESP operating performance was noted as a result of parametric testing.

LIST OF ACRONYMS AND ABBREVIATIONS

| | |
|-------------|--|
| ACI | Activated carbon injection |
| APC | Air pollution control |
| B&W | Babcock & Wilcox |
| COC | Chain of Custody |
| DARCO Hg | Sorbent manufactured by NORIT Americas. Formerly known as DARCO FGD |
| DARCO Hg-LH | Sorbent manufactured by NORIT Americas. Formerly known as DARCO FGD-E3 |
| DOE | Department of Energy |
| ESP | Electrostatic precipitator |
| FGD | Flue gas desulfurization |
| ID Fan | Induced draft fan |
| kacfm | Thousand actual cubic feet per minute |
| kW | Kilowatt |
| MW | Megawatt |
| NETL | National Energy Technology Laboratory |
| O&M | Operating and Maintenance |
| PAC | Powdered Activated Carbon |
| PC | Pulverized coal |
| PRB | Powder River Basin |
| SCA | Specific collection area |
| SCEM | Semi-continuous emission monitor |
| SDA | Spray dryer absorber |
| SGLP | Synthetic groundwater leaching procedure |
| SSD | Sorbent Screening Device |
| TCLP | Toxicity characteristic leaching procedure |