### BOA:

### Asbestos Pipe-Insulation Abatement Robot

#### PROJECT GOAL

 Automated Asbestos Pipe-Insulation Abatement Robot & Support System for remote and minimally manually-attended abatement tasks

#### TECHNICAL APPROACH

- Remote and automatic self-propelled travelling mini-enclosure
- In-situ cutting, water-blasting, encapsulation and drying under high-speed airflow-induced vacuum
- Off-board water-separation (recycled & reused), waste/solids centrifuging and bagging and airflow HEPA-filtering

#### WORK SCOPE

- Proof-of-concept demonstration: CMU WI/SP '95/'96
- Cost-Benefit Study Development: CMU SU'96
- Develop 4-inch prototype and demonstrate on surrogate: K-25 SU'98
- Modify prototype for ruggedness and 3-inch pipe: CMU WI'98
- Demonstration at DoE site on asbestos: TBD WI'98 to SU'99














# Technology Overview

#### • TECHNOLOGY MATURITY

- Competing Baseline
  - Glovebagging
  - Full-enclosure abatement
- Technology Maturity
  - SDG Level 5 (completed); awaiting OK to go to Level 6

#### TECHNOLOGY RELEVANCE

- Aligned with STCG at INEEL: ID-7.2.11
  - INEEL seeking appropriate demo-site
  - Awaiting go/no-go decision from INEEL
- Broadly applicable across the DoE complex; No takers yet though!
- Aligned with NIBS demonstration-cycle; Likely demo at Pentagon???

# System Performance

#### • SYSTEM CAPABILITY

- Increased Abatement Rates up to 20 30 feet/hour
- OSHA Alternate Method Allowance Issued 1997
- Fiber-count verification below EPA and OSHA PEL & TWA limits

#### POTENTIAL & BENEFITS

- Job-cost reduction of 25% (glovebagging) to 50% (full enclosure)
  compared to manual techniques
- Dose-reduction to to operator removal from abatement-site by up to 100'
- Reduced fatigure from lack of heat-exhaustion
- Waste-volume reduction by more than 60% due to inherent size-cuts
- Application to on-going DoE and commercial abatement jobs
- Applicability to 3" & 4" pipe-diameter (current) and larger (future)

### Technical Progress

#### • SCHEDULE & TIMING

- Project Duration: November 1994 to June 1999
- Total Funding: \$2,291K

#### • STATUS

- Demonstration of system at on-going DoE (K-25) or commercial nuclear abatement site completed in August 1998
- Prototype hardening and modification for simultaneous 3-inch pipe handling completed in December 1998
- Awaiting asbestos-abatement site-selection for final demonstration.....
- Teamed with IUOE and NIBS for training and regulatory demonstration demonstration site-selection and notification pending (Feb.'99)
- Attempting to partner with commercial abaters for non-DOE demo (since Jan.'99)