the Energy to Lead

# **Enabling Technologies for Oxy-fired Pressurized Fluidized Bed Combustor Development**

**Kickoff Briefing** 

W. Follett - Program Manager
M. Fitzsimmons - Principal Investigator
Gas Technology Institute
October 23, 2015

## > Agenda

- Project Overview
- Objectives and Tasks
- Team Members and Responsibilities
- Risks and Mitigation
- Schedule and Deliverables
- Budget and Spend Plan
- Summary



# Enabling Technologies for Oxy-PFBC Development Overview

#### **Description and Impacts**

#### **Program Description**

- Demonstrate technologies at pilot scale that will improve Oxy-PFBC economics and reduce scale-up risk
- Budget: \$2.6M (\$2.0M DOE funding)

#### **Impacts**

- Supports path to exceed DOE's cost goal of \$106.4/MWh
- •SCO2 and improved gas cleanup technologies improve Oxy-PFBC COE from \$107 to \$82/MWh
- •Closes key technology gaps and validates at pilot scale

## Technology Objectives

- Supercritical CO2 (SCO2) Heat Exchanger Quantify SCO2 heat transfer coefficients and pressure drop in an Oxy-PFBC environment to anchor design rules for scale-up
- Staged Coal Combustion Develop design rules for injector placement for robust operation that maintains an oxidizing environment and avoids slagging
- Isothermal Deoxidation Reactor (IDR) Define operational limits on flue gas O2 concentration for an isothermal catalyst bed and demonstrate heat recovery



#### **Team Members and Roles**

- GTI (Gas Technology Institute) Lead, PFBC technology
- Linde, LLC Isothermal DeOxo Reactor technology and integration with SCO2 cycle
- CANMET Pilot plant test facility and test support
- CCPC (Canadian Clean Power Coalition) Funding for Canadian feedstock testing

#### **Schedule**

	9/3/2015 - 9/2/2016	9/3/2016 - 9/2/2017	
Tasks	Year 1	Year 2	
Program Management			Final
			Report
Component Development		Fab complete	
In-bed SCO2 HEX		Install	
Staged coal combustion		Install	
lsothermal DeOxo Reactor		Install	
	Test	Plan Pilot Te	esting
Pilot Test		plete Comple	ete
Testing			
Canadian Feedstock Testing			CCPC
Oxy-PFBC Ph. II Testing (for	[	10	Testing
reference)			Complete




# **Project Background and Benefits**

- GTI (formerly Aerojet Rocketdyne, Advanced Energy group) has ongoing efforts in Oxy-PFBC and Supercritical CO2 Brayton cycle technologies
  - This effort is the first to test the two technologies together

The payoff is expected to be significant reductions in the cost of electricity (COE) for systems

with CO2 capture

Linde provides an improved gas cleanup system to further improve performance



Projected performance exceeds the DOE Advanced Combustion Goal and approaches the DOE Transformative Goal



# **Oxy-PFBC Technology Overview**

#### **PRODUCT**

- Oxy-fired, pressurized fluidized bed combustor equipment for coal-fired power plants
- Elutriated flow removes ash and sulfur prior to recycle

#### **BENEFITS**


- Produces affordable electric power with near zero emissions
- Produces steam for heavy oil recovery using low value feedstock (petcoke, coal, biomass)
- Produces pure CO<sub>2</sub> for Enhanced Oil Recovery (EOR)

#### **MARKETS**

- Electric power generation with CO<sub>2</sub> capture
- Heavy oil production (once-through steam)
- Light oil production (CO<sub>2</sub> floods)

#### **STATUS**

- Long-life, in-bed heat exchangers demonstrated in 1980s
- Concept modified for oxygen-firing rather than air
- Technology development contracts with DOE
- Next step: Build & operate Pilot scale (1 MWth) plant




Commercial Scale PFBC Concept

Heritage Rocketdyne
Test Facility that
Demonstrated
Long Life In-bed Heat
Exchanger





# **ZEPS<sup>TM</sup> Powerplant Concept Vision**



- Enhanced efficiency and near zero emissions
- Enabling Technologies program focused on SCO2 HEX, staged fuel injection, improved gas cleanup

## Agenda

- Project Overview
- Objectives and Tasks
- Team Members and Responsibilities
- Risks and Mitigation
- Schedule and Deliverables
- Budget and Spend Plan
- Summary




## **Objectives**

### Project Objectives:

- Develop technologies at the pilot-scale that will significantly improve the economics of our current oxycombustion pathway
- Directly address technology gaps associated with scale-up and system performance for both atmosphericand pressurized oxy-combustion technology pathways in the DOE NETL program portfolio
- Mature the advanced supercritical CO2 Brayton cycle technology at the combustor level

### Technology Objectives

- Supercritical CO2 (SCO2) Heat Exchanger Quantify SCO2 heat transfer coefficients and pressure drop in an Oxy-PFBC environment to anchor design rules for scale-up
- Staged Coal Combustion Develop design rules for injector placement for robust operation that maintains an oxidizing environment and avoids slagging
- Isothermal Deoxidation Reactor (IDR) Define operational limits on flue gas O2 concentration for an isothermal catalyst bed and demonstrate heat recovery





## **Success Criteria**

## ➤ In-bed SCO2 Heat Exchanger

- Demonstrate that the measured heat transfer coefficients and pressure drop support significant improvement in projected cost of electricity (COE) for a commercial scale application for the SCO2 Brayton cycle relative to a steam Rankine cycle
- A significant improvement in COE is defined as a reduction of five percent or more based on the use of scaled test data

## Staged Coal Combustion

 Demonstrate that second stage coal injection can be achieved while maintaining an oxidizing environment without slagging

#### Isothermal Deoxidation Reactor

 Demonstrate performance, including heat recovery, that supports reduced cost of electricity at commercial scale



## In-bed SCO<sub>2</sub> Heat Exchanger


## **Technology Overview and Approach**

### Background

 One technology gap for SCO2 is integration with the heat source, including use of SCO2 as the working fluid in the in-bed heat exchangers

### Approach

- Operating conditions
  - SCO2 system will be a closed loop system running at 2500 psia and between 400F and 700F
  - Operating conditions were chosen so the heat exchanger tube Reynolds and Prandtl numbers enable scaling to the predicted commercial operating conditions (3000 psia and 1000-1300F)
  - Conditions avoid potential condensation on the bed-side surface of the tubes, and allow use of steel alloys with demonstrated compatibility with SCO2
- Determine hot and cold-side heat transfer coefficients, and coolant pressure drop, to enable scaling
- Coolant conditioning (heating and cooling) in the SCO<sub>2</sub> supply system will establish design performance for heat exchangers
- Scaling risk is minimized by running at similar coolant tube Reynolds number as in a commercial plant, and by using full scale in-bed heat exchanger tubes, particle sizes and velocities in the pilot



Modular pilot design enables retrofit of SCO2 coolant and fuel / oxygen injectors



## **Staged Coal Combustion**


## **Technology Overview and Approach**

### Background

- Staged combustion is planed for the commercial scale Oxy-PFBC design to maximize power/volume and maintain uniform bed temps below ash slagging conditions
- The GTI Oxy-PFBC is expected to have a different thermal profile than previous fluidized beds due to the fine coal and pressurized conditions

### Approach

- Characterize the single stage thermal profile during Oxy-PFBC Phase II testing, then select the 2<sup>nd</sup> stage injection point
- Demonstrate and characterize operation of the second stage injectors
  - Fuel for two-stage tests will be Illinois #6. Additional tests will be conducted with Canadian fuels in Subtask 3.4
  - Specific tradable features that drive performance will be characterized: flue gas recycle rate, fuel particle size and ash content, and coolant flow control
  - Oxygen / fuel flow rates and bed cooling will be varied to study bed injection point temperatures and ash behavior (burnout percentage, particle temperature, agglomeration potential)
- Develop performance curves for multiple fuels for scale-up to commercial size power plants
  - Knowledge is required to balance the power cycle (steam or SCO2) with the coal combustion cycle, optimize compression requirements, and generate the most commercially viable design





# **Isothermal Deoxidation Reactor (IDR)**

## Technology Overview and Approach


### Background

- The Linde isothermal reactor is a fixed bed reactor with indirect heat exchange suitable for endothermic and exothermic catalytic reactions.
- The IDR will reduce the oxygen content in the flue gas below 100 ppm level making the final CO<sub>2</sub> suitable for EOR.
- This project will also test the benefits of integrating the heat of oxidation reactions of supplemental fuel and/or CO<sub>2</sub> impurities into the SCO2 Brayton Cycle

## Approach

- The isothermal reactor will be fabricated as a single piece to replace the existing deoxidation catalytic reactor in the CO<sub>2</sub> purification unit from the Oxy-PFBC Phase II project. The existing DCC and LiCONOX will be used.
- The IDR uses an internal heat exchanger with supercritical steam or CO<sub>2</sub> working fluid to maintain a near constant temperature throughout the catalyst bed
- Characterize and define operational limits, in terms of flue gas O<sub>2</sub> content and heat recovery for the retrofits to the CO<sub>2</sub> purification unit.
  - O<sub>2</sub> residual content in the flue gas is managed by altering the fuel/oxygen ratio in the PFBC. The quantity of oxygen removed is controlled by the fuel flow rate into the catalytic reactor.
  - Temperature of the catalyst bed is controlled by matching catalytic deoxidizer fuel flow rate with catalyst heat exchanger coolant flow
  - Performance of the heat exchanger and balance between reaction and heat removal are to be measured in multiple locations to allow design of full scale cooled reactors
  - Fuel for the catalytic deoxidizer is to be natural gas, with hydrogen as a fallback option







# Task 1.0 - Project Management and Planning

- Manage and direct the project in accordance with a Project Management Plan
  - Meet all technical, schedule and budget objectives and requirements
  - Ensure that project plans, results, and decisions are appropriately documented and project reporting and briefing requirements are satisfied.
- The Recipient shall update the Project Management Plan 30 days after award and as necessary throughout the project to accurately reflect current status of the project.
  - PMP was updated and approved
- Project risk management
  - Follow risk management methodology in the Project Management Plan
  - Identify, assess, monitor and mitigate technical uncertainties as well as schedule, budgetary and environmental risks associated with all aspects of the project
  - Results and status shall be presented during project reviews and in Progress Reports with emphasis placed on the medium- and high-risk items



# **Task 2.0 – Component Development**

- Task 2.0 Design, fabricate and install the technologies into the pilot plant, and conduct facility integration tasks to update Piping and Instrumentation Diagrams (P&IDs) and control narratives
  - Subtask 2.1 In-bed SCO<sub>2</sub> Heat Exchanger
    - Design, acquire, fabricate and assemble SCO2 system components for the oxy-fired coal pilot plant, including the coolant loop CO<sub>2</sub> compressor and CO<sub>2</sub> temperature conditioning components.
  - Subtask 2.2 Staged Coal Combustion
    - Design, acquire, fabricate and assemble the second stage injection system
    - The system should be designed for retrofit compatibility with the previously designed pilot scale combustor hardware.
  - Subtask 2.3 Isothermal Deoxidation Reactor (IDR)
    - An IDR system with heat recovery shall be fabricated and installed at the PFBC pilot plant.



## Task 3.0 – Pilot Plant Testing

(Subtasks 3.1 and 3.2)

- Subtask 3.1 Test Planning
  - Integrated pilot plant test plans shall be developed and Hazardous Operations (HAZOPS)
    assessments completed
  - Refine cost projections to complete pilot testing in Budget Period 2
- Subtask 3.2 Commissioning
  - Pilot plant commissioning tests shall be conducted under this task to make it operational and ready for testing
  - Subsystem testing of new hardware prior to full plant operation
    - Leak tests at pressure, flow tests, and, where applicable, heat-up transients of fluid thermal conditioning units.



## Task 3.0 – Pilot Plant Testing

(Subtask 3.3)

#### Subtask 3.3 – Testing

- Up to two weeks of testing shall be completed over a two month period with Illinois #6 fuel to achieve the following objectives:
  - Demonstrate operation of in-bed heat exchangers with SCO<sub>2</sub>, including validation of heat transfer coefficients
    - Determine hot and cold-side heat transfer coefficients, and coolant pressure drop, to enable scaling
    - Coolant conditioning (heating and cooling) in the SCO<sub>2</sub> supply system will establish design performance for heat exchangers, which is an important metric for Brayton cycle power systems.
  - Demonstrate and characterize operation of the second stage injectors.
    - Oxygen flow rates, fuel flow rates and bed cooling will be varied in such a way as to allow a study of bed injection point temperatures and ash behavior (burnout percentage, particle temperature, agglomeration potential)
  - Characterize and define operational limits, in terms of flue gas O<sub>2</sub> content and heat recovery
    - Oxygen residual content in the flue gas is managed by altering the fuel/oxygen ratio in the PFBC. The quantity of oxygen removed is controlled by the fuel flow rate into the catalytic reactor.
    - Performance of the heat exchanger and balance between reaction and heat removal are to be measured in multiple locations to allow design of full scale cooled reactors



## Task 3.0 – Pilot Plant Testing

(Subtask 3.4)

#### Subtask 3.4 – Canadian Feedstock Testing

- Under this subtask, two Canadian coals, Genesee and Saskatchewan lignite, shall be tested to demonstrate operation with different feedstock
- Up to two weeks of testing is targeted over a 3-month period
- Importance of Genesee and Saskatchewan lignite
  - The objective is to test two coals that are of interest to Canadian power producers and have potential performance benefits in the Oxy-PFBC system
  - The two primary coal producing and using regions in Canada are Alberta and Saskatchewan
    - Genesee (Alberta subbit #1) is of interest because of its high calcium and low sulfur content, which should reduce the need for limestone for sulfur capture
    - Saskatchewan lignite (similar to North Dakota lignite) is of interest because of its current use in the Boundary Dam CCS plant, its lower energy content and its lower ash fusion temperature relative to Illinois #6
  - The test experience with these two coals will span the likely range for agglomeration propensity and help expand the operating envelope of the Oxy-PFBC unit




## > Agenda

- Project Overview
- Objectives and Tasks
- Team Members and Responsibilities
- Risks and Mitigation
- Schedule and Deliverables
- Budget and Spend Plan
- Summary



# **Team Members and Responsibilities**



**Organization Chart** 



# **Team Members and Responsibilities**

Organization	Role/Responsibility
gti.	<ul> <li>Project lead &amp; PFBC technology</li> <li>Process &amp; system engineering</li> <li>Risk mitigation &amp; pilot test planning</li> </ul>
Linde	<ul><li>Gas supply and clean-up systems</li><li>PFBC Heat exchanger design support</li></ul>
CanmetENERGY	<ul><li>Fluidized Bed Pilot Test Facility</li><li>Plant operating personnel</li></ul>

Roles are aligned to team member capabilities

	AR	Linde	Canmet
WBS 1.0 – Program Management			
WBS 2.0 – Component Testing			
WBS 2.1 – In-bed SCO2 HEX			
WBS 2.2 – Staged coal combustion			
WBS 2.3 – Isothermal DeOxidation Reactor			
WBS 3.0 – Pilot Testing			
WBS 3.1 – Test Planning			
WBS 3.2 – Commissioning			
WBS 3.3 – Testing			
WBS 3.4 - Canadian Feedstock Testing			

Legend: Lead Support

Project is organized with clear roles and responsibilities to facilitate task performance



## > Agenda

- Project Overview
- Objectives and Tasks
- Team Members and Responsibilities
- Risks and Mitigation
- Schedule and Deliverables
- Budget and Spend Plan
- Summary



# Risks and Mitigation – Technical Risks

1) Risk: Uneven oxygen mixing creates local reducing zones


**Mitigations**: Heritage designs available. Inject through multiple ports.

2) **Risk:** Second stage temperature is too high (caused by short reactor)

**Mitigations**: Characterize thermal profiles in pilot. Reduce firing rate kW/m2 in two-stage test.

- 3) **Risk:** Lack of familiarity with SCO2 working fluid results in unpredicted behavior **Mitigation**: Standard safety precautions, HAZOPS. Design system to tolerate failures of single components.
- 4) **Risk:** Packaging of De-Oxidizer heat exchanger prevents accurate cooling where needed in catalyst bed.

**Mitigation**: Phase II pilot reactor data will guide design. Can incorporate extra cooling to mitigate a moving reaction front.



#### Consequence

- 1)Risk level at beginning of tests
- 1: Risk level at end of tests



# Risks and Mitigation – Nontechnical Risks

	Probability (Low,	Impact	Risk Management
Description of Risk	Moderate, High)	(Low, Moderate, High)	Mitigation and Response Strategies
Resource Risks:			
Inadequate personnel available	Low	Moderate	Bring people in from AR that are outside of the Energy group. If sufficient AR people are not available, bring in outside contract personnel on a temporary basis.
Management Risks:			
Lack of coordination between team members	Low	Moderate	Continue to conduct weekly team meetings to coordinate activities and assess impacts of project results across multiple organizations. Daily tagup meetings for relevant team members will be established as necessary for tasks requiring intense interactions, such as during test preparation and test campaigns.
Schedule Risks:			
Inadequate schedule for completing pilot testing	Low	Moderate	Maintain two months of schedule slack between the end of Oxy-PFBC Phase II pilot testing and installation of equipment for testing on this program.
<b>Budgetary Risks:</b>			
Inadequate budget	Low	Moderate	Monitor technical progress against expenditures and develop action plans when necessary to maintain project on schedule and budget. Use experienced test crews to minimize risk of cost overruns on testing.
Environmental, Safety, and	l Health Risks:		
Injury during testing	Low	Moderate	Conduct Haz Ops and Level of Protection Analysis (LOPA), design hardware to applicable safety standards, conduct safety training of all personnel, conduct regular safety meetings and reviews, follow established safety procedures.
External Influences Risks:			
None identified			



## > Agenda

- Project Overview
- Objectives and Tasks
- Team Members and Responsibilities
- Risks and Mitigation
- Schedule and Deliverables
- Budget and Spend Plan
- Summary



# **Schedule**

					9/3/2015		9/3/2016		
		Start	End	Cost					
Tasks	WBS	date	date	(\$M)	Year	1	Yea	r 2	
					Kickoff Briefing		Plan plete		l Report
Key program milestones							Component ab Complete	Re	peration port Pilot Testing
WBS 1.0 Program Management				0.34					
	1.1,								
Management	1.2	9/3/15	9/2/17						
Reporting	1.4	10/1/15	10/2/17						Final Repo
WBS 2.0 Component Development				1.32					'
In-bed SCO2 HEX	2.1								
Design and component acquisition		5/1/16	8/31/16						
Assemble		9/1/16	11/30/16				Fab co	mplete	
Install		2/1/17	2/28/17						
Staged coal combustion	2.2					_	<u>L</u>		
Design and assemble		10/1/15					Fab comp	lete	
Install		1/1/17	1/31/17						
Isothermal DeOxidation Reactor	2.3								
Design and component fab		10/1/15							
Assemble		9/1/16	11/30/16				Fab	complete	
Install		2/1/17	2/28/17			Test	Plan		
WBS 3.0 Pilot Test				0.95			plete		
Test Planning	3.1	3/1/16	8/31/16				7	Pilot Tes	ting
Commissioning	3.2	3/1/17	3/31/17				Y	Complet	e
Testing	3.3	4/1/17	5/31/17				Plan		
Canadian Feedstock Testing	3.4					Com	plete		
Test Planning		3/1/16	8/31/16						PC Testing
Testing		6/1/17	7/31/17						Complete
Oxy-PFBC Ph. II Testing (for reference)	N/A	4/1/16	10/31/16			[	!		
			Total	2.61					



# **Deliverables**

Budget	Task		Planned	Planned	Actual	
Period	No.	Milestone Description	Start	Comp	Comp	Verification Method
1	1.4	Conduct Kickoff Briefing	10/1/15	10/31/15	10/23/15	Presentation file
1	2.3	Complete Design of Isothermal DeOxidation Reactor	10/1/15	5/31/16		Design Review briefing file
1	2.2	Complete Design of Staged Coal Combustion Assembly	10/1/15	4/30/16		Design Review briefing file
1	2.1	Complete Design of SCO2 Heat Exchanger	5/1/16	5/30/16		Design Review briefing file
1	3.1	Complete Pilot Plant Test Plan	3/1/16	8/31/16		Pilot Plant Test Plan file
1	2.2	Complete Coal Injector Fab	10/1/15	8/31/16		Photos of completed hardware
2	2.1	Complete In-Bed HEX Fab	5/1/16	11/30/16		Photos of completed hardware
2	3.3	Complete Pilot Testing	3/1/17	5/31/17		Pilot Plant Operation Report file
2	3.4	Complete CCPC Testing	6/1/17	8/15/17		Pilot Plant Operation Report file
2	1.4	Pilot Plant Operation Report	7/31/17	8/31/17		Pilot Plant Operation Report file
1, 2	1.4	Periodic, Topical, and Final Scientific/Technical Reports	Varies	Varies		Reports

## > Agenda

- Project Overview
- Objectives and Tasks
- Team Members and Responsibilities
- Risks and Mitigation
- Schedule and Deliverables
- Budget and Spend Plan
- Summary



# **Budget and Spend Plan**

## ➤ Program Funding Profile

		dget Period 1 2015 - 9/2/2016			Budget Period 2 9/3/2016 - 9/2/2017					
	Government		Cost Government				Cost			
	Share			Share	Share			Share	Total	
Aerojet Rocketdyne*	\$	443,599	\$	-	\$	507,642	\$	-	\$ 951,241	
Canmet	\$	483,056	\$	87,824	\$	361,980	\$	237,535	\$ 1,170,395	
Linde	\$	151,806	\$	37,951	\$	48,670	\$	12,167	\$ 250,594	
CCPC Testing	\$	-	\$	158,760	\$	1	\$	79,360	\$ 238,120	
Total	\$	1,078,461	\$	284,535	\$	918,292	\$	329,062	\$ 2,610,350	
Cost Share %		79%		21%		74%		26%		



<sup>\*</sup>Aerojet Rocketdyne portion will become GTI once contract is novated from Aerojet Rocketdyne to GTI

# **Budget and Spend Plan**


## ➤ Program Costing Profile

				Budget F	eri	iod 1			Budget Period 2								
	9/3/2015 - 9/2/2016											9/3/2016 - 9/2/2017					
Baseline Plan	Q1 Q2 Q3 Q4							Q1	Q3	Q4							
Federal	\$	112,349	\$	252,673	\$	163,363	\$	550,074	\$	213,343	\$	302,673	\$	305,378	\$	96,878	
Non-Federal	\$	13,891	\$	15,641	\$	50,201	\$	204,804	\$	12,167	\$	118,768	\$	138,764	\$	59,384	
Total Planned	\$	126,240	\$	268,314	\$	213,564	\$	754,878	\$	225,510	\$	421,441	\$	444,142	\$	156,262	
Cumulative Plan																	
Federal	\$	112,349	\$	365,022	\$	528,385	\$	1,078,459	\$	1,291,802	\$	1,594,475	\$	1,899,853	\$	1,996,731	
Non-Federal	\$	13,891	\$	29,532	\$	79,733	\$	284,537	\$	296,704	\$	415,472	\$	554,235	\$	613,619	
Total Planned	\$	126,240	\$	394,554	\$	608,118	\$	1,362,996	\$	1,588,506	\$	2,009,947	\$	2,454,088	\$	2,610,350	

# **Summary**

Oxy-PFBC with SCO2 Brayton cycle exceeds DOE targets for COE and CO2 capture, approaching DOE Transformative Goal

The Enabling Technologies program will test three key technologies at the pilot scale to demonstrate improved performance and reduce scale up risk



➤ GTI / Linde / Canmet team has the skills and depth to successfully develop and demonstrate the proposed technologies