

Development and Bench-Scale Testing of a Novel Biphasic Solvent-Enabled Absorption Process for Post-Combustion Carbon Capture (DE-FE0031600)

**Presenter: Paul Nielsen
Illinois State Geological Survey**

Pittsburgh, PA · August 16, 2018

Project Overview

Technology Background

Scope of Work/Technical Approaches

Current Status

Plan for Future Scale-Up /Development

Objectives

- ❑ Advance the development of a transformational biphasic CO₂ absorption technology from lab- to bench-scale
- ❑ Design, fabricate and test an integrated 40 kWe bench-scale capture unit with simulated and actual coal flue gas
- ❑ Demonstrate the technology progressing toward achieving the DOE's Transformational Capture goals

Project Participants

□ University of Illinois (**Technology Developer**)



Illinois State Geological Survey


- David Ruhter (MS, Lab Manager)
- Hafiz Salih (PhD, Environmental Engineer)
- Hong Lu (PhD, Chemical Engineer)
- Qing Ye (Post-Doctoral Research Fellow)
- Varenya Mehta (MS, Environmental Engineer)
- Paul Nielsen (PhD, Chemical Engineer)
- Yongqi Lu (PhD, Chemical/Environmental Engineer)

Illinois Sustainable Technology Center

- BK Sharma (PhD, Senior Chemical Engineer)
- Kevin O'Brien (PhD, Director)
- Wei Zheng (PhD, Senior Chemist)

□ Trimeric Corporation (**Design and Fabrication, TEA**)

- Darshan Sachde (PhD, Senior Chemical Engineer)
- Katherine Dombrowski (Principal Technical Staff)
- Kevin Fisher (VP, P.E., Principal Engineer)
- Ray McKaskle (P.E., Principal Engineer)




Budget Profile and Duration

Project duration: 36 mon, 3 Budget Periods (4/6/18–4/5/21)

- BP1: 9 mon (4/6/18-1/5/19)
- BP2: 12 mon (1/6/19-1/5/20)
- BP3: 15 mon (1/6/20-4/5/21)

Funding Profile:

- DOE funding of \$2,981,779
- Cost share (in-kind) of \$750,051 (20.1%)



Project Overview


Technology Background

Scope of Work/Technical Approaches

Current Status


Plan for Future Scale-Up /Development

Biphasic Process (BiCAP)



- ❑ Water lean Aqueous/Organic amine blend
 - CO₂-rich solvent separates into 2 liquid phases
- ❑ Reduced solvent flow to regenerator
- ❑ Enhanced CO₂ absorption via removal of rich solvent

Progression of Technology Development




Current Status of Solvent and Process R&D

Solvent Development	Results	Status
~80 solvents screened	2 solvents selected	Completed
VLE	Absorption capacity: similar to 5 m MEA	Completed
Absorption kinetics	Comparable to faster than MEA	Completed
Oxidation and thermal stabilities	Thermal stability at 150°C ~ MEA at 120°C; Oxidation stability ~8 times < MEA	Completed
Viscosity	CO ₂ -saturated rich phase solutions < 50 cP	Completed
Phase Separation	≥98% of CO ₂ uptake in <50% of solution	Completed
Heat of desorption	Estimated with VLE data	Completed
Corrosion effect	Less corrosion than MEA on CS or SS	Completed
CO ₂ absorption	Lab 10 kWe absorption column; Faster rates than MEA demonstrated in testing	Completed
CO ₂ stripping	Lab 10 kWe desorption system; Heat duty 2400 kJ/kg CO ₂ for BiCAP-1, 2000 for -2	Near Completion

Lab 10 KW_e Absorption and Desorption Tests Demonstrated Performance of BiCAP



- ❑ CO₂ absorption rate 12% faster than 5 m MEA for BiCAP-1
- ❑ Demonstrated effectiveness of liquid-liquid phase separation unit



- ❑ Tested up to 150 °C, 9 bar
- ❑ Minimum Reboiler Heat Duty:
 - BiCAP-1: 2400 kJ/kg CO₂
 - BiCAP-2: 2000 kJ/kg CO₂

Projected Energy Performance for Net 550 MW_e


	BiCAP*	DOE Case 12 (MEA)	DOE Case B12B (Cansolv)
Net Generating Capacity, MWe	550	550	550
Gross Generating Capacity, MWe	700	802	728
Amount of CO₂ captured, tonne/hr	478	548	480
Total Steam Derate, MWe	71.1	139	86
Reboiler/Flash Heat Duty, MWth	278	542	331
Thermal to Electric Energy, %	25.6	25.6	25.8
Direct Electrical Derate, MWe	44.8	75.2	51.7
Compression Duty, MWe	31.5	44.9	35.7
Other (Pumps, Fans, etc.), MWe	13.3	30.3	16.0
Total Derate for CO₂ Capture, MWe	116	214	137
Total parasitic use for entire plant, MWe	150	252	178

* Updated BiCAP case (Cold rich feed bypass the heat exchanger)


- ❑ Total derate 43% less than MEA
- ❑ CAPEX 20% less than MEA

Biphasic Solvents are Stable

Thermal Stability: BiCAP-1 @ 150 °C ~ MEA @ 120 °C



Oxidative Stability: BiCAP-1 8x < MEA @ 50 °C



- Corrosion rate of 2-3 times < MEA for carbon steel, minimal for stainless
- Viscosity <50 cP for CO₂-rich phase, <10 cP mixed @ 40 °C

Project Overview


Technology Background

Scope of Work/Technical Approach


Current Status

Plan for Future Scale-Up /Development


Project Task Flow



Design and Fabrication (BP1 and BP2)



Operation (BP3)



Solvent Management (BP1 and BP2)

Project
starts

BP1
2018

New studies of (1) solvent
volatility/loss and (2) process
modeling & optimization

Task 3 Volatility and Emissions

Component volatility by FTIR

Lab testing water wash options
Aerosol generation and control

9-mon

BP2
2019

Solvent Management
Studies

Task 7 Solvent Management

Degradation and reclamation
Ion exchange/adsorption

Develop in-situ loading
measurement

21-mon

Project Overview

Technology Background


Scope of Work/Technical Approaches

Current Status

Plan for Future Scale-Up /Development


Solvent Volatility & Losses

- ❑ DX-4000 FTIR purchased from GASMET
 - Volatility measurements in existing VLE cell in August/September
- ❑ Volatile losses and aerosol control to be tested in existing 10 kW lab absorber column
 - Water wash section to be added
 - 2-3 trays/packings to be tested
 - Total emissions to be measured by FTIR, aerosols collected by membrane filters and analyzed by TOC
 - Purchasing SO₃ aerosol generator





ASPEN Process Modeling

Mixed Solvent (Absorber)




CO₂-Rich Phase (Stripper)



- Process model regressed for BiCAP-1, in progress for -2
- BiCAP-2 expected to have better performance

Proposed Skid Flow Diagram



- ❑ Finish modeling ASAP (optimization and range for parametric testing)
- ❑ Finalize design by end of year

Project Overview


Technology Background

Scope of Work/Technical Approaches

Current Status

Plan for Future Scale-Up /Development

Progression of Technology Development



Acknowledgments

- ❑ Funding Support by USDOE/NETL through Cooperative Agreement No. DE-FE0031600
- ❑ DOE/NETL Project Manager: Andrew Jones
- ❑ DOE/NETL Contract Specialist: Bethan Young

Thank you!

Contact Information:

Yongqi Lu (Project PI)
Illinois State Geological Survey
Tel: 217-244-4985
Email: yongqilu@Illinois.edu