



Injecting Carbon Dioxide into Unconventional Storage Reservoirs in the Central Appalachian Basin with an emphasis on Enhanced Coalbed Methane Recovery

Project Number: DE-FE0006827

Nino Ripepi
Virginia Tech

U.S. Department of Energy
National Energy Technology Laboratory
Carbon Storage R&D Project Review Meeting
Developing the Technologies and Building the
Infrastructure for CO₂ Storage
August 21-23, 2012



Presentation Outline

- Benefit to the Program
- Goals and Objectives
- Organization
- Technical Overview
 - Characterization
 - Modeling
 - MVA Plans
- Schedule



Benefit to the Program

- Develop technologies that will support industries' ability to predict CO₂ storage capacity in geologic formations to within ± 30 percent.
- Conduct field tests through 2030 to support the development of BPMs for site selection, characterization, site operations, and closure practices.
- The research project is testing the potential for enhanced coalbed methane (ECBM) and enhanced gas (EGR) production and recovery
- The technology, when successfully demonstrated, will provide guidance for commercialization applications of ECBM and EGR



Project Overview: Goals and Objectives

★ Objectives:

- Inject 20,000 metric tons of CO₂ into **CBM wells** over a one-year period in Central Appalachia
- Perform a small (approximately 300 tons) Huff and Puff test in a **shale gas well**

★ **Duration:** 4 years, October 1, 2011–September 30, 2015

★ Goals

- Test the storage potential of unmineable coal seams and shale reservoirs
- Learn about adsorption and swelling behaviors of coal and shale (methane vs. CO₂)
- Test the potential for enhanced coalbed methane (ECBM) and enhanced gas (EGR) production and recovery
- Improve knowledge of unconventional and stacked storage systems (coal and shale)



Research Partners

- Virginia Center for Coal and Energy Research (Virginia Tech)
- Cardno Marshall Miller & Associates
- Gerald Hill
- Southern States Energy Board
- Virginia Department of Mines, Minerals and Energy
- Geological Survey of Alabama
- Sandia Technologies
- Det Norske Veritas (DNV)
- Consol Energy (Research Group)

Industrial Partners

- Consol Energy (CNX Gas)
- Harrison-Wyatt, L.L.C.
- Alpha Natural Resources
- Dominion Energy

Project Timeline

Phase I

18 months

(10/1/11 – 3/31/13)

- Characterization
 - Drill char. Well
 - Core sample analysis
 - Modeling
 - Baselines for monitoring
- Injection design
- Monitoring design
 - Well locations
 - Geophysical surveys
- **Go/no go 1: permits, access (12 months)**
- **Go/no go 2: characterization (18 months)**

Phase II

18 months

(4/1/13 – 9/30/14)

- Site preparation
 - Conversion of production wells
 - Drill monitor wells
 - Install additional monitor stations
- **CO₂ injection (10/01/2013-09/30/2014)**
- Monitoring
 - Atmosphere
 - Surface
 - Reservoir

Phase III

12 months



(10/1/14 – 9/30/15)

- Site closure
 - Conversion of injection and monitor wells
 - Site restoration
- Post-injection characterization
 - Data analysis and interpretation
 - Post-injection monitoring
 - Reservoir modeling


Ongoing: Management and Planning, Risk Analysis and Assessment, Characterization, Modeling, Monitoring, Education/Outreach

CBM Test – Selection Criteria


- CONSOL Operation
- Mineral and Surface Ownership
- Access
- Production
- EUR
- Depletion
- Depth
- Structure
- Continuity
- Regional Seals
- Faulting
- In-Fill Wells
- Perforations, Stimulation and Breakdown (Frac Records)





CBM Injection Test Sites Russell and Buchanan Counties, VA




CO₂ Injection Decline-Curve Analysis Phase II Injection Well RU-84 (BD-114)






Aerial View of CBM Site and CO2 Transport Plans




DD8




Decline Curve Analysis BU-1923 (DD-7)











CBM Injection Test Site Reserves and State of Depletion




Pocahontas No. 9 Structure Map



Pocahontas No. 9 Structure

-  POCAHONTAS NO. 9 STRUCTURE ISOLINE
C. I. = 25 FEET
-  SURFACE FAULT
-  ANTICLINE
-  SYNCLINE
-  POCAHONTAS NO. 3 DEEP MINE
-  CNX GAS CBM WELL
-  EQUITABLE CBM WELL
-  INJECTION WELL CANDIDATE


Cross Section Location Map



Cross Section Location


- A — A' LINE OF CROSS SECTION
- SURFACE FAULT
- POCAHONTAS NO. 3 DEEP MINE
- CNX GAS CBM WELL
- EQUITABLE CBM WELL
- GOB WELL
- INJECTION WELL CANDIDATE
- CROSS SECTION WELL

Cross Section Inset A – A'




LEE FORMATION

POCAHONTAS FM.



Net Coal Isopach Map

(Upper Horsepen to Pocahontas No. 1)



Net Coal Isopach Map

NET COAL THICKNESS ISOLINE;
CONTOUR INTERVAL = 4.0 FEET

SURFACE FAULT

POCAHONTAS NO. 3 DEEP MINE

CNX GAS CBM WELL

EQUITABLE CBM WELL

GOB WELL


DD-7
 DD-8
 DD-9
INJECTION WELL CANDIDATE

NET COAL THICKNESS


	< 10.0 FEET		18.0 - 22.0 FEET
	10.0 - 14.0 FEET		22.0 - 26.0 FEET
	14.0 - 18.0 FEET		> 26.0 FEET

Overview of Reservoir Modeling


- **Preliminary Reservoir Modeling – Single Zone**
 - ARI's COMET3
- **Detailed Reservoir Modeling**
 - ARI's COMET 3 – Four Zones (3 Injection, 1 Production)
 - Computer Modeling Group's GEM Program – By Seam
- **Coupling GEM with FLAC3D for Geomechanical Modeling**
(Poster Session)



Thickness Modeling - Challenges



Modeling Methodology






Key Reservoir Modeling Inputs for Preliminary Model

- Initial Gas Content = 400 ft³/ton
- Initial Permeability = 8md/4md
- Pressure Gradient = 0.3 psi/ft
- Half Fracture Length = 650 ft
- Coal Porosity = 1%
- **Producing Coal Depth = 1800 feet**
- **Total Coal Thickness = 15 feet**

Initiation of Injection, October 2013




Well Candidates: DD7, DD7A, DD8

Well Candidates
DD7, DD7A, DD8



Matrix CO₂, scf/ cuft

Well Candidates
DD7, DD7A, DD8





Sorbed CH₄ Recovery, %

After 20,000 Tons Injected



Well Candidates: DD7, DD7A, DD8

Well Candidates
DD7, DD7A, DD8



Matrix CO₂, scf/ cuft

Well Candidates
DD7, DD7A, DD8




Sorbed CH₄ Recovery, %

End of Injection, October 2014


Well Candidates: DD7, DD7A, DD8

Well Candidates
DD7, DD7A, DD8



Matrix CO₂, scf/cuft

Well Candidates
DD7, DD7A, DD8




Sorbed CH₄ Recovery, %

4 Years After the End of the Injection, October 2017


Well Candidates: DD7, DD7A, DD8

Well Candidates
DD7, DD7A, DD8



Matrix CO₂, scf/cuft


Well Candidates
DD7, DD7A, DD8




Sorbed CH₄ Recovery, %

ECBM after 1 and 4 Years Post-Injection: 22 – 106 MMcf


DD8A




CC7A




CC6A



EE8




Monitoring, Verification and Accounting (MVA)



Monitoring Well Candidates

MVA program features


- 2-3 monitoring wells, depending on:
 - Access
 - Anticipated plume growth
 - Tests to be conducted (VSP/crosswell seismic)
 - Future well utilization (conversion or plugged)



Offset Well Testing

MVA program features


- 2-3 monitoring wells, depending on:
 - Access
 - Anticipated plume growth
 - Tests to be conducted (VSP/crosswell seismic)
 - Future well utilization (conversion or plugged)
- Offset well testing
 - Pressure
 - Gas content
 - Production
 - Temperature



Surface Monitoring Stations

MVA program features


- 2-3 monitoring wells, depending on:
 - Access
 - Anticipated plume growth
 - Tests to be conducted (VSP/crosswell seismic)
 - Future well utilization (conversion or plugged)
- Offset well testing
 - Pressure
 - Gas content
 - Production
 - Temperature
- Surface test stations
 - Soil gas composition
 - Groundwater tests
 - Microseismic array
 - Surface deformation measurement
 - Isotope and Tracers




Monitoring, Verification and Accounting (MVA)

MVA program features

- ★ 2-3 monitoring wells, depending on:
 - Access
 - Anticipated plume growth
 - Tests to be conducted (VSP/crosswell seismic)
 - Future well utilization (conversion or plugged)
- Offset well testing
 - Pressure
 - Gas content
 - Production
 - Temperature
- Surface test stations
 - Soil gas composition
 - Groundwater tests
 - Microseismic array
 - Surface deformation measurement
 - Isotope and Tracer









Shale Test

- West Virginia Targets: Lower Huron Shale
- Virginia Targets: Lower Huron Shale
- Tennessee Targets: Chattanooga Shale
- Selection Criteria
 - Ownership / Access
 - Vertical vs. Horizontal
 - Co-Mingled Production
 - Production
 - Depth
 - Structure
 - Liquids Production
 - Completion and Stimulation


Lower Huron Shale Cross Section Location Map



Cross Section A-A' Inset McDowell County, West Virginia












Depth to Lower Huron Shale



Shale Injection Well Candidates


Depth to Base of Lower Huron Shale

-  CNX GAS SHALE INJECTION CANDIDATE
 -  BASE OF LOWER HURON SHALE DATA POINT
 -  BASE OF LOWER HURON SHALE ISOLINE; CONTOUR INTERVAL = 100 FEET
 -  SURFACE FAULTS
- BASE OF LOWER HURON SHALE**
- | | |
|--|--|
|  < 5000 FEET |  6000 - 6500 FEET |
|  5000 - 5500 FEET |  > 6500 FEET |
|  5500 - 6000 FEET | |







Chattanooga Shale Study Area



Chattanooga Shale Cross Section Location



Cross Section A-A' Inset Morgan & Anderson Counties, TN





Accomplishments to Date

- Completed Geologic Characterization for CBM Test Site
- Preliminary Geologic Characterization for Shale Test Site
- Site Selection of 3 CBM Wells for Injection
- Access Agreements for CBM Test completed
- Access Agreements for Shale Test under review
- Conducted Risk Workshop and developed Risk Register
- Performed preliminary reservoir modeling analysis and assessment
- Initiated Core Testing Program
- Initiated Public Outreach Plan

Task Name	Deliverables	Funding	Phase I				Phase II				Phase III							
			FY 2012				FY 2013				FY 2014				FY 2015			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Task 1.0--Project Management and Planning	Updated Project Management Plan	\$741,678																
Task 2.0--Site Selection and Access Agreements	Site Selection Memo and Access Agreements	\$691,528																
2.1--Initial Site Screening and Selection	CO2 Procurement Plan																	
2.2--Leases, Agreements, Permitting, etc.	Permitting Action Plan																	
2.3--Outreach and Education	Public Outreach Plan																	
Task 3.0--Site Characterization, Modeling, and Monitoring	Site Characterization, Modeling, and Monitoring Plan	\$3,217,450																
3.1--Detailed Geologic Characterization	Catalog of Well Logs File																	
3.2--Reservoir Modeling	Well Drilling and Installation Plan																	
3.3--Exploratory Characterization and Monitoring Wells	MVA Plan																	
3.4--Monitoring, Verification and Accounting																		
Task 4.0--Risk Analysis	Risk assessment and mitigation plan	\$216,095																
4.1--Develop Risk Register																		
4.2--Develop Risk Assessment and Mitigation Plan																		
4.3--Management of Risks																		
4.4--Update and Reassess Risk Plan																		
Task 5.0--Injection Design and Planning	Site Development, Operations, and Closure Plan	\$558,891																
5.1--Test Site Operations																		
5.2--Design of Monitoring Wells																		
5.3--Design of Injection Wells																		
Task 6.0--Pre-injection Site Preparation	Implementation Status Report	\$2,973,479																
6.1--Conversion of Production Wells																		
6.2--Conversion of Characterization/Monitoring Wells																		
6.3--Construction of Facilities																		
6.4--Monitoring																		
Task 7.0--Injection Operations	Quick-look Memo Mid-term Memo	\$4,391,325																
7.1--Injection Tests																		
7.2--Reservoir Monitoring																		
7.3--Surface Monitoring																		
7.4--Reservoir Modeling and Verification																		
Task 8.0--Post Injection Monitoring and Analysis	Updated Site Characterization/ Conceptual Models Plan	\$816,057																
8.1--Post-injection Monitoring																		
8.2--Interpretation and Assessment																		
Task 9.0--Closeout/Reporting	Commercialization Plan Best Practices Plan	\$767,588																
9.1--Closure of Site(s)																		
9.2--Reporting																		