

# Radiocarbon as a Reactive Tracer for Tracking Permanent CO<sub>2</sub> Storage in Basaltic Rock

DE-FE0004847

Juerg M. Matter

The Earth Institute, Lamont-Doherty Earth Observatory,  
Columbia University

---

U.S. Department of Energy  
National Energy Technology Laboratory  
Carbon Storage R&D Project Review Meeting  
Developing the Technologies and  
Infrastructure for CCS  
August 20-22, 2013



# Presentation Outline

---

- Benefit to the Program
- Project Overview
- The CarbFix Project, Iceland
- Monitoring & Verification Results
- Accomplishments to Date
- Summary

# Benefit to the Program

---

- The goal of the project is to develop and test novel geochemical tracer techniques for quantitative monitoring, verification and accounting of stored CO<sub>2</sub>. These techniques contribute to the Carbon Storage Program's effort of ensuring 99% storage permanence.

# Benefit to the Program cont.

---

- We are developing and testing the feasibility of carbon-14 ( $^{14}\text{C}$ ) as a reactive tracer for quantitative monitoring and accounting of geological  $\text{CO}_2$  storage.
- None of the currently applied  $\text{CO}_2$  monitoring approaches are able to provide a surveying tool for **dissolved** or **chemically transformed**  $\text{CO}_2$ .
- The technology, when successfully demonstrated, will provide an improvement over current monitoring practices.


# Project Overview:

## Goals and Objectives

---

- Monitor subsurface CO<sub>2</sub> transport with trifluormethylsulphur pentafluoride (SF<sub>5</sub>CF<sub>3</sub>) and sulfurhexafluoride (SF<sub>6</sub>).
- Testing carbon-14 (<sup>14</sup>C) as a reactive tracer for geochemical reactions (including mineral carbonation) caused by CO<sub>2</sub> injection at the CarbFix pilot injection site, Iceland.
- Drilling small diameter coreholes into injection zone for mineral carbonation study on core samples.
- Quantify the extent of mineral carbonation in the CarbFix basalt CO<sub>2</sub> storage reservoir.
- This research leads to advanced monitoring and accounting of geologic CO<sub>2</sub> storage.

# MINERAL CO<sub>2</sub> SEQUESTRATION INTO BASALT: THE CARBFIX PROJECT



- ~200 tons of CO<sub>2</sub> injected in January 2012
- ~1500 tons of CO<sub>2</sub> will be injected between January – December 2013

# CarbFix Partners

---

- Orkuveita Reykjavíkur (Reykjavik Energy), Iceland
- University of Iceland, Iceland
- CNRS, University of Toulouse, France
- Columbia University, New York, USA

Target zone for CO<sub>2</sub> sequestration identified at 400-800 m depth

Groundwater

Gas injected fully dissolved in water into target zone


2 kg/s of CO<sub>2</sub> from Condensers  
0.07 kg/s 2.2 thousand tons per year

800 kg/s of steam, gas and water from deep and hot (>240 °C) geothermal wells

Hellisheidi geothermal power plant




# Injection Process



distance between injection and first monitoring well is 150 m

# Tracer injection system



# Injection Phases

---

## Phase I

pure CO<sub>2</sub> injection of ~200 tons  
(January – February 2012)


**SF<sub>6</sub> & <sup>14</sup>C tracers**

## Phase II

CO<sub>2</sub>+H<sub>2</sub>S injection (80% CO<sub>2</sub>, 20% H<sub>2</sub>S)  
~1500 tons of CO<sub>2</sub>  
(2013)


**SF<sub>5</sub>CF<sub>3</sub>, AmidRhod G & <sup>14</sup>C**

# Monitoring Wells




# Phase I: SF<sub>6</sub> Monitoring Results

- Goal: Monitor advective and dispersive transport of injected solution




# Phase I: $^{14}\text{C}$ Monitoring




# Phase I: $^{14}\text{C}$ Monitoring

- Goal: Monitor  $\text{CO}_2$ -fluid-rock reactions (carbon mass balance)




# Phase I: $\delta^{13}\text{C}_{\text{DIC}}$ Monitoring Results

- Goal: Monitor  $\text{CO}_2$ -fluid-rock reactions





# Phase I: CO<sub>2</sub> Reactivity



# Carbon Mass Balance

1. Calculating mixing between injected solution and reservoir fluid using  $SF_6$

$$[SF_6]_i = X[SF_6]_{IS} + (1 - X)[SF_6]_{BW}$$



2. Calculating theoretical dissolved inorganic carbon concentration ( $DIC_{mix}$ ) due to pure mixing in the reservoir

$$DIC_{mix} = X_{SF_6} \cdot DIC_{IS} + (1 - X_{SF_6}) \cdot DIC_{BW}$$


3. Calculating difference between measured and theoretical DIC

$$\Delta DIC = DIC_{sample} - DIC_{mix}$$

# Carbon Mass Balance



# $^{14}\text{C}$ Mass Balance



# Accomplishments to Date

---

- Pure CO<sub>2</sub> injection (Phase I) was successfully completed.
- The mixed gas CO<sub>2</sub>+H<sub>2</sub>S injection (Phase II) is currently being performed.
- Continuous collection of fluid and gas samples for chemical and tracer analyses is being conducted in injection and monitoring wells for Phase I and Phase II injection.
- Initial and major breakthrough of CO<sub>2</sub> from Phase I in the first monitoring well occurred in April 2012 and February 2013, respectively.
- Initial breakthrough of injected CO<sub>2</sub> from Phase II occurred in August 2012.


# Summary

---

- Preliminary analysis of the tracer data from the Phase I injection indicates CO<sub>2</sub> mineralization via CO<sub>2</sub>-fluid-basalt reactions.
- Mass balance calculation reveals that over 85% of the injected CO<sub>2</sub> from Phase I has been mineralized.
- The developed and applied tracer techniques of non-reactive (SF<sub>6</sub>, SF<sub>5</sub>CF<sub>3</sub>) and reactive tracers (<sup>14</sup>C) allows for quantitative monitoring and verification of CO<sub>2</sub>-fluid-rock reactions.
- The developed and applied tracer techniques are successful surveying tools for dissolved and chemically transformed CO<sub>2</sub>, leading to a quantification (mass balance) of stored CO<sub>2</sub> in geologic reservoirs.

# Appendix

## Organization Chart



# Gantt Chart

Tasks	BP I					BP II								BP III			
	Qt 1	Qt2	Qt3	Qt4	Qtr5	Qt1	Qt2	Qt3	Qt4	Qt5	Qt6	Qt7	Qt8	Qt1	Qt2	Qt3	Qt4
<b>Task 1.0 Project Management, Planning and Reporting</b>							E					J					
<b>Task 2.0 Monitoring the CO<sub>2</sub> movement with SF<sub>5</sub>CF<sub>3</sub> in the basalt formation</b>							E					J					
Subtask 2.1 Monitoring the SF <sub>5</sub> CF <sub>3</sub> concentration in target injection interval and overlying shallow aquifer		A						F		I				M			
Subtask 2.2 SF <sub>5</sub> CF <sub>3</sub> Data Analysis			C					G		I				M			
<b>Task 3.0 Monitoring of geochemical reactions and in situ mineral carbonation with <sup>14</sup>C</b>							E					J					
Subtask 3.1 Monitoring the <sup>14</sup> C concentration in target injection interval and overlying shallow aquifer			B					F		I				M			
Subtask 3.2 Carbon-14 and d <sup>13</sup> C Analysis					D			G		I		K		M			
<b>Task 4.0 Mineral carbonation studies on core samples</b>																	
Subtask 4.1 Wireline core drilling																	
Subtask 4.1.1 Drilling plan									H				L				
Subtask 4.1.2 Drilling and coring														N			
Subtask 4.2 Mineralogical and geochemical analysis of core samples																O	
<b>Task 5.0 Quantification of mineral carbonation in reservoir</b>																P	