

*the Energy to Lead*

# **Pilot Test of a Nanoporous, Super-hydrophobic Membrane Contactor Process for Post-combustion CO<sub>2</sub> Capture**

**DOE Contract No. DE-FE0012829**

---

**S. James Zhou, Shiguang Li, Travis Pyrzynski, and Howard Meyer, *GTI*  
Yong Ding and Ben Bikson, *PoroGen*  
Song Wu and Sandhya Eswaran, *MHPS-AEE*  
Katherine Searcy, *Trimeric***

Presentation for 2014 NETL CO<sub>2</sub> Capture Technology Meeting

July 31, 2014

# Funding and performance period

---

- **Funding**: \$12,544,638
  - DOE: \$10M
  - Cost share: \$2.54M (20% of the total budget)
    - GTI: \$1,150K
    - ICCI: \$600K
    - PoroGen: \$625K
    - MHPS-AEE: \$135K
- **Performance period**: Oct. 1, 2013 – Sep. 30, 2017

# Project objectives and goal







## ▪ Objectives:

- Build a 1 MW<sub>e</sub> equivalent pilot-scale CO<sub>2</sub> capture system (20 ton/day) using PEEK hollow fibers in a membrane contactor and conduct tests on flue gas at the NCCC
- Demonstrate a continuous, steady-state operation for a minimum of two months
- Gather data necessary for process scale-up


## ▪ Goal

- Achieve DOE's Carbon Capture performance goal of 90% CO<sub>2</sub> capture rate with 95% CO<sub>2</sub> purity at a cost of \$40/tonne of CO<sub>2</sub> captured by 2025

# Our team


Member	Specific Project Roles
	<ul style="list-style-type: none"><li>• Project management and planning</li><li>• EH&amp;S analysis</li><li>• System design and construction</li><li>• Site preparation, system installation, and shakedown</li><li>• Pilot test at the NCCC</li></ul>
	<ul style="list-style-type: none"><li>• PEEK hollow fiber and module development</li><li>• Supporting system design and construction</li></ul>
	<ul style="list-style-type: none"><li>• Advanced H3-1 solvents for HFC application</li><li>• Supporting techno-economic analysis</li></ul>
	<ul style="list-style-type: none"><li>• Techno-Economic Analysis</li></ul>
	<ul style="list-style-type: none"><li>• Consulting support on gas compression</li></ul>
	<ul style="list-style-type: none"><li>• Site host</li></ul>

# Timeline and scope




# What is a membrane contactor?

- High surface area membrane device that facilitates mass transfer
- Gas on one side, liquid on other side



- Membrane does not wet out in contact with liquid
- **Separation mechanism:**  $CO_2$  permeates through membrane and reacts with the solvent;  $N_2$  does not react and has low solubility in solvent

# Process description



**Flue gas after FGD**  
 Temperature: 40 to 80°C  
 Pressure: 1-4 psig

T (°C)	P (psig)
~120	1-50+



Polymer	Max service temperature (°C)
PTFE	250
PVDF	150
Polysulfone	160
<b>PEEK</b>	<b>271</b>

- The PEEK hollow fibers exhibit exceptional solvent resistance: exposure of fibers to MEA solution (30%) for 1,500 hours at 120 °C had no adverse effect on the mechanical properties or gas transport

# Bench-scale development (Oct. 1, 2010 – Dec. 31, 2013): objective and scope

2010

Objective: develop PEEK membrane contactor technology to meet DOE's target of  $\geq 90\%$  CO<sub>2</sub> capture in one stage,  $>95\%$  CO<sub>2</sub> purity





**BP3**

Integrate absorption/regeneration




Field testing






# PEEK membrane: from fibers to commercial modules



**Hollow fibers**


OD: 18 mil  
ID: 10 mil

**Commercial**  
8" diameter  
60" long



**Module scale-up from bench to commercial**

- 2" bench – 0.12 m<sup>2</sup> (lab)
- 2" bench – 0.5 m<sup>2</sup> (lab)
- 2" bench – 3 m<sup>2</sup> (lab )
- 4" field – 15 m<sup>2</sup> (field)
- 8" commercial – 60 m<sup>2</sup> (pilot-scale)



**Housing**



**Module in housing**

# Bench-scale membrane absorber study (over 140 tests)

- **Gas feed (bore side):** simulated flue gas compositions at temperature and pressure conditions after FGD
- **Solvents (shell side):** aMDEA (40 wt%) and activated  $K_2CO_3$  (20 wt%)
- **BP1 technical goal achieved**

Parameters	Goal	aMDEA	$K_2CO_3$
CO <sub>2</sub> removal in one stage	≥ 90%	90%	94%
Gas side ΔP, psi	≤ 2	1.6	1.3
Mass transfer coefficient, (sec) <sup>-1</sup>	≥ 1	1.7	1.8



Module for lab testing (Ø2" x 15" long, 1m<sup>2</sup>)

- **Performance not affected by O<sub>2</sub>, SO<sub>x</sub>, NO<sub>x</sub> contaminants in feed**

# Bench-scale membrane desorber study

## Technical goals achieved

Parameters	Goal	Mode III	Mode IV
CO <sub>2</sub> purity	≥ 95%	97%	97%
CO <sub>2</sub> stripping rate (kg/m <sup>2</sup> /h)	≥ 0.25*	2.8	4.1

\* Calculated based on a mass transfer coefficient of 1.0 (sec)<sup>-1</sup>

### Notes:

- 97% CO<sub>2</sub> purity, the rest is condensable water vapor
- Much higher CO<sub>2</sub> rate obtained in regeneration because trans-membrane pressure drop is used (higher pressure in liquid side than gas side), and liquid compression is of low cost (compared to gas compression)


# Bench-scale: integrated absorber/ regeneration and field testing




# Bench-scale field test process flow diagram

MWG's  
Station  
3 fan

Downstream  
of the fan



# Bench-scale field test results with aMDEA and H3-1 solvents




# Membrane contactor field performance: mass transfer coefficient for absorption

Solvent	L/G ratio, L/L	CO <sub>2</sub> removal in one stage	Mass transfer coefficient, (sec) <sup>-1</sup>
aMDEA	0.0080	90.4%	1.2
H3-1	0.0044	92.7%	1.4

Mass transfer coefficient for conventional contactors: 0.0004-0.075 (sec)<sup>-1</sup>



# Preliminary process flow diagram for the 1MW pilot plant





# PEEK membrane contactor system advantages

- Exceptional thermal, mechanical & chemical resistance
- Super-hydrophobic, non wetting, ensures independent gas & liquid flow under flue gas conditions
- High packing density via structured hollow fiber membrane module design for improved mass transfer
- Orders magnitude high mass transfer coefficient for CO<sub>2</sub> absorption and desorption for reduced absorber and desorber size
- Reduced CAPEX and OPEX



# MHPS advanced H3-1 solvent advantages

---

- H3-1 solvent has been tested in our PEEK membrane contactors
- H3-1 test results show higher mass transfer coefficients than the aMDEA solvent
- Published data from NCCC and EERC show that the required solvent flow rate and heat duty of H3-1 are 18 to 26% and 33 to 42% lower than benchmark MEA solvent obtained from conventional column based absorption/desorption process testing

# Technical and economic challenges of applying membrane contactor to existing PC plants

---


- Performance – Maximize overall mass transfer coefficient to reduce absorption system size
- Durability – Long-term membrane life in contact with solvent
  - Improve membrane hydrophobicity
- Contactor scale-up and cost reduction
  - Make larger diameter module, module packaging to reduce module cost

# Techno-economic analysis results based on bench-scale test results

Case	COE, \$/MWhr	Increase in COE	\$/Tonne CO <sub>2</sub> Captured*
DOE Case 11 no capture	80.95	--	
DOE Case 12 state of the art (amine plant)	147.30	82%	\$66.47
Membrane contactor with aMDEA	<b>126.28</b>	<b>56%</b>	<b>\$54.69</b>
Membrane contactor @ $K_{Ga}=2$ (1/s)	<b>111.57</b>	<b>38%</b>	<b>\$47.40</b>
<b>R&amp;D strategy to meet DOE's target</b>			
Improved membrane performance	CAPEX and OPEX savings		
Membrane fabrication cost	CAPEX savings		
Module materials of construction	CAPEX savings		
Advanced H3-1 solvent	OPEX savings		
Optimizing the process configuration and operating conditions to minimize energy consumption	OPEX Savings		

\* In 2011 dollars

# Slipstream test project BP1 milestones, schedule and decision points



Milestones		Decision Points	
a	Complete preliminary Techno-Economic Analysis study	A	GO/No-GO decision point based on results from preliminary TEA and EH&S studies
b	Complete preliminary EH&S study		
c	Achieve intrinsic CO <sub>2</sub> permeances of 1,700 to 2,000 GPU in 2-inch diameter modules	B	Successful completion of all work proposed in Phase I, and satisfactory meeting all milestones
d	Issue pilot-plant design package		
e	Submit Phase I report		

# Scope of work for other slipstream test budget periods

---

## BP2

- 8-inch diameter commercial-sized module fabrication
- Parts and equipment procurement
- 1 MW<sub>e</sub> CO<sub>2</sub> capture system construction

## BP3

- Site preparation and system installation at the NCCC
- Procure H3-1 solvent for the pilot testing
- Test system shake down at NCCC
- Parametric testing at NCCC performed prior to continuous testing

## BP4

- Identify operational conditions for the continuous steady-state run at NCCC
- Run continuous steady-state tests for a minimum of two months
- Gather data necessary for further process scale-up
- Final Techno-Economic Analysis and EH&S study

# Success criteria and decision points

Decision Point	Date	Success Criteria
Go/no-go decision points	9/30/2014	<ol style="list-style-type: none"> <li>1) PEEK hollow fiber membrane: membrane intrinsic permeance 1,700 to 2,000; and</li> <li>2) Final pilot-plant design package submitted to DOE</li> </ol>
Go/no-go decision points	9/30/2015	<ol style="list-style-type: none"> <li>1) HFC modules pass QC tests</li> <li>2) 8-inch diameter modules: <math>\geq 90\%</math> CO<sub>2</sub> removal rate, membrane contactor volumetric mass transfer coefficient <math>\geq 2.0</math> (sec)<sup>-1</sup>, gas side pressure drop &lt; 14 kPa (2 psi); and</li> <li>3) The 1 MW<sub>e</sub> pilot system constructed.</li> </ol>
Go/no-go decision points	9/30/2016	<ol style="list-style-type: none"> <li>1) The 1 MW<sub>e</sub> pilot system installed at NCCC;</li> <li>2) Operating to shows <math>\geq 90\%</math> CO<sub>2</sub> removal rate in one stage, membrane contactor overall volumetric mass transfer coefficient <math>\geq 2.0</math> (sec)<sup>-1</sup>.</li> </ol>
Completion of the project	9/30/2017	<ol style="list-style-type: none"> <li>1) Demonstrated a continuous steady-state operation for a minimum of two months; and</li> <li>2) Final Techno-Economic Analysis delivered to DOE, and</li> <li>3) Final report shows 90% CO<sub>2</sub> capture rate with 95% CO<sub>2</sub> purity at a cost of \$40/tonne of CO<sub>2</sub> captured achieved</li> </ol>

# Risks and mitigation strategies

Description of Risk	Risk Mitigation Strategies
<b>Technical Risks</b>	
Particulates fouling the membrane	Filters and guards for particulates
Pressure drop across the module affects parasitic load.	Fiber dimension
<b>Process risks</b>	
Cost of the process not in line with expected outcome	Capital costs reduction by increasing module diameter and scale of manufacturing. Operating costs reduction by using advanced solvents
Corrosion or fouling of membrane system equipment	Materials of construction, process modification, pre-treatments
<b>EH&amp;S implications of the proposed technology</b>	
Environmental, health, and safety during testing and commercial implementation	Identify potential EH&S issues related to module fabrication, system operations/maintenance/decommissioning. Establish plans to mitigate potential hazards, wastes and emissions.



# Plans for future testing/development/commercialization

Time	Development	Module diameter	Projected # of modules*
<b>By 2013</b>	Bench-scale (Successfully Completed)	4-inch	1
<b>By 2017</b>	1 MWe pilot scale (In Progress)	8-inch	17
<b>By 2020</b>	25 MWe demonstration	8-inch	425
		30-inch	30

\* Calculated based on:

- Module area:
  - Current  $\varnothing$ 8-inch module: 100 m<sup>2</sup>
  - Projected  $\varnothing$ 16-inch module: 400 m<sup>2</sup>
  - Projected  $\varnothing$ 30-inch module: 1400 m<sup>2</sup>



PoroGen's new facility currently has equipment capacity to produce 1,000 eight-inch membrane modules annually.

# Summary

---

- Promising technology based on field tests
  - $\geq 90\%$  CO<sub>2</sub> removal in one stage
  - Mass transfer coefficient of  $1.7 \text{ (sec)}^{-1}$ , which is over one order of magnitude greater than conventional contactors
- Pilot-scale Phase I research progress
  - Preliminary EH&S study completed
  - TEA in progress

# Acknowledgements

- Financial support



- DOE NETL José Figueroa
- ICCI Dr. Debalina Dasgupta