

LOW ENERGY CO₂ CAPTURE ENABLED BY BIOCATALYST DELIVERY SYSTEM

2015 NETL CO2 Capture Technology Meeting Pittsburgh, PA.

Project: DE-FE0012862

June 24, 2014



Participants, Duration, Funding



Project awardee and subcontract for TEA:



Enzyme Supply:



Rethink Tomorrow

WorleyParsons

- Duration: 36 months (Oct 2013 to Sept 2016)
- Funding: DOE Funding: \$4,053,160
 <u>Akermin Cost share: \$1,013,289 (20%)</u>
 Total Project: \$5,066,449



PROJECT OBJECTIVES

- Modify existing pilot unit
- Assess performance of a new non-volatile, environmentally benign solvent
- Demonstrate on-stream biocatalyst maintenance
- Complete six-month demonstration at the National Carbon Capture Center (NCCC)
- Meet Techno-Economic Analysis Estimates
 - parasitic power: <220 kWh/t CO₂
 - capital costs reduced by >20%
 - cost of capture reduced by >30%



90% CO2 capture is assumed for all DOE goals



TECHNOLOGY BACKGROUND

Chemical absorption of CO₂ in a novel low-energy solvent accelerated by a catalysts, carbonic anhydrase (CA)

$$cO_{2} + H_{2}O \xleftarrow{enz_{y}me} H^{+} + HCO_{3}$$

B + H⁺ \xleftarrow{BH}



Challenge: how to make an enzyme evolved in nature work in harsh industrial environments?





- Temperature (40- 105 °C)
- Extreme pH
- Impurities (SOx, NOx, etc.)
- Shear Forces
- Multiphasic systems

Enzyme engineering and advanced enzyme delivery systems are critical for solving the problem



AKERMIN'S BIOCATALYST DELIVERY SYSTEM





PROOF OF CONCEPT: CATALYST ON PACKING

Two solvents tested: K2CO3 and AKM24 (May – Oct 2013)







REMAINING CHALLENGES: FURTHER REDUCTION OF ENERGY AND IN SITU BIOCATALYST REPLACEMENT

□ Introduce new solvent, AKM-24

- High CO2 loading
- Low regeneration energy
- Non-volatile
- Thermally stable
- Highly water-soluble
- Manufacturing route established
- Low EH&S risks



Replace catalyst on packing with catalyst in suspension



CATALYST RECIRCULATION OPTIONS

Within the absorber only	Within absorber and stripper
Efficient particle separation	No separation is needed
Moderately thermostable CA	Highly thermostable CA
Lower rate catalyst inactivation, less frequent catalyst replacement	Higher rate catalyst inactivation, more frequent catalyst replacement
Fewer performance issues expected	Likely issues with particles in the striper (inactivation, foaming)
Standard high temperature stripper	Lower temperature stripper with vacuum; extra stage of compression

- In addition, the economics of both options needs to be considered:
 - Equivalent work of CO₂ capture for either option
 - Overall cost of capture (including the enzyme)



TOTAL EQUIVALENT WORK ESTIMATES

Total equivalent work using Aspen after input of thermodynamic and kinetic data





Milestone



~30% reduction in ICOE



COST OF CAPTURE FOR VARIOUS CAPTURE SYSTEMS



~20% reduction in cost of capture appears achievable





EFFECT OF BIOCATALYST HALF-LIFE ON COE



Minor effect with half-life exceeding 100 days



FLOW DIAGRAM FOR PROCESS WITH CATALYST SEPARATION AND STRIPPING AT 105 °C







ENHANCEMENT FACTORS FOR ENZYME ON PACKING AND MICROPARTICLES VS. MEA





Milestone

CO₂ CAPTURE OVER TIME: CLOSED LOOP REACTOR WITH BIOCATALYST SEPARATION

2 LPM AKM24 @ 30 wt.%, 15 SLPM Gas Flow (13.3% Inlet CO_2), 35-40 °C Column @ 2 psig





SUMMARY OF PROGRESS TO DATE

- Produced and tested multiple biocatalyst batches on kg-scale
- Installed lab-scale closed loop reactor
- Demonstrated >20X biocatalyst enhancement
- Completed 100-hrs on-stream test, demonstrated avg. 90% capture
- Generated equilibrium and rate data for baseline AKM24 for a range of concentrations, temperatures, and CO2 loadings
- Built enzyme kinetic model in Aspen and validated with data
- Identified cases with total equivalent work < 230 kWh/t CO2</p>
- Identified low cost biocatalyst separation option
- Completed Process Safety Analysis



FUTURE WORK AND NEXT SCALE ACTIVITIES

Commercial scale Biogas treating unit

- Size: 500 Nm³/hr. biogas
 - (50% of avg. commercial unit)
- \$7 MM, three year project
- 50% funding through EUDP (Danish Energy Agency)
- Schedule:
 - Project Kickoff Jan 2014
 - Commissioning Nov 2015
 - Start Operations Dec 2015
 - 24 months operation and testing



Upgrading biogas to pipeline specification at industrial scale using biocatalyst



- **DOE/NETL:** This material is based upon work supported by the Department of Energy National Energy Technology Laboratory under Award Number DE-FE0004228.
- Disclaimer: This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency.

