Intelligent Monitoring Systems and Advanced Well Integrity and Mitigation Project Number DE-FE-00026517

> Barry Freifeld Lawrence Berkeley National Lab Scott McDonald, Salil Arora Archer Daniels Midland

> > U.S. Department of Energy National Energy Technology Laboratory DOE Annual Review Meeting August 16-18, 2016

Presentation Outline

- Benefits to the DOE CCS Program
- Project Overview
- Methodology & Expected Outcomes
- Project Tasks Updates
- Project Milestones
- Project Timeline

Benefit to the Program

Carbon Storage Program Goal Support:

Goal (1) Develop and validate technologies to ensure 99 percent storage permanence by reducing leakage risk through early detection mitigation.

Goal (2) Develop technologies to improve reservoir storage efficiency while ensuring containment effectiveness by advancing monitoring systems to control and optimize CO₂ injection operations.

Goal (4) Contributing to the Best Practice Manuals for monitoring, verification, and accounting (MVA) with regard to IMS.

Benefit to the Program

IMS System Benefits:

- Reduce overall storage cost.
- Increase monitoring sensitivity.
- Increase monitoring reliability by using an integrated system.
- Optimize operation and maintenance activities.
- Reduce project risk during and after the injection of CO₂.

Project Overview: Goals and Objectives

- Develop an integrated IMS architecture that utilizes a permanent seismic monitoring network, combines the real-time geophysical and process data with reservoir flow and geomechanical models.
- Create a comprehensive monitoring, visualization, and control system that delivers critical information for process surveillance and optimization specific to the geologic storage site.
- Use real-time model calibration to provide reservoir condition forecasts allowing site optimization.

Decatur Site Overview

Richland CC

ADM Facility

Compression & Dehydration

IMS

Area

VW#2

GM#2

CCS#2

NSEC

VW#1


CCS#1

GM#1

CO₂ Collection Blower Area

USGS Seismic Monitoring





Methodology


- The proposed ICCS IMS program is transformative. It integrates into a single real-time processing framework the following emergent technologies.
 - DAS seismic imaging (VSP & surface reflection)
 - Permanent surface orbital vibrator
 - Hybrid geophone/DAS microseismic array
 - DTS well integrity monitoring

Existing vs. New Technology

Convention Seismic



DAS Seismic



Seismic surveys are considered the backbone technique for CO2 storage monitoring programs.

Stringing thousands of cables and running thumper trucks every few years can test the limits of good neighbors. Costs are high.


Permanent reservoir monitoring offers a way to obtain higher quality information with minimal intrusion into surrounding lands –

- DAS provides high spatial and temporal resolution.
- Installation can be in horizontal directionally drilled • boreholes beneath bodies of water, existing infrastructure.
- Excitation of DAS cables can be achieved through permanent fixed rotary sources for continuous monitoring.




Landscaping Other O

Saves the mess and cleanup work!



Distributed Acoustic Sensing

- Standard optical fibre acts as the sensor array
 - Typical sampling at 10kHz on 10,000m fibre
 - Standard gauge length of 10m
 - Spatial sampling of 25cm
 - DAS measures change in average elongation per 10m gauge length per 0.1ms acoustic time sample, sampled every 0.25 m in distance





Parker et al., Distributed Acoustic Sensing – a new tool for seismic applications, *first break* (32), February 2014

$$\left[u\left(z+\frac{dz}{2},t+dt\right)-u\left(z-\frac{dz}{2},t+dt\right)\right]-\left[u\left(z+\frac{dz}{2},t\right)-u\left(z-\frac{dz}{2},t\right)\right]$$

Ζ,

Surface Orbital Vibrator – VFD Controlled AC Induction Motor






FAT Helical Wound Cable


Anderson and Shapiro – HWC on soft mandrel 1980 US Patent 4375313 Hornman et al. (2013 75th EAGE) introduced a helical wound FO cable LBNL trialed multiple designs with varying physical properties Line 5 installed one length of HWC for comparison to straight fiber




mandrel.

Lessons learned – acoustic impedance of cable and surrounding soil is important






New Silixa Ltd. Carina Sensing System 100X Lower noise floor



Data collection courtesy Aquistore Project: PTRC/GSC/LBNL and JOGMEC

IMS Fiber Optic and CASS Layout



Expected Outcomes

- ICCS IMS project will provide a new approach towards comprehensive monitoring using automated workflows.
- Providing real-time support for operations.
- Maturing of DAS permanent reservoir monitoring for surface reflection seismic from a TRL of 6 to 8.
- Best practices report detailing IMS CASSM technology.

PROJECT TASKS UPDATES


Task/Subtask Breakdown

Task 2.0 - IMS Design

 Design an IMS that utilizes seismic and process monitoring data to create a comprehensive monitoring, visualization, and control system that delivers real time information for process surveillance and optimization.

Subtask 2.1 - IMS Data Acquisition and Processing Equipment

 Identify the IMS's required process and reservoir monitoring data feeds. Specify the IMS's hardware requirements related to data acquisition, processing, and storage, which includes programmable logic controllers (PLC), device CPU, servers, and storage devices.



Task/Subtask Breakdown

Subtask 2.2 - IMS DAS Surface Cable and Rotary Sources CASSM

 Design the layout and integration scheme for the surface DAS cable with the site's existing well deployed DAS system. Design and specify rotary source equipment related to motor, bearings, coupling, oscillating source, instrumentation, and electrical.


Subtask 2.3 - IMS Software Design and Development

 Develop real-time data pre-processing, filtering, and stacking system for CASSM DAS data including automated reflection vertical seismic profile (VSP) analysis flow, horizon-based inversion code, integrated IMS graphical user interface, and inverse modeling to improve constraints on scCO₂ plume extent.


Subtask 2.3 – IMS Software Design and Development

- Main IMS software design challenge: Integrate heterogeneous data streams
- 3 major components: (1) Data input, (2) Core process, (3) Monitoring information output
- Core analysis processes
 - Monitor reservoir integrity in near-real time
 - Continuously update reservoir model through parameter estimation scheme

IMS general software layout



Geophysical and in-well data pre-processing layout




Task 2.0 IMS Design Subtask 2.3: IMS Software Design and Development

Time-lapse feasibility evaluation using synthetic seismic data

- <u>Detectability</u> of the time-lapse changes
- *Interpretability* of the time-lapse signals
- <u>Repeatability requirements</u> imposed on the CASSM system


Fold Analyses → Superb Spatial Sampling

- Focus: southeast-northwest branch of the "L-shaped" ADM acquisition layout
- Sources: 3 surface orbital vibrators (SOV)
- Receivers:
 - 2 downhole DAS array at CCS2 (1919 m) and VW2 (1493 m)
 - 1 buried surface DAS array (CCS2→SOV3; offset range = 791 m)




- High fold count (>= 100) within 850-meter radius of the injection well CCS2
- Fold count as high as 750 in the 50-meter vicinity of CCS2

Time-Lapse Analyses → Promising Detectability and Interpretability



- Both time-lapse metrics (NRMS and time shift) show good sensitivities to the migration of the scCO2 plume front (NRMS_{max}: 30%-110%; Δt_{max}: 1 ms to 5 ms)
- Majority of NRMS > 10%–30% detectability thresholds (literature values for surveys of "good" repeatability)

Noise Analyses (AWGN) \rightarrow Time-Lapse Signals Require More Stacks




- Small plume thickness → Time-lapse signal intensity lower than primary reflections of stand-alone survey → Require 3-4 times more stacks than conventional surveys
- Achievable with SOV

Task/Subtask Breakdown

Subtask 2.4 – Design of Passive Microseismicity Monitoring System


 Develop near real-time extraction of DAS derived data into detection and location processing system. Develop processing, filtering, stacking, cross-correlation tools to automatically pick phase arrival on DAS channels. Test detection and location weighting for improved event location uncertainties.



Subtask 2.4 updates

Subtask 2.4 – Design of Passive Microseismicity Monitoring System

- Automated detection of seismic signals of interest
- Grouping in families and subfamilies of similar characteristics
- Template matching on stacked subfamilies to arrive at group of similar waveforms (used to extract travel times, etc.)
- Likely detection threshold lowering by an order of magnitude



Deliverables / Milestones / Decision Points

Task 1.0 - Project Management and Planning

- Updated project management plan.
- Complete NEPA documentation.

Task 2.0 – IMS Design

- Final design documentation including but not limited to: process instrument diagrams, equipment specifications, and IT network diagram.
- Algorithm description and testing results for the data pre-processing, filtering, stacking, and VSP analysis tools for CASSM DAS data and horizon-based inversion tools for the IMS.

Deliverables / Milestones / Decision Points

Task 3.0 – IMS Construction

 Topical report detailing the final constructed design including as-built design documentation such as process instrument diagrams, equipment specifications, and IT network diagram. The report will include a section on the integration of all components of the IMS.

Task 4.0 – IMS Operation

- Topical report detailing the commissioning and operation of the IMS. The report will include sections on plume tracking and best practices for utilization of the IMS CASSM system.
- Passive Seismic Monitoring Quarterly Seismic Event Catalog.

Briefings & Technical Presentations

• DOE annual briefings to review and explain the plans, progress, and results of the technical effort.

Milestone Status – Q3 2016

Milestone Description	Planned Completion	Actual Completion	Verification Method	Comments
Milestone 1-2 (B): Kickoff Meeting	12/31/15	12/31/15	Presentation file	
Milestone 1-1 (A) Project Management Plan	3/31/16	7/31/16	PMP document and sub-award agreements	Delays in obtaining funding and AFE approval
Milestone 2-1 (C) Completion of installation plan	6/30/16	8/31/16	Quarterly progress report and supplement	Delay in obtaining easements, revisions to rotary source and foundation design

Milestone Status – Q3 2016

Milestone Description	Planned Completion	Actual Completion	Verification Method	Comments
Milestone 2-2 (D) Completion of design of the planned architecture	6/30/16	6/30/16	Quarterly progress report and supplement	
Milestone 2-3 (E) Microseismic monitoring system	6/30/16	6/30/16	Quarterly progress report and supplement	
Milestone 2-4 (F) Software Design and Development	6/30/16	6/30/16	Quarterly progress report and supplement	
Milestone 2-5 (G) Final Design Review	7/31/16	9/30/16	Quarterly progress report and supplement	Critical design phase milestone

Project Timeline

			201	5						2016									2017											20	18						20.	19
ID	Task Name	Sep	Oct	Nov D	ec Ja	an Fe	Mar	Apr	May Jun	n Jul	Aug	Sep	Oct	Nov De	ec J	Jan Feb Ma	r Apr	May	Jun Ju	ul A	lug Si	ep C	ct Nov	Dec	Ja	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb
1	Phase I – Project Prerequisites													I					!																			
2	Task 1: Project Management and Planning	┝		_																																		
3	Task 2: Project Fact Sheet			└ ►																																		
4	Task 3: NEPA	 			Ь																																	
5	Complete Project Prerequisites		_		4	_		_		_																												
6	PHASE II – IMS Design																																					
7	Task 4: IMS Data Acquisition and Processing Equipment	┝						ו							ì																							
8	Task 5: Design CASSM	•						ו							i																							
9	Task 6: IMS Software Design and Development	→						ו											S			r																
10	Task 7: Design Passive Microseismicity Monitoring system				┝												八	-	3	Ŋ	4																	
11	Task 8: IMS Final Design Review						H]																													
12	Task 9: IMS Equipment Procurement	 								-																												
13	Task 10: Construction and Environmental Peruits	5						→)	;																							
14	Complete IMS Design				_	_			_				_L		_																							
15	PHASE III – IMS Installation					1		Ŀ)																													
16	Task 11: Develop Construction Plans							┝					Ь							Ι.	n	-	st	C				4			r							
17	Task 12: IMS Data Acquisition and Processing Equipment Installation											+			Ъ)		1				2)(O						U	I							
18	Task 13: IMS DAS Surface Cable and Rotary Sources CASSM Installation											┡			Ь)		i																				
19	Task 14: IMS Control, Monitoring, and Data Acquisition, Software Installation					ï									┝			ī																				
20	IMS Installation Complete					Ń										L.		1																				
21	PHASE IV – IMS Commissioning and Operation															L																						
22	Task 15: Instrumentation, controls, and data network commissioning															→												4										
23	Task 16: DAS Surface Cable and Rotary Sources CASSM Commissioning															→							r	J			Ø			U								
24	Task 17: Commission Utility Systems															└→																						
25	Task 18: IMS Operation													i		4																		հ				
26	IMS Commissioning and Operations Complete													i																			k					
27	PHASE V – Close out Reporting																																Ļ					
28	Task 18: Final Reporting																																Ļ	-		Ъ]	
29	PROJECT COMPLETE														-					_									_							L,		
															-					-									-			-					4	Ē

Updated Project Timeline

		Resource				2015 2016 2017 2018 2019
D	Task Name	Names	Start	Finish	Duration	Sep Oct Nov Dec Ian Feb Mar Apr May Ian Jul Aug Sep Oct Nov Dec Ian Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jun Feb Mar Apr Mar Ap
1	Task 1.0 – Project Management and Planning		10/1/2015	10/1/2015	0w	
2	Subtask 1.1: Project Management Plan	ADM	10/1/2015	3/31/2016	26w 1d	
3	Subtask 1.3: Kickoff Meeting	ADM	10/1/2015	12/31/2015	13w 1d	
4	Complete Project Prerequisites		4/1/2016	4/1/2016	0w	
5	Task 2.0 – IMS Design		10/1/2015	10/1/2015	0w	
6	Subtask 2.1: IMS Data Acquisition and Processing Equipment	LBNL	1/1/2016	7/1/2016	26w 1d	→
7	Subtask 2.2: Design CASSM	LBNL	1/1/2016	7/1/2016	26w 1d	+
8	Subtask 2.3: IMS Software Design and Development	LBNL	1/1/2016	8/1/2016	30w 2d	
9	Subtask 2.4: Design Passive Microseismicity Monitoring system	USGS	3/1/2016	7/1/2016	17w 4d	
10	Subtask 2.5: IMS Final Design Review	ALL	8/2/2016	8/31/2016	4w 2d	→ — 」 ◊
11	Subtask 2.6: IMS Equipment Procurement	ADM	8/1/2016	5/1/2017	39w 1d	
12	Subtask 2.7: Construction and Environmental Permits	ADM, RCC	5/2/2016	7/29/2016	13w	
13	Complete IMS Design		8/1/2016	8/1/2016	0w	
14	Task 3.0 – IMS Installation		9/1/2016	9/1/2016	0w	
15	Subtask 3.1: Develop Construction Plans	ADM	9/1/2016	9/29/2016	4w 1d	
16	Subtask 3.2: IMS Data Acquisition and Processing Equipment Installation	ADM, LBNL	9/30/2016	3/29/2017	25w 4d	→
17	Subtask 3.3: IMS DAS Surface Cable and Rotary Sources CASSM Installation	ADM, LBNL	9/30/2016	3/29/2017	25w 4d	→ <mark>· · · · · · · · · · · · · · · · · · ·</mark>
18	Subtask 3.4: IMS Control, Monitoring, and Data Acquisition, Software Installation	LBNL, ADM	3/30/2017	5/29/2017	8w 3d	
19			5/30/2017	7/28/2017	8w 4d	
20	Task 4.0 – IMS Commissioning and Operation		7/31/2017	7/31/2017	0w	
21	Subtask 4.1: Instrumentation, controls, and data network commissioning	ADM	7/31/2017	8/28/2017	4w 1d	→ <mark></mark>
22	Subtask 4.2: DAS Surface Cable and Rotary Sources CASSM Commissioning	ADM	7/31/2017	8/28/2017	4w 1d	→ <u> </u>
23	Subtask 4.3: Commission Utility Systems	ADM	7/31/2017	8/28/2017	4w 1d	
24	Subtask 4.4: IMS Operation	ALL	8/29/2017	10/29/2018	61w	<u>ب</u>
25	Subtask 4.5 Validate IMS real-time reduced order models	LBNL, ADM, SCS	8/29/2017	10/29/2018	61w	÷¢
26	Subtask 4.6 Passive Microseismicity Monitoring	USGS, ADM	8/29/2017	10/29/2018	61w	→¢
27	IMS Commissioning and Operation Complete		10/30/2018	10/30/2018	0w	
28	Final Reporting		10/30/2018	10/30/2018	0w	
29	PROJECT COMPLETE		10/1/2018	10/1/2018	1d	

IMS Project Summary

Supports Carbon Storage Program Goals.

- Reduce overall storage cost.
- Increase monitoring sensitivity.
- Increase monitoring reliability by using an integrated system.
- Optimize operation and maintenance activities.
- Reduce project risk during and after the injection of CO₂.