#### Innovative, Versatile and Cost-Effective Solid Oxide Fuel Cell Stack Concept

Nguyen Q. Minh

Center for Energy Research University of California, San Diego La Jolla, California

18<sup>th</sup> Annual Solid Oxide Fuel Cell Project Review Meeting Pittsburgh, PA June 12-14, 2017

# Innovative, Versatile and Cost-Effective SOFC Stack Concept Project

- <u>Project</u>: Innovative, Versatile and Cost-Effective Solid Oxide Fuel Cell Stack Concept (DE-FE0026211)
- <u>DOE/NETL Project Manager</u>: Dr. Patcharin Burke
- <u>Project Team</u>:
  - UCSD
    - Center for Energy Research: Dr. Nguyen Minh (PI), Dr. Yoon Ho Lee (Postdoctoral scholar), Dr. Eduard Ron (Postdoctoral scholar)
    - Department of Electrical Engineering and Center for Memory and Recording Research: Dr. Eric Fullerton, Haowen Ren (graduate student)
    - Department of NanoEngineering: Dr. Shirley Meng, Erik Wu (graduate student)
  - FuelCell Energy
    - Dr. Hossein Ghezel-Ayagh and Dr. Alireza Torabi

#### **Project Objective and R&D Work**

 <u>Objective</u>: Develop and evaluate a versatile stack configuration based on a prime-surface interconnect design for a broad range of power generation applications

 <u>R&D Work</u>: Involve R&D activities to demonstrate fabricability, operability and affordability of the stack design

#### **STACK DESIGN CONCEPT**

# Stack Design

#### **Incorporating Conventional Cells**



## **Features of Stack Concept**

- Reduced weight and volume
- Flexibility in gas flow configuration
- Reduced stacking performance losses
- Improved sealing
- Versatility in incorporation of different types of cell construction

#### **Prime-Surface Interconnect Design**



Cross Section



#### **Stack Design** Incorporating Sintered Cells



#### Not in Scale

#### **Stack Design** Cross Flow Gas Manifolding



#### Not in Scale

# Stack Design

#### **Incorporating Metal-Supported Cells**



### **Project Technical Activities**

- Prime surface interconnect design and fabrication development
- Metal-supported cell structure development
- Stack development
- Stack operation demonstration
- Stack cost assessment

#### PRIME SURFACE INTERCONNECT DEVELOPMENT

#### **Preliminary Interconnect Design Assessment**

- Flow distribution
- Mechanical loading
- Current collection
- Formability

#### **Prime Surface Interconnect Design**



Parameter	Value
Interconnect height	2.5mm
Interconnect sheet	0.3mm
thickness	
Cone angle	60°
Diameter of the cone	4mm
Mass of one sample	10.56 grams
(60 mm x 60 mm)	

## **Gas Flow Distribution Modeling**

• Approach: FLUENT software, LES & URANS turbulence models

• Inlet boundary conditions:

Parameter	Value
Inlet velocity	2 m/s
Temperature of the flow	800°C
Interconnect design	Egg carton shape
Fuel type	Hydrogen

## **Gas Flow Patterns**

#### Plane near interconnect/cell interface



• Flow is uniform with areas of boundary layer detachment in the wakes of the hills

#### Plane in interconnect center



- Flow exhibits areas of acceleration
- Potentially that can be used for improved diffusion

## **Mechanical Loading Modeling**

- Approach: ANSYS Mechanical software, modeling of loading within a stack
- Parameters:

Parameter	Value
Temperature of the cell	800°C
Interconnect design	Egg carton shape
Cell type	Conventional anode-supported
Number of cells in the stack	100
Interconnect material	Ferritic stainless steel

#### **Stress Analysis**



 The appeared stresses of 3.65MPa at the bottom cell are much lower than the yield strength of ferritic stainless steel (240MPa)

## **Current Collection Modeling**

- Approach: Analytical calculations
- Parameters:

Parameter	Value
Interconnect height	2.5mm
Interconnect sheet	0.3mm
thickness	
Cone angle	60°
Diameter of the cone	4mm

#### **Current Collection Losses**

**Egg-carton interconnect** 



- Evaluation was performed for a simplified interconnect design and egg carton shape
- Egg-carton shape accounts for insignificant increase in the area-specific resistance as compared to that of a cell
- Negligible current density losses with egg carton shaped interconnects

### **Interconnect Formability**



**Engineering drawing** 

- Engineering drawing produced
- Hydroforming method of production chosen
- The interconnect manufacturer Borit<sup>™</sup> contacted
- Positive feedback on its manufacturability received

# Prime Surface Interconnect Design

#### **Preliminary Assessment Summary**

- No flow maldistribution
- Stress estimated at interconnects well below yield strength of stainless steels
- Interconnect current collection without significant losses
- Formability possible with hydroforming

#### METAL-SUPPORTED CELL STRUCTURE FABRICATION

## **Sputtering Process**



# **Sputtering for SOFC Cell Fabrication**

• Fabrication of dense and porous layers



Nano-scale Dense YSZ layer

Scalability



Goldstone Vacuum Sputter System http://www.goldstone-group.com/





 Potential cost effectiveness





Weimar et al, PNNL Report PNNL-22732, 2013

#### **Fabrication of Dense YSZ Layers**

Structure & Condition



#### **Fabrication of Porous YSZ Structures**









#### **Fabrication of Porous Ni-YSZ Layers**







### **Fabrication of Porous LSC-YSZ Layers**





#### **EDX Mapping of Deposited LSC- YSZ Layer**



#### **Fabrication of SOFC Cell**



#### **Fabrication of SOFC Cell**



# Metal-Supported Cell Development

#### **Preliminary Fabrication Results Summary**

- Fabrication feasibility demonstration by sputtering
  - Dense YSZ electrolyte layers
  - Porous YSZ structures
  - Porous Ni-YSZ layers
  - Porous LSC-YSZ layers
  - Single cell structures
- Uniform layer thickness and excellent interfaces between layers
- Electrode porosity improvements required

### **Near-Term Future Work**

- Prime surface interconnect development
  - Initiate and evaluate hydroforming of egg carton shaped interconnect and characterize fabricated samples
  - Modify and optimize design
- Metal-supported cell structure development
  - Modify and optimize sputtering process and characterize fabricated samples
  - Fabricate and characterize single cells
  - Fabricate cell components and single cells on metal supports
- Stack development
  - Initiate assembling of stacks incorporating prime surface interconnects and sintered cells

#### Acknowledgments

- DOE/NETL SOFC project management, especially Dr. Patcharin Burke
- UCSD/FCE SOFC project team