



Texas Clean Energy Project A 400MW Power/Polygen Project With 90 percent carbon capture

Pittsburgh Coal Conference

October 6th, 2015


Karl E. Mattes, SP VP, Summit Power Group


Summit Power





- Summit Power Group is a Seattle-based developer of clean energy projects
- Founded 23 years ago by former U.S. Secretary of Energy Don Hodel & COO of Department of Energy Earl Gjelde
- Summit's projects:
 - Over 7,000 MW completed
 - Over 2,500 MW in development
- Summit's principal project types:
 - Wind power
 - Solar power
 - Natural gas-fired power plants
 - Carbon capture projects





Five Siemens gasifiers of TCEP-type on line in China







The Siemens gasifier







TCEP financing readiness & shovel-readiness



- All key permitting is now complete:
 - Record of Decision from US DOE on 9/29/11 (completes NEPA/EIS process)
 - Air permit issued 12/28/10 (no opposition/request for hearing)
- Off-take agreements completed & signed:
 - 100% of power sold to CPS Energy for 25 years
 - 100% of CO2 sold for 30 years (two investment-grade offtakers)
 - 100% of urea sold for 20 years (confidential to be announced)
- EPC Team Updating FEED (front end engineering + design) 1stQ 2015
 - EPC Team Members: China Huanqui Contracting & Engineering Corp. (HQC) + US partner in place (to be announced), Siemens, and Veolia
 - Anticipated 2015 financial closing and groundbreaking
 - All of debt to be provided by the Export-Import Bank of China (Chexim)

Where is the Project?







Site Location and Infrastructure








Figure 2.1. Polygen plant site and associated linear facilities.

The 600-acre site (after a rain)







2013 – 2015 Update





- 1. 2013 result; plant too expensive, contract structure needs enhancement, returns of project too low
- 2. Reduce cost
 - Replace 2-SFG500's gasifiers with 1-SFG850
 - Change F-class turbine to H-class
 - Input lessons learned
 - Reduce redundancy
 - Optimize, modularize, value engineer in FEED
- 3. Change contracting plan
 - Single EPC
 - Single constructor
 - Address labor
 - Reset O&M

Plot Plan Improvements





Cost Savings;

- Terraced landscape using natural elevation of site, reducing soil processing
- Reduced coal pile by 15 days
- Re-orientated buildings and process units
 - ASU, AMM/UREA, H2SO4, Cooling Tower, Aux Equipment
 - Raw water processing, wastewater processing
 - Results in pipe, steel, concrete, construction savings
 - Building placement optimized
- Coal handling optimized, saving conveyance
- Rail; deleted one shoofly track and double track throughout
- Work around an existing well
- Evaporation pond sizing and use
- Road routing at south entrance
- Drainage ditch sizing

FEED Update - Goals & Objectives






- Update the 2010-2011 FEED using the new plant configuration and verify assumptions of cost, schedule and performance
- 2. Optimize the design compared to the prior FEED, in regard to value engineering, modularization, and overall size of the project
- 3. Complete licensor PDP's, and leverage more engineering in order to sharpen costs
- 4. Identify all commodities with certainty including concrete, soil, steel, pipe, etc., and construction manhours
- 5. Prepare a FEED Update cost estimate, and convert to a LSTK price with provision to manage construction volatility

FEED Update Organization







FEED Update Results





- 1. Cost estimate results in significantly lower CAPEX
- 2. Feed stock savings result from utilizing less coal, and higher power block efficiency
- 3. Revenue streams to offtakers maintained
- 4. Overall plant economics enhanced in relation to 2013

EPC/O&M Contracts





- STCE is completing EPC contract negotiation; HQC/US Partner (CB), and Siemens (PB), Veolia (WTR)
- STCE is negotiating an O&M contract with US partner for a 20 year term

Contact information





Summit Power Group, LLC: www.summitpower.com

Texas Clean Energy Project: www.texascleanenergyproject.com

Contact Laura Miller, Director of Projects, Texas, for more information: lmiller@summitpower.com