

High Yield and Economical Production of Rare Earth Elements from Coal Ash

DOE Contract DE-FE0027167 – Phase 2

Physical Sciences Inc., Andover, MA,
Center for Applied Energy Research, Lexington, KY
Winner Water Services, LLC, Sharon, PA

Presentation to:

Rare Earth Elements (REE) Program Portfolio
2018 Annual Review Meeting
Pittsburgh, PA
10 April 2018

Acknowledgement:

This material is based upon work supported by the U.S. Department of Energy under Award DE FE0027167.

Disclaimer:

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Presentation Outline

- **Phase 2 Programmatics**
- **Rare Earths Recovery Process Overview**
- **Phase 1 Results Summary**
- **Phase 2 Overview**
- **Phase 2 Objectives**
- **Phase 2 Tasks, Schedule, Milestones, and Deliverables**
- **Current Status**
- **Summary**


Phase 2 Programmatic

- **Area Of Interest (AOI) 2 program: Pilot Scale Technology**
 - Existing separation technology previously demonstrated successfully on bench scale
 - Ready or near-ready for design at pilot scale
 - Pilot plant design to be delivered at end of Phase I
 - Ready for scale up to commercial scale at completion of Phase II
- **30-month Phase 2 program: 9/29/2017 – 3/31/2020**
 - Phase 1 ended 8/31/2017
- **Team:**
 - Physical Sciences Inc. (PSI), Andover, MA
 - Center for Applied Energy Research (CAER), Lexington, KY
 - Winner Water Services, LLC (WWS), Sharon, PA
- **Total Contract Value ~\$7.5M = \$6M DOE funds + \$1.5M Cost Share**

Rare Earths Recovery Process Overview

VG-2018-024-3

- **Physical separation stage, followed by a chemical separation stage, followed by a post-processing stage**
- **Proposed Product: REYSc-enriched mixture (dry concentrate)**
- **Higher Value Products: REY-rich & Scandium-rich concentrates**
- **By-products: Cement substitute, secondary fuel carbon,**



Phase I Results Summary


Ash Source Selection

- Ash from eastern KY coal selected for Phase 2 developments
- The average REYSc content of 556 ppm measured from a composite of 20 ash samples > 300 ppm (DOE requirement)



Sample	Sc	Y	Σ REE	Σ REY	LREE/HREE
Composite	33	59	457	516	7.46

Individual Rare Earth Elemental Content for Selected Ash Fraction



**Significant content of Nd (~170 ppm), Y (~70 ppm), and Sc (~40 ppm)
Reasonable (>~10 ppm) content of Pr, Gd, Dy, Er, Tb**



Chemical Processing of Selected Ash Fraction

- **Developed chemical processes for the selected ash fraction to recover REYSc with high yield and high enrichment in two final concentrate products of commercial value.**
 - Concentration expressed on elemental basis i.e. the content of REY or Sc relative to that of all elements)
- **Product 1: REY-rich concentrate:**
 - REY Yield > 18%, Conc > 30 wt%
 - Sc Yield ~ 18%, Conc ~ 0.5 wt%
 - REY concentration >> objective target (10 wt%)
- **Product 2: Sc-rich concentrate:**
 - Sc Yield ~ 18%, Conc ~ 1.5 wt%
 - REY Yield > 4%, Conc ~ 6 wt%
 - REE conc >> threshold target (5 wt%)




Post-Processing for REY and Sc Relative Content

Physical Sciences Inc.

VG-2018-024-8

- **Post-processing step 1 leads to:**

- 3X increase in REY enrichment
- Efficient separation from other contaminants
- Product well-suited for REY separation



- **Chemical processing and economics modeled in Aspen**
 - Capital and operating expenses per model
 - Modified per our team's experience
 - Result: Pro forma spreadsheet model
- **Physical processing economics modeled**
 - Capital and operating expenses per CAER experience
 - Result: Pro forma spreadsheet model
- **Integrated process economics modeled**
 - Added capital expenditures of physical and chemical processes
- **Modular, transportable physical and chemical processing plants**

Capacity, Products and Annual Production

VG-2018-024-10

- **Designed a nominal 1200 tpd physical processing plant and 600 tpd chemical processing plant**
 - Return on Investment (ROI) of < 5 years
- **Both physical and chemical processing plants**
 - Decoupled operations
 - Modular designs for operational flexibility and transportability
- **Byproduct ash fractions shipped to local markets**
- **Annual production of major REE, Sc, and Y concentrate (kg)**

	LREE				H	R	E	E		Other HREE
Sc	La	Ce	Pr	Nd	Eu	Gd	Tb	Dy	Y	Ho, Er, Tm, Yb, Lu
11K	11K	9K	300	10K	350	2K	300	2K	14K	300-800

Phase II Overview

Overall Project Goal

- **Develop and demonstrate a pilot scale plant to economically produce salable rare earth element-rich concentrates, including yttrium, scandium, and commercially viable co-products from coal ash feedstock; using environmentally safe, and high-yield physical and chemical enrichment processes.**
- **Phase 2 Project Metrics**

Performance Parameter	Threshold Value	Objective Value
Feedstock REYSc ^{fl} Content	>300 ppm (Whole Mass Basis)	>500 ppm (Whole Mass Basis)
Total REYSc Enrichment in Final Concentrate	>10 wt% (Elemental Basis)	>20 wt% (Elemental Basis)
Return on Investment*	<7 y	<5 y
Delivered Concentrate Quantity ^{&}	~50 g [§]	~0.5 kg ^{§§}

REYSc = Rare Earth Elements Plus Yttrium and Scandium, *Scale-dependent ~ 600 tpd, &Ten 5g split samples, 5g split sample required per solicitation.


Phase II Team

VG-2018-024-13

- **The CAER, PSI, WWS team provides a complete integrated science, technology, engineering, technology transition, and commercialization solution for DOE/NETL**
- **Key Personnel:**
 - **PSI:**
 - Dr. Prakash Joshi, PI/PM
 - Dr. Dorin Preda, Lead Chemist
 - Dr. Matthew Boucher, Lead Chemical Engineer/Process Modeling
 - **CAER:**
 - Dr. James Hower, Coal geochemistry, materials characterization
 - Dr. John Groppo, Mineral processing, feedstock logistics, site qualification
 - **WWS:**
 - Mr. Todd Beers: Chemical Engineering and technology commercialization
 - Mr. Michael Schrock, Chemical Engineering; plant design

Phase 2 Scope – I Overall Program

- **Demonstrate the Phase 1 REYSc separation/enrichment technology in pilot plant(s) with *decoupled* operating capacities of ~ 0.4 tpd physical processing, and ~ 0.5 tpd chemical processing.**
 - Both pilot designs will be *modular* and *transportable*.



Phase 2 Scope – II Physical Processing Pilot

- **The physical pilot plant comprises existing equipment at the CAER facility in Lexington, KY, which is being repaired/refurbished for use in Phase 2**
- **The physical pilot will be decoupled from the chemical pilot located at the WWS facility in Sharon, PA.**
 - ~ 40 tons of selected ash will be transported to CAER facility
- **Physical processing pilot, will be operated over < ~ 4 weeks for a significant demonstration while conserving project funds, producing 10 to 20 tons of the chemically processable ash fraction**
- **The selected ash fraction will then be transported to the WWS plant in Sharon, PA for chemical processing**

Phase 2 Scope – III Chemical Processing Pilot

- **Chemical processing pilot will utilize WWS's existing, proven solvent extraction equipment to the maximum extent possible, and also procure additional equipment**
- **The chemical pilot will be operated over ~ 2 to 4 weeks for a significant demonstration while also conserving project funds, producing ~ 50 to 500 grams of deliverable REYSc-enriched concentrate**
- **Pilot will demonstrate the high recovery/ recycling of reagents at > 95% efficiency.**
- **Establish processes for environmentally safe disposal of waste products**

Phase 2 Scope – IV

Chemical Micropilot & Techno-Economic Modeling

VG-2018-024-17

- **A ~1-5 kg/d Micropilot Plant will be developed at PSI, Andover, MA**
 - Quick turnaround validation of pilot plant processing parameters and to provide data for chemical pilot plant design

- **A critical part of Phase 2 will be to refine, enhance, and validate the Phase 1 Aspen-based Techno-Economic Model of REYSc recovery from coal ash using the results from physical and chemical pilot plant operations**
 - Fidelity of the resulting Phase 2 model is expected to be AACE Class 2
 - Model will be used to develop design of a commercial scale plant for profitable (ROI < 5 y) REYSc at the conclusion of Phase 2

Phase II Objectives

Phase 2 Project Objectives - I

Phase 2 Objective:

- **Demonstrate the REYSc separation/enrichment technology developed in Phase 1 in a pilot scale plant with operating capacity of 0.1-1 metric ton per day (tpd)**

Specific Objectives:

- 1. Refine and complete detailed design of the chemical pilot plant(s) from Phase 1**
 - *Modular, transportable designs*
- 2. Assemble and operate a *micropilot (chemical) plant* for quick turnaround validation of pilot plant processing parameters, and provide data for chemical pilot plant design**

- 3. Assemble pilot scale plant at CAER for physical processing of ash**
- 4. Construct a *modular* pilot scale chemical plant at WWS facilities**
- 5. Demonstrate operation of the physical pilot plant using the power plant (ash feedstock selected in Phase 1)**
 - Modular, mobile CAER plant that uses the selected ash feedstock
 - Operation at ash source, decoupled from chemical pilot plant

Phase 2 Project Objectives - III

- 6. Demonstrate operation of the chemical pilot plant using the selected ash fraction produced by the physical pilot plant**
 - Operation at WWS facility in Sharon, PA
 - Selected ash fraction transported to this facility from Lexington, KY
- 7. Refine and enhance the Phase 1 techno-economic model using results of above physical and chemical pilot plant operations**
 - Produce AACE Class 2 costing fidelity model in Phase 2
 - Current Phase 1 model is AACE Class 3
- 8. Develop and provide design of a commercial scale plant for profitable REYSc recovery from coal ash at Phase 2 conclusion**
 - Use the above refined Phase 2 techno-economic model
 - ROI metrics as previously stated

Phase II Tasks, Schedule, Program Milestones, and Deliverables


Phase 2 Tasks

Task #	Title	Lead/Performing Organizations	Performance Period (Months)	Budget Period
1.0	Project Management and Planning	PSI	1-18	1
1.0	Project Management and Planning	PSI	19-30	2
2.0	Site Host Agreement	PSI	2-6	1
3.0	Provide Split Samples	PSI	26-28	2
4.0	Physical Processing Demo & Ash Characterization	UK/CAER	2-27	1&2
4.1	Physical Processing Pilot Implementation	UK/CAER	4-18	1
4.1.1	Physical Processing Plant Preparations	UK/CAER	4-12	1
4.1.2	Physical Processing Plant Operational Demo	UK/CAER	12-18	1
4.2	Ash Fractions Characterization	UK/CAER	2-18	1
4.2	Ash Fractions Characterization	UK/CAER	19-27	2
5.0	Chemical Processing	WWS/PSI	2-28	1&2
5.1	Micropilot Plant and Experimental Developments	PSI	2-16	1
5.2	Chemical Processing Pilot Development	WWS/PSI	4-28	1&2
5.2.1	Chemical Pilot Plant Design	WWS/PSI	4-12	1
5.2.2	Chemical Pilot Plant Construction	WWS/PSI	9-18	1
5.2.3	Chemical Pilot Plant Shakedown	WWS/PSI	16-18	1
5.2.4	Chemical Pilot Plant Optimization and Demo	WWS/PSI	19-27	2
6.0	Techno-Economic Modeling	PSI	4-18	1
6.0	Techno-Economic Modeling	PSI	19-27	2
7.0	Commercial Plant Design	WWS/PSI	26-28	2
8.0	Engineering Development Support	PSI	2-18	1
8.0	Engineering Development Support	PSI	19-28	2

Phase 2 Schedule

VG-2018-024-24

- 30-month program



TIM = Technical Interchange Meeting

Phase 2 Milestones and Deliverables

VG-2018-024-25


Milestone	Program Month	Planned Completion Date
Kickoff Meeting	1	24 January 2018
Updated Project Management Plan	1	31 January 2018
Technical Interchange Meeting (TIM) #1 @CAER	3	15 March 2018
Quarterly Report #1	3	31 January 2018
Design Review @ NETL	6	04 May 2018
Host Site Agreement	6	04 May 2018
Construction, Waste Mgmt Docs for Phys & Chem Pilots	6	04 May 2018
Quarterly Report #2	6	04 May 2018
TIM #2 @WWS (Chem Plant Site Visit)	9	10 August 2018
Quarterly Report #3	9	27 July 2018
Sys Test, Ops, Sample & Analysis Plan for Phys Pilot	10	24 August 2018
TIM #3 @ CAER (Physical Pilot Site Visit/Demo)	12	26 October 2018
Quarterly Report #4	12	29 October 2018
Sys Test, Ops, Sample & Analysis Plan for Chem Pilot	13	30 November 2018
Quarterly Report #5	15	28 January 2019
TIM #4 @ PSI (Micropilot Site Visit)	15	08 February 2019
TIM #5 @ WWS (Chemical Pilot Shakedown Tests)	18	26 April 2019
Quarterly Report #6	18	29 April 2019
Physical Pilot Test Report	19	04 June 2019
Quarterly Report #7	21	29 July 2019
TIM #6 @ NETL (Readiness Review)	22	04 September 2019
Quarterly Report #8	24	28 October 2019
TIM #7 @ WWS (Chemical Pilot Demo)	26	06 January 2020
Quarterly Report #9	27	31 January 2020
Final REYSc Product Split Sample Delivery	27	07 February 2020
Chemical Pilot Test Report	28	28 February 2020
Techno-Economic Analysis Report	28	28 February 2020
Technology Development and Commercial Plant Design	28	28 February 2020
Phase 2 Final Report	30	30 April 2020
Phase 2 Final Briefing @ NETL	30	30 April 2020

Current Status

Modular, Transportable Physical Processing Plant

VG-2018-024-27

- **Reconditioned 40' Trailer for Transport & Use**
- **Reconditioned 2" Hydrocyclone**
- **Reconditioned 4'x4' Hydraulic Classifier**
- **Assembling 2x30 liter Flotation Cells**
- **Assembling 1'x1.5' Drum Magnet**



Ash Feedstock site agreement with EKPC for access, logistics, sampling, and transportation has been negotiated in currently in final round of signatures



Modular, Transportable Chemical Processing Plant

- **Winner's facility (formerly a Westinghouse torpedo production plant) in Sharon, PA is currently being refurbished with structural, spatial and electrical/water/ utilities infrastructure for the plant**
- **Detailed plant design currently in progress:**
 - Building upon Phase 1 Final Design Package, Feasibility Report, and Aspen Techno-Economic Model(s)
 - Initial discussions to review requirements and design approach on 03/27/2018
- **Design review ~ 4 May 2018**



Micropilot Plant

VG-2018-024-29

- **Plant, hoods, exhausts assemblies done**
- **Safety Reviews, and Safety Walkthrough completed**
- **Chemicals monitoring and waster disposal procedures in place**
- **Plant Standard Operating Procedure (SOP) approved by Safety Committee**
- **Plant testing has commenced: Four 5 L reactors plus peripherals**



Summary

- **The Physical Sciences Inc., Winner Water Services, and Center for Applied Energy Research Phase 2 program has been initiated and is progressing per our proposed plan**
 - Kickoff meeting held at NETL 24 January 2018
- **Host site agreement with EKPC for access, logistics, sampling, facilitates, transportation of selected ash feedstock....has been negotiated in currently in final round of signatures**
- **Refurbishment, assembly, and construction of Physical Processing Pilot is well underway at CAER, Lexington Site preparations for the Chemical Processing Pilot in progress at Winner Water facilities in Sharon, PA**
- **Detail design of Chemical Processing Pilot has been initiated**
- **Micropilot Plant at PSI in Andover, MA is ready for operation with initial data expected this week**