



**10 MWe CDCL LARGE PILOT PLANT DEMONSTRATION
- Phase I Feasibility
DE-FE0031582**

DOE Kickoff Meeting

TRANSFORMING OUR WORLD | 150 YEARS

May 22, 2018

Outline

☐ Background


☐ Technical Approach for 10 MWe Large Pilot

☐ Project Details

- Objectives
- Project Structure
- Project Schedule
- Project Budget


☐ Risk Management

CDCL Process



Two-stage Counter-current Moving Bed


CDCL Commercialization Path



B&W & OSU CDCL Collaboration


DOE Syngas CL Demo at NCCC Year: 2010-2017	<ul style="list-style-type: none">• Design and demonstration of 250 kWth syngas chemical looping facility
DOE Commercialization Phase I Year: 2012-2013	<ul style="list-style-type: none">• Conceptual design of 550 MWe commercial plant• Techno-economic analysis (>90 % CO₂, <35 % increase in COE)• Technology gap analysis
DOE Phase II A Year: 2013-2015	<ul style="list-style-type: none">• Laboratory cold model test• Design of 250 kWth pilot plant• Cost estimate for construction and test
DOE-ODSA Phase II B Year: 2015-2017	<ul style="list-style-type: none">• Construction and test of 250 kWth CDCL facility
DOE-ODSA Heat Integration Year: 2016-2018	<ul style="list-style-type: none">• Combustor simulation• Heat exchanger network integration and optimization• Dynamic model of integrated CDCL-steam cycle
DOE-ODSA Adv. Control Year: 2015-2017	<ul style="list-style-type: none">• Develop HLC-SMC process automation control architecture• Establish algorithm for high temperature ECVT sensor• Test process control and optimization concepts at 25 kWth scale
DOE- ODSA 10 MWe pre-FEED Year: 2017-2019	<ul style="list-style-type: none">• Develop a pre-FEED of a 10MWe CDCL pilot plant

Development of Chemical Looping Platform Technology



Particle Development

3000 Redox Cycles



Before



After




Particle Strength Comparison

Oxygen Carrier/Catalyst Particle	Strength (MPa)
OSU OC	120
Other Chemical Looping Combustion	72
Chemical looping Steam Reforming	26
Commercial WGS Catalyst Pellet	6.8
Traditional ATR Catalyst	6.5



Jet Cup



- Stability over 3000 redox cycles at 1000 °C; equivalent to 8 months of commercial operation
- High attrition resistance compared with commercial FCC particles in jet-cup experiment


25 kW_{th} Sub-Pilot Demonstration




- > 800 hours of operational experience
- > 200 hours continuous successful operation
- Smooth solids circulation
- Complete ash separation in reducer.
- Achieve nearly pure CO₂ from reducer outlet
- 17 test campaigns completed

200-hour Continuous Sub-Pilot Test


Reducer Carbon Conversion Profile



Combustor Gas Profile



Reducer Gas Profile



Sample Data: PRB Process Performance

- Continuous steady carbon conversion from reducer throughout all solid fuel loading (5- 25kWth)
- <0.25% CO and CH₄ in reducer outlet = **full fuel conversion** to CO₂/H₂O
- <0.1% CO and CO₂ in combustor = **negligible carbon carry over**, nearly 100% carbon capture

Outline

- ❑ **Background**

- ❑ **Technical Approach for 10 MWe Large Pilot**

- ❑ **Project Details**

- **Objectives**
- **Project Structure**
- **Project Schedule**
- **Project Budget**

- ❑ **Risk Management**

CDCL Technology Development




Laboratory
2.5 kWth

- Particle recyclability and reactivity
- Individual reactions in the reducer and combustor




25 kWth

- Integrated operation reducer and combustor for more than 200 hours
- Coal conversions
- CO₂ Purity




250 kWth

- Adiabatic reducer operation for more than 250 hours
- Process efficiency
- Evaluate emissions
- Large scale particle manufacturing
- Particle attrition



4 x 2.5 MWe

- Long Term operation
- Coal distribution
- Modular integration and operation - Start up, turn down, shutdown cycles
- Steam generation
- Economics



1 x 70 MWe

- Commercial Operation of a single module
- Fabrication

Scale Up Plan




x10

Laboratory
2.5 kWth




x10

25 kWth




x30

250 kWth



x30

4 x 2.5 MWe



1 x 70 MWe


Critical Dimension
Scale up Factor:
x1

Reducer reactor
Critical Dimension:
1.5"




Critical Dimension
Scale up Factor:
x4

Reducer reactor
Coal distribution
Distance:
6"




Critical Dimension
Scale up Factor:
x6

Reducer reactor
Coal distribution
Distance :
3'




Critical Dimension
Scale up Factor:
x2.3

Reducer reactor
Coal distribution
Distance :
7'




Critical Dimension
Scale up Factor:
x2.8

Reducer reactor
Coal distribution
Distance:
20'




10 MWe Modular Pilot Design



- 4 Modules of 2.5 MWe
- 1st module will be built and operated to validate the design.
- Following modules will be constructed
- Integration of the modules operation and controls

CDCL Steam Generation Scheme



Advantage of Modular Design and Sparing Philosophy

☐ Startup

- Sequential module startup with sharing resources

☐ High Reliability

- Independent steam generation
- Easier for scheduling maintenance
- 4-33% modules provide full load capacity with module-out of service



☐ Flexible Operation

- Fast response
- Turn down/up
- Particle exchange among modules

Technology Gap and Mitigation Plan

Design/Technology Issues	Past Mitigation	Ongoing Mitigation	Plan Mitigation
Particles			
Manufacturing Cost	Under OSU's Scope	Particle Manufacturer (JM)	Multiple Manufacturers
Attrition	250 kWth / NCCC	Attrition Tests / 250 kWth	10 MWe Large Pilot
High Temperature Resistance	TGA	TGA / 250 kWth	10 MWe Large Pilot
Reducer			
Coal Injection & Distribution	25 kWth Sub-Pilot	Coal RXN Model / 250 kWth	10 MWe Large Pilot
Char Residence Time	25 kWth Sub-Pilot	Coal RXN Model / 250 kWth	10 MWe Large Pilot
Ash Separation / Enhancer Gas	CFM / 25 kWth Sub-Pilot	CFM / 250 kWth	10 MWe Large Pilot
Char Carryover	CFM / 25 kWth Sub-Pilot	CFM / 250 kWth	10 MWe Large Pilot
Pressure Drop	Phase I / 25 kWth Sub-Pilot	250 kWth	10 MWe Large Pilot
CO ₂ Purity	25 kWth Sub-Pilot	250 kWth	10 MWe Large Pilot
Sulfur, NOx, Hg Emissions	25 kWth Sub-Pilot	250 kWth	10 MWe Large Pilot
Alkaline Management	2" BFB Studies	2" BFB Studies	10 MWe Large Pilot
Combustor			
Heat Exchanger surface	B&W's CFB Technology	B&W's CFB Technology	10 MWe Large Pilot
Auto-thermal Operation	Phase I (Calculation)	250 kWth	10 MWe Large Pilot
Process			
Operation	25 kWth Sub-Pilot / NCCC	250 kWth	10 MWe (modular)
Start up/Shut down	25 kWth Sub-Pilot / NCCC	250 kWth	10 MWe (modular)
Safety	25 kWth Sub-Pilot / NCCC	250 kWth	10 MWe (modular)

250 kW_{th} Pilot Plant - Design



Pilot Design:

- Reducer Design
- Material and Energy Balances
- Support Structure Design
- Detail Construction Drawings

Specifications

- Materials: Refractory lined Carbon Steel
- Max Operating Temperature: 2012 °F
- Reducer : Counter-current moving bed
- Combustor : Bubbling bed
- Overall Height: 32 ft
- Footprint = 10' x 10'
- Thermal Rating: 250 kW_{th}
- Coal Feed Rate: 70 lb/hr
- Coal Size: Pulverized coal
- Particle Transport: Pneumatic
- Oxygen Carrier: Iron based
- Size: 1.5 mm

250 kW_{th} Pilot Plant




250 kW_{th} Test Campaign Summary

Test Campaigns		Main Achievements	Lessons Learned
#1	Refractory bake out	Heated up to 1600 °F for more than 24 hrs	<ul style="list-style-type: none"> ○ Quench system ○ Need extra NG injection
#2	Unit shake down, start up and operation	<ul style="list-style-type: none"> • Reached 1800 °F • Achieved expected solid circulation • Characterization of temperature/pressure distributions, gas sampling and analysis 	<ul style="list-style-type: none"> ○ Coal injection pressure unbalance ○ Blower capacity low at startup
#3	Coal injection test	<ul style="list-style-type: none"> • Reached 1950 °F • Injected coal successfully • High volatile conversion • Attrition rate < 0.18%/hr 	<ul style="list-style-type: none"> ○ Air infiltration ○ Agglomeration due to over heating


Lessons Learned and Solutions

Lessons Learned	Solutions
High flame temp may cause particle agglomeration	Operate burner under a leaner condition to maintain a lower flame temperature
Air should be preheated to a higher temperature to reduce burner demand	Modify the flange and piping to be stainless steel to allow higher inlet temp of air
Air infiltration exists under vacuum condition	<ul style="list-style-type: none">• Seal the reducer better before next test• Operate under positive pressure


250 kW_{th} Pilot – Test Results



Attrition rate < 0.18%/hr



250 kW_{th} Pilot – Test Results



- high coal volatile conversion
- Carbon slip into the combustor not observed

Goal of Ongoing Work

- Temperature of Bottom Moving Bed reducer above 1650 °F
- Limit the amount of agglomerates and maintain long-term (>300 hours) stable solid circulation
- Demonstrate reduction-oxidation cycling of particles
- Continuous operation with coal injection for minimum 24 hours
- Coal conversion > 90%
- Attrition rate under reaction condition < 0.1%/hr
- Achieve adiabatic reducer operation

Outline

- ❑ Background
- ❑ Technical Approach for 10 MWe Large Pilot
- ❑ Project Details
 - Objectives
 - Project Structure
 - Project Schedule
 - Project Budget
- ❑ Risk Management

Phase I Objectives

- **Form the team**
- **Secure funding and commitments**
- **Host site agreement**
- **Environmental information volume**
- **Cost and schedule estimates for Phase II**

Phase II/III Objectives

NETL 10 MWe PHASE II

Year: 2019-2020

- 2.5 MWe module design
- CDCL integration with existing plant
- Balance of Plant (BOP) equipment specifications
- Process control specifications
- Proposal and cost estimates for Phase III

NETL 10 MWe PHASE III-A

Year: 2020-2022

- Construction and operation of first module
- Commissioning first module and BOP

NETL 10 MWe PHASE III-B

Year: 2022-2025

- Construction of remaining modules
- Commissioning and testing of full plant

Objective: Demonstrate 10 MWe CDCL pilot plant

Project Participants

▸ Federal Agencies

- DOE/NETL

▸ State Agency

- Ohio Development Services Agency

▸ Project Participants

- Babcock & Wilcox (B&W)
- Ohio State University (OSU)
- Clear Skies Consulting
- Dover Light & Power (DPL)
 - Trinity Consultants
 - Worley Parsons
- Electric Power Research Institute (EPRI)

▸ Industrial Review Committee

- American Electric Power
- Duke Energy
- FirstEnergy
- CONSOL Energy
- Johnson Matthey (JM)



Development
Services Agency



Clear Skies
Consulting



EPRI | ELECTRIC POWER
RESEARCH INSTITUTE

Trinity
Consultants



FirstEnergy

JM

CONSOL ENERGY




Division of Responsibility

Team	Responsibility
Babcock & Wilcox	Project management; technology lead; CDCL engineering design
Ohio State University	Technology support
Clear Skies Consulting	Provide industrial representation and guidance
Dover Light & Power	Provide host site and the related information
Johnson Matthey*	Large-scale oxygen carrier manufacture
EPRI	Techno-economic analysis
Worley Parson	Provide engineering services for the BOP to integrate CDCL equipment
Trinity Consulting	Environmental impact assessment, EIV and NEPA

* Join in Phase II/III

Phase I Team Organization



Tasks and Schedule

10 MWe CDCL Large Pilot Facility		Phase I															
		Budget Period 1															
		FQ3	FQ4		FQ1		FQ2		FQ3								
		2018												2019			
Project Tasks	Description	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7
	1.0 Project Management, and Reporting (Phases I, II, III)																
	1.1 General Project Management																
	1.2 Project Review Meetings																
	1.3 Quarterly Progress Reports																
	1.4 Project Final Report and Close-out Documents																
	<i>Milestone: Final Report</i>																
	PHASE I																
	2.0 Project Commitment and Complete Environmental Information Volume (EIV)																
	2.1 Host Site Agreement and Team Commitments																
	2.2 Draft Environmental Assessment																
	2.3 Develop Environmental Information Volume																
	<i>Milestone: Environmental Information Volume (EIV)</i>																
	2.4 Draft State of Ohio EPA Permit-To-Install (PTI)																
	2.5 Draft Mitigation Action Plans (MAP)																
	3.0 Cost and Schedule Estimates for Phase I																
	3.1 Develop Phase II Project Work Breakdown Structure (WBS)																
	3.2 Prepare a Cost Breakdown and Estimate for Phase II Workscope																
	<i>Milestone: Cost Breakdown Structure for Phase II</i>																
	<i>Milestone: Cost Estimate for Phases II and III</i>																
	<i>Milestone: Topical Report</i>																

10 MWe CDCL Large Pilot Facility		Phase II											
		Budget Period 2						BP3					
		Q2	Q3	Q4	Q1								
Project Tasks	Description	2019											
		1	2	3	4	5	6	7	8	9	10	11	12
PHASE II													
5.0	Release of Functional Specifications												
5.1	Heat and Material Balance												
5.2	Mechanical Design and Drawings												
5.3	Electrical Designs and Drawings												
5.4	General Arrangement Drawings												
5.5	Hazard Design and Operation (HAZOP)												
5.6	NEPA Study												
5.7	Phase III Test Plan												
5.8	Operating Procedures												
6.0	Balance of Plant Equipment Specifications												
6.1	Balance of Plant Specifications and Modifications												
6.2	Environmental Control Equipment												
6.3	CO2 Compression Equipment												
6.4	Waste Treatment and Disposal												
7.0	CDCL Integration with Existing Steam Turbine Equipment Specifications												
7.1	Steam Turbine Components												
7.2	CDCL Specific Piping and Instrumentation Drawings												
8.0	Process Controls Specifications & Drawings												
8.1	Plant PLC specifications												
8.2	Upgrade Existing Controls to Accommodate CDCL unit												
8.3	Focal Point Optimization												
8.4	ProTRAX Dynamic Model & Simulator												
8.5	P&IDs and Drawings												
9.0	General Arrangement Drawings (Process and Equipment)												
9.1	CDCL Equipment Arrangement Drawings												
9.2	Balance of Plant General Arrangement Drawings												
10.0	Building and Utilities Design and Cost Estimate												
10.1	General Construction - project manager, construction supervision												
10.2	Site Construction -building excavation, utilities, pavements, site upgrades												
10.3	Concrete - building and equipment foundations concrete												
10.4	Masonry, Metals, Wood & Plastic, Building Envelope, Doors & Windows, Finishes												
10.5	Special Construction, Fire Protection, Restrooms, Lighting, General Utilities												
11.0	Prepare Phase III Proposal & Firm Cost Estimate												
11.1	Prepare Firm Cost Estimate and Schedule												
11.2	Prepare Phase III Proposal												
12.0	Purchase Requisitions for Mechanical Components												
12.1	CDCL-Specific Components - fabricated and purchased												
12.2	CDCL Piping and Instrumentation Drawings												
13.0	Purchase Requisitions for Instrumentation and Controls												
13.1	PLC Components and Upgrade to Existing controls Requisitions												
13.2	Balance of Plant Instrumentation and Controls Requisitions												
13.3	CDCL Integration with Existing Steam Turbine Equipment Requisitions												
14.0	Order long-lead items (optional)												
	Order Steel and Materials of Construction												

10 MWe CDCL Large Pilot Facility												Phase III-A													
												Budget Period 3						Budget Period 3						PB3	
												Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1						
Project Tasks	Description	2020												2021											
		1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
PHASE III -A																									
15.0 Construction and Operation - First Module																									
15.1	Equipment Procurement																								
15.2	Procurement of Electrical and Instrumentation Equipment																								
15.3	Fabricated Components																								
15.4	Supplies and Consumables																								
15.5	Oxygen Carrier Manufacturing																								
15.6	Building Erection																								
15.7	Equipment Installation																								
15.8	Fabricated Components Installation																								
15.9	Instrumentation and Controls Installation																								
16.0 Commissioning of First Module and BOP Equipment																									
16.1	Individual Equipment Commissioning																								
16.2	Cold-Flow Tests Commissioning																								
16.3	Hot-flow Test Commissioning and Refractory Dry out																								
16.4	Upgrades to First Module Design Specifications																								

10 MWe CDCL Large Pilot Facility		Phase III-B											
		Budget Period 3			Budget Period 3				Budget Period 3				BP6
		Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1
Project	Description												
Tasks													


Host Site: Dover Light & Power

Existing

- 20 MWe Stoker coal fired boiler

Planning

- 10 MWe natural gas package boiler
- 10 MWe CDCL unit
- Increase power capacity
- Preserve a balance between coal and natural gas
- Potential CO₂ market from local industries



20 MWe Steam Turbine

Project Budget

Recipients	Federal	Cost-share	Total
PHASE I (4/1/2018 – 7/31/2019)			
B&W	\$377,859	\$50,000	\$427,859
OSU	\$240,000	\$72,500	\$312,500
EPRI	\$79,732	\$19,932	\$99,664
DL&P	\$0	\$35,000	\$35,000
Clear Skies	\$43,603	\$10,901	\$54,504
Total	\$741,194	\$188,333	\$929,527
Percent	79.74%	20.26%	100%
PHASE II (2019-2020) - Estimated			
Total	\$3,000,000	\$750,000	\$3,750,000
PHASE III (2020-2025) - Estimated			
Total	\$40,000,000	\$10,000,000	\$50,000,000

Outline

- ❑ **Background**
- ❑ **Technical Approach for 10 MWe Large Pilot**
- ❑ **Project Details**
 - **Objectives**
 - **Project Structure**
 - **Project Schedule**
 - **Project Budget**
- ❑ **Risk Management**

Risk Management

Description of Risk	Probability	Impact	Risk Mitigation Strategies
Delay in design activities	Moderate	Moderate	Sequence the design activities to ensure that the cost estimates for Phases II can be developed
Unavailable resources	Moderate	Moderate	<ul style="list-style-type: none"> • Accommodate B&W's personnel to satisfy the project needs as well as B&W commercial needs • Give this project high priority • Look for contractors outside B&W
Poor Project Execution	Low	Moderate	<ul style="list-style-type: none"> • B&W has extensive experience executing similar or larger DOE projects • Develop project breakdown structure and task activities • Track performance against deliverables and milestones
Delay in contract release	Low	Moderate	B&W has many contracts with DOE-NETL and has compiled terms and conditions so contract negotiation should be quick.
Cost overruns	Low	Moderate	<ul style="list-style-type: none"> • Track costs associated with major tasks separately • B&W will notify DOE on any possible budget variance and how to remedy the situation
Safety	Low	High	No operation of experimental or commercial facilities is required as part of the Phase I scope
Unable to acquire the design data specific to 10 MWe plant	Moderate	High	<ul style="list-style-type: none"> • Continue with the design of the plant until we gather the required information • Perform additional 250 kWth pilot tests to gather such information with non-federal funds • Install one module first and test it

Acknowledgements

This presentation is based upon work supported by the Department of Energy under Award Number [DE-FE0031582](#) and the Ohio Development Services Agency under Award Number [OER-CDO-D-17-03](#).