



Project Kick-Off Meeting FE0031597

Mixed-Salt Based Transformational Solvent Technology for CO₂ Capture

Palitha Jayaweera

Principal Scientist

Advanced Technology and Systems Division

SRI International

Sep 4th, 2018


Presentation Outline

- Technology Background
 - Needs to reduce CO₂ capture costs
 - Advanced Mixed-Salt Process
 - Process Benefits
- New Project Structure
 - Objectives and Budget
 - Project Team and Organization
 - Development Path
 - Work Organization
 - Project Tasks
 - Available Resources
 - Project Status Update
 - Milestones
 - Risk Management
- Acknowledgements

Reducing Capture Costs Beyond the Current Values

New transformational technologies

-A step reduction of the regeneration energy is required



- Low regeneration energy by solvent pairing
- Energy recovery by heat integration

Advanced Mixed-Salt Process Details

How it works:

Selected composition of potassium carbonate , ammonium salts and an amine

- Overall heat of reaction 35 to 60 kJ/mol (tunable)

Absorber operation at 20° - 40° C at 1 atm


Regenerator operation at 90° - 120° C at ~10 atm

- Produce high-pressure CO₂ stream

$K_2CO_3-NH_3$ -Amine-CO₂-H₂O system


High CO₂ cycling capacity
Reduced Ammonia Emission
Reduced Reboiler duty
Reduced CO₂ Compression Energy

A significant step change for reaching DOE's reduced CO₂ capture cost targets.




Process Enhancements

Enhanced Kinetics at High Temperature



Observed rate enhancement of CO₂ absorption efficiency by comparison of mixed-salt with NH₃

Low Energy Requirement for CO₂ Stripping




Estimated regenerator heat requirement for mixed-salt system with 0.2 to 0.6 cyclic CO₂ loading. Comparison with neat K₂CO₃ and MEA is shown

(Source for the Shell K₂CO₃ process, Schoon and van Straelen, 2011).

Absorber side: Reduced packing height
Regenerator side: Reduced water evaporation

Power Loss due to Steam Extraction




The net loss in power output from the steam cycle due to steam extraction for capture as a function of solvent regeneration temperature and the solvent heat requirement for regeneration.

Source: Adapted from Luquiaud and Gibbins, Chem Eng Res Des (2011); the Mixed-Salt data are from SRI's TEA

CO₂ Compression Energy




Both MSP and A-MSP require less energy for CO₂ compression



Electricity output penalty of compression to 100 bar as a function of desorber pressure

Source: Luquiaud and Gibbins, Chem Eng Res Des (2011).

Selected Reactions





In the A-MSP, the tertiary amine is added to the MSP system.

The $\text{K}_2\text{CO}_3\text{-NH}_3\text{-R1R2R3N-H}_2\text{O-CO}_2$ system has an additional equilibrium reaction given in Eq. (7).



Ammonia as a Catalyst




NH_3 cycle at the gas-liquid boundary.

Boiling Point and Measured Henry's Constant Values for Amines.


Amine	Boiling Point (°C)	Henry's Constant (Pa)
Methyl-diethanolamine (MDEA)	245	12.7
Diglycolamine (DGA)	223	13.9
Piperazine (PZ)	146	43.4
2-Methyl-piperazine (2-MPZ)	155	48.2
Ethylenediamine (EDA)	117	62.7
Monoethanolamine (MEA)	170	70.7
1-Methyl-piperazine (1-MPZ)	119	114
2-Amino-2-methyl-1-propanol (AMP)	166	288

Modeling Data

CO₂ Partial Pressure of 10 molal Advanced Mixed-Salt Solution



CO₂ Absorption at 20 ° and 30°C .




CO₂ Desorption at 10 bar


For the regeneration, the modeled composition can desorb CO₂ at > 10 bar at 100° C, a much lower temperature than MSP.

AMSP → *Pathway to reach DOE 2030 CO₂ capture goals*

Temperature Dependence of the Rate of CO₂ Absorption




Measured
(ammonia solution)



Predicted


Advanced Mixed-Salt Comparison with Ammonia and K_2CO_3



NH₃ vapor pressure as a function of CO₂ loading. A comparison between MSP and 10 m aqueous ammonia at 20°C is shown.

Reference. Jayaweera et al, "Mixed-Salt Solutions for CO₂ Capture," in *Absorption-Based Post-combustion Capture of Carbon Dioxide*, Elsevier, 2016, pp. 167-200.

Absorber-Side



Comparison of CO₂ released to the vapor phase during regeneration for CO₂-rich Mixed-Salt (0.6 CO₂ loading) and K₂CO₃ solutions

Regenerator-Side

New Project

Mixed-Salt Based Transformational Solvent Technology for CO₂ Capture

- Project Objectives
 - Very high CO₂ loading capacity
 - Solvent rich system
 - Regenerate CO₂ at >10 bar at temperatures less than 120°C
 - Collect the experimental V-L-E data for the AMSP.
 - Develop predictive equilibrium and rate based models for the AMSP
 - Potential to reach DOE cost target \$30/ton CO₂ by 2030


Project Team

Mixed-Salt Based Transformational Solvent Technology for CO₂ Capture

Project Manager: Andrew Jones, NETL

Prime Contractor: SRI International


Project Team: US and International Partners



15

Opportunities for US-Norway Collaborations leading to new IP and new markets

Work Organization



Project Budget


Contract No: DE-E0031597

DOE Funding: \$2,999,992 (~79%)

Partner Share: \$782,817 (~21%)

- **SRI International, USA**
 - Advanced mixed-salt composition development and testing
- **DTU, Denmark (Cost-share partner)**
 - VLE Measurements & Thermodynamic modeling
- **OLI Systems, USA**
 - Flowsheet Model Design (energy and mass balance)
- **Trimeric, Corp., USA**
 - Process Techno Economic Analysis
- **SINTEF, Norway (Cost-share partner)**
 - Emission and degradation studies
 - Alternative Mixed-salt composition development and testing

Our Systematic Technology Development Approach



Testing

- SRI
- DTU
- STINTEF

Modeling

- OLI Electrolyte Model
- OLI FOWSHEET MODEL
- DTU UNIQAC
- TRIMERIC cost model

Advanced Mixed-Salt Process optimization with
experimental and modeling approach

1. Equilibrium Model (DTU Data)
2. Rate based Model (SRI Data)



1. ASPEN Modeling
2. OLI ESP Modeling



Mass & Energy
Balance

Test Matrix


Parameter	BP1	BP2
Gas flow rate	<20 lpm	>100 lpm
Packing density	Fixed	Mellapak 250-450
Absorber temperature	20-30°C	15-40°C
Absorbent composition	Variable	Fixed
Regenerator temperature	100-120°C	100-120°C

Measurement of VLE Data and Thermodynamic Modeling at DTU

- Two systems are considered:
 - $\text{CO}_2\text{-NH}_3\text{-R1R2R3N-H}_2\text{O}$
 - $\text{CO}_2\text{-NH}_3\text{-R1R2R3N-K}_2\text{CO}_3\text{-H}_2\text{O}$
- For both systems, the following measurements will be performed:
 - Measurement of equilibrium pressure for Vapor-Liquid-Equilibrium (VLE)
 - Water activity measurements
 - Solid-Liquid-Equilibrium analysis
- No data for these systems have previously been reported in the open literature
- The measured data will be used for determining parameters in the thermodynamic model, Extended UNIQUAC.
- After the model parameters have been determined, the model can be used for process simulation in AspenPlus®.

Flow-Sheet Modeling at OLI Systems


- Incorporation of DTU VLE data into the ESP model
- Incorporation of SRI test Data to develop the rate based model.
- Develop the flowsheet model to produce heat and mass balance information
- Trimeric will use the OLI flowsheet model to prepare TEA



Mixed-Salt Based Transformational Solvent Technology for CO₂ Capture

Team : SRI (USA), SINTEF (Norway), OLI (USA), DTU (Denmark), Trimeric (USA)

Funding : US DOE (SRI Project) & CLIMIT (SINTEF Project)




Opportunities for reducing CO₂ from small and large-scale applications

Existing Infrastructure for Testing

Photographs of lab and large bench scale setups

Large bench scale system

Lab scale system



- A: Rich solution inlet locations
- B: Discharge locations for high NH_3/K solution
- C: Discharge locations for low NH_3/K solution
- D: Heat exchangers (Cold rich \leftrightarrow Hot lean)

Project Tasks

BP1: 18 months BP2: 18 months

- Task 1: Project Management and Planning (SRI)
- Task 2: Vapor-Liquid-Equilibria Measurements (DTU)
- Task 3: Process Kinetic Assessment (SRI)
- Task 4: Emission and Degradation Measurements (SINTEF)
- Task 5: Rate-Based Model Development (OLI)
- Task 6: Preliminary Techno-economic Analysis (Trimeric)
- Task 7: Integrated System Testing (SRI)
- Task 8: Process Flowsheet Model Development (OLI)
- Task 9: Techno-economic Analysis (Trimeric)

* Tasks in Red will be performed in BP2

Project Timeline

BP1: 18 months; BP2: 18 months							2018		2019		2020				2021	
			BP1						BP2							
			6/1/18	9/1/18	12/1/18	3/1/19	6/1/19	9/1/19	12/1/19	3/1/20	6/1/20	9/1/20	12/1/20	3/1/21		
Task	Start Date	End Date	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12		
Advanced -Mixed-Salt Process (BP1 and BP2)	6/1/2018	5/31/2021														
Task 1.0 - Project Management and Planning	6/1/2018	5/31/2021														
Project Kick-Off Meeting	6/1/2018	8/31/2018														
Technology Maturation Plan	6/1/2018	5/31/2021														
Milestones			a	b	c				l, j							
Task 2.0 : VLE Measurements	6/1/2018	5/31/2021														
Subtask 2.1 - VLE Measurements of the MDEA-NH3-CO2-H2O System	6/1/2018	4/30/2019														
Subtask 2.2 - Solid-Liquid Equilibrium Analysis	3/1/2019	11/30/2019														
Subtask 2.3 - VLE Measurements of the MDEA-K2CO3-NH3-CO2-H2O System	9/1/2019	11/30/2019														
Milestones								d								
Task 3.0 - Process Kinetic Measurements	9/1/2018	11/30/2020														
Subtask 3.1 - Bench-Scale Test Plan Development	9/1/2018	1/31/2019														
Subtask 3.2 - Absorption Measurements	9/1/2018	11/30/2019														
Subtask 3.3 - Regeneration Rate Measurements	9/1/2018	11/30/2019														
Subtask 3.4 - Test Data Analysis	9/1/2018	11/30/2019														
Milestones					e			f								
Task 4.0 - Process Kinetic and Emission Assesments	12/1/2019	5/31/2021														
Subtask 4.1 - Oxidative and Thermal Degradation Study	12/1/2019	5/31/2020														
Subtask 4.2 - Emission Measurements at the Recipient's Team Member Facility	12/1/2019	5/31/2021														
Subtask 4.3 - Integrated Testing with Amine and Mixed-salt blends	12/1/2019	5/31/2021														
SINTEF Submit the Data Report to SRI	4/1/2021	4/30/2021														
Milestones										k				l		
Task 5.0 - Rate Based Model Development	6/1/2018	11/30/2019														
Subtask 5.1 - Thermodynamic model for the MDEA-K2CO3-NH3-CO2-H2O system	6/1/2018	11/30/2018														
Subtask 5.2 - Data Analysis and Predictive Model Development	12/1/2018	11/30/2019														
Milestones									g							
Task 6.0 - Preliminary Techno-Economic Analysis	12/1/2018	11/30/2019														
Subtask 6.1 - Review of A-MSP Flow-sheet	5/1/2019	11/30/2019														
Subtask 6.2 - Techno-Economic Analysis	9/1/2019	11/30/2019														
Subtask 6.3 - First Decision Point (a. Report b. Continuation)	9/1/2019	11/30/2019														
Milestones									h							
Task 7.0 - Integrated System Testing at the Recipient Site	12/1/2020	5/31/2021														
Subtask 7.1 - Development of Test Plan and Submission to DOE	12/1/2020	2/29/2020														
Subtask 7.2 - Integrated Testing with MSP and A-MSP Compositions	3/1/2020	2/28/2021														
Subtask 7.3 - Regenerator Steam use Measurements	12/1/2020	5/31/2021														
Subtask 7.4 - Test Data Analysis	5/1/2020	5/31/2021														
Milestones									m					n		
Task 8.0 - Flow-Sheet Model Development	6/1/2020	5/31/2021														
Subtask 8.1 - Development of Process Flow-Sheet Model	6/1/2020	12/31/2020														
Subtask 8.2 - Evaluation of Process Heat and Mass Balances	9/1/2020	4/30/2021														
Milestones														o		
Task 9.0 - Techno-Economic Analysis	9/1/2020	5/31/2021														
Subtask 9.1 - Techno-Economic Analysis	9/1/2020	3/31/2021														
Subtask 9.2 - Update the State Point Data Table	1/1/2021	3/31/2021														
Subtask 9.3 - Technology Gap Analysis	1/1/2021	3/31/2021														
Subtask 9.4 - Environmental Health and Safety Risk Assessment	1/1/2021	3/31/2021														
Submit the State Point Data Table	4/1/2021	4/30/2021														
Submit the Technology Gap Analysis	4/1/2021	4/30/2021														
Submit the Technology Maturation Plan	4/1/2021	4/30/2021														
Project Review at DOE	5/1/2021	5/31/2021														
Final Report Submission	5/1/2021	5/31/2021														
Milestones																
																p,q,r,s

Success Criteria and Decision Points

Decision Point	Basis for Decision/Success Criteria
A. Completion of Budget Period 1	Successful completion of all work proposed in Budget Period 1
	Submission of a Technology Maturation Plan
	Submission of Preliminary Techno-Economic Analysis topical report
	Experimentally validate at least 10 bar pressure in the regenerator ~120°C
	Partnering agreement finalized
	Successful completion of the VLE model development and demonstrating the lower regeneration (less than 120°C) potential of the A-MSP solution
	Completion of the spread-sheet model by OLI to demonstrate the regeneration energy to be less than 2.3 GJ/tonne CO ₂
B. Completion of Budget Period 2	Successful completion of all work proposed
	Completion of integrated A-MSP bench-scale testing with selective, high-pressure regeneration of ammonia rich and potassium + amine rich streams, including parametric testing with a simulated flue gas, and continuous testing with a simulated flue gas at partner facility; bench-scale testing results showing ≥ 0.10 kg-CO ₂ /kg working solution loading capacity, ammonia emissions < 10 ppm in the stack gas, and total energy consumption < 1.8 GJ/tonne CO ₂ (including the estimated compression work) that indicate significant progress toward achieving the DOE's Transformational CO ₂ Capture goals of 95% CO ₂ purity at a cost of \$30/tonne of CO ₂ captured
	Submission of (1) an updated State-Point Data Table; (2) a Techno-Economic Analysis topical report; (3) a Technology Gap Analysis topical report; and (4) an Environmental Health & Safety Risk Assessment topical report based on the results of bench-scale testing
	Submission of a Final Report

Risk Table

Description of Risk	Probability (Low, Moderate, High)	Impact (Low, Moderate, High)	Risk Management Mitigation and Response Strategies
Technical Risks:			
Precipitation of solids in the absorber	Low	Low	Store rich solution in a separate tank overnight; design a SOP to avoid shutdowns with rich solutions. General SOPs for operating ammonia-based processes are available at SRI.
Residual amine in the exit gas stream	Moderate	Moderate	Use a tertiary amine as the starting amine to reduce residual amine. Select lowest volatility among the commonly used amines. For any new amine blends, we will study the VLE before testing in the bench-scale test system.
Residual ammonia in the exit gas stream	Moderate	Moderate	Increase the water-wash column fresh-water flow to capture ammonia vapor.
High-pressure drop in the absorber column	Low	Moderate	Monitor and control the recycled liquid flow and flooding level.
Solvent interaction with acid gases	Moderate	Moderate	Monitor solvent composition and control the bleed and make-up flow of solvents.
Particulate accumulation	Low	Low	Monitor suspended particles in the absorption solution. Replace solution if too high.
Thermal management of absorber columns	Low	Moderate	Monitor column temperature closely and control cooling water flow accordingly.
Thermal management of regenerator	Low	Moderate	Control the steam flow and heat exchanger flow closely. Monitor temperature sensor profiles to avoid rapid temperature changes.
Resource risks:			
Delays in procurement of required components	Low	Moderate	Plan ahead with vendors. Place orders early and have backup vendors. We have been working with a reliable chemical broker for bench-scale testing.
Delays in construction	Low	Moderate	Plan ahead with realistic timelines. Meet with staff regularly and address issues early on.
Management risks:			
Project team availability	Low	Moderate	Identify a backup team.
Health and safety	Low	High	Prepare SOPs and train operators.

Milestone Log - BP1

BP	Task/ Subtask No.	Milestone Description	Planned Completion	Actual Completion	Verification Method
1	1	a. Updated PMP	7/1/2018	8/1/2018	PMP file
1	1	b. Kickoff Meeting	8/31/2018		Presentation file
1	1	c. Technology Maturation Plan	9/30/2018		TMP file
1	2.1-2.3	d. Completion of quaternary system VLE measurements at DTU and submission of speciation curves	11/30/2019		Results reported in the QR report
1	3.1	e. Bench-scale absorber and regenerator test plans submitted	1/31/2019		Results reported in the QR report
1	3.1-3.4	f. Completion of at least 20 kinetic test runs at SRI	11/30/2019		Results reported in the QR report
1	5.1-5.2	g. Completion of rate-based model development at OLI	11/30/2019		Results reported in the QR report
1	6.2	h. Preliminary Techno-Economic Analysis topical report submitted	11/30/2019		Results reported in the QR report and a topical report
1	1	i. Partnering agreement	11/30/2019		Partnering Agreement submitted to DOE/NETL
1	1	j. Budget Period 1 summary topical report submitted	11/30/2019		Results reported in the QR report and a topical report



Milestone Log - BP2

2	4.1-4.3	k. Completion and submission of SINTEF report #1 providing properties and characterization for at least one new amine	5/31/2020		Results reported in the QR report
2	4.2-4.3	l. Completion and submission of SINTEF report #2 to SRI providing emission information to support the EH&S report	3/31/2021		Results reported in the QR report
2	7.1	m. Integrated system test plan submitted	2/28/2020		Results reported in the QR report
2	7.1-7.4	n. Completion of integrated system testing for at least 100 hours at SRI	3/31/2021		Results reported in the QR report
2	8.1-8.2	o. Completion of flow-sheet model development at OLI and delivery of complete stream flow details, mass and energy balance for the optimal configuration	2/28/2021		Results reported in the QR report
2	9.1	p. Techno-Economic Analysis topical report submitted	3/31/2021		Topical Report and summary in Final Report
2	9.2	q. Updated State-Point Data Table submitted	3/31/2021		Final Report
2	9.3	r. Technology Gap Analysis topical report submitted	3/31/2021		Topical Report and summary in Final Report
2	9.5	s. Environmental Health & Safety Risk Assessment topical report submitted	3/31/2021		Topical Report and summary in Final Report
2	1	Draft Final Report submitted	6/30/2021		Final Report file

Project Status Update

As of (7/31/2018)	Status
Task 1.0 - Project Management and Planning	
Task 2.0 – VLE Measurements at DTU	
Subcontract award	In progress
VLE measurements	To begin soon
Task 3.0- Kinetic Measurements at SRI	
Bench-scale setup and test plan development	Started
Absorption measurements	To begin soon
Task 5.0- Rate Based Model Development at OLI	
Subcontract award	Completed
Flow-sheet modeling	To begin soon
Task 6.0- Preliminary Techno Economic Analysis (OLI/Trimeric/SRI)	
Subcontract Award to Trimeric	Completed
Preliminary TEA	To begin soon

Project Location



SRI's site in Menlo Park, CA (~ 65 acres)

Team Member Locations



Denmark



New Jersey



TRIMERIC CORPORATION

Texas



Norway

Acknowledgements

NETL (DOE)

- Andrew Jones, Steven Mascaro, Jose Figueroa, Lynn Bricket, John Litynski and other NETL staff members

SRI Team

- Palitha Jayaweera, Indira Jayaweera, Elisabeth Perea, Regina Elmore, Srinivas Bhamidi, Bill Olsen, Marcy Berding, Chris Lantman, and Barbara Heydorn

US and International Collaborators

- DTU (Kaj Thomsen, Philip Fosbol)
OLI Systems (Prodip Kondu and Andre Anderko),
Trimeric Corporation (Andrew Sexton)
POLIMI (Gianluca Valenti, Davide Bonalumi, and Stefano Lillia),
Stanford University (Adam Brant and Charles Kang),

Industrial Partner/Observer

- IHI Corporation

Thank You

Contact:

Palitha Jayaweera

palitha.jayaweera@sri.com

1-650-859-2989

Headquarters

333 Ravenswood Avenue
Menlo Park, CA 94025
+1.650.859.2000

Additional U.S. and
international locations

www.sri.com

Disclaimer

This presentation includes an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.