



# Large Bench-scale Development of a Non-Aqueous Solvent CO<sub>2</sub> Capture Process for Coal-fired Power Plants

*Jak Tanthana*, S. James Zhou, Paul Mobley, Aravind Rabindran, Mustapha Soukri, Vijay Gupta, and Marty Lail



Thor Mejdell, Andrew Tobiesen, Kristin Lauritsen, Ugo Aronu, Lars Hovdahl

DE-FE0026466

DOE Program Manager: Steve Mascaró

2018 NETL CO<sub>2</sub> Capture Technology Meeting

**August 13 - 17, 2018**

## Worldwide Presence and Financial Strength

**\$972 M** 

FY2017 Revenue

**3,852**   
Projects

(fiscal year 2017)

**1,198**   
Clients

(fiscal year 2017)

**12**   
U.S. Offices

Research Triangle Park, NC

Ann Arbor, MI

Atlanta, GA

Berkeley, CA

Chicago, IL

Fort Collins, CO

Portland, OR

Rockville, MD

San Francisco, CA

Seattle, WA

Waltham, MA

Washington, DC

**12**   
International  
Offices

Abu Dhabi, United Arab Emirates

Barcelona, Spain

Beijing, China

Belfast, Northern Ireland

Jakarta, Indonesia

Kuala Lumpur, Malaysia

Ljungskile, Sweden

Manchester, United Kingdom

Nairobi, Kenya

New Delhi, India

San Salvador, El Salvador

Toronto, Canada

## ENERGY TECHNOLOGIES

Developing advanced process technologies for energy applications by partnering with industry leaders

Biomass  
Conversion

Industrial Water  
Treatment

Carbon Capture &  
Utilization,  
Gas Separations

Advanced Materials  
for Catalysis &  
Separations

Syngas Processing

Natural Gas

# Presentation Overview

- Project Overview and Objectives
- Project Summary and Budget
- Budget Period 1 Review
  - Milestones and Accomplishments
  - NAS Solvent
  - Process Engineering and Design
  - Bench-Scale Testing
- Budget Period 2 Update
  - Overview, Tasks, and Objectives
  - BP2 Progress
- Next Steps

# Project Overview

## **Total Funding: \$4,532,652**

Federal: \$3,468,584

Cost Share: \$1,064,068

## **Objective:** Continue the advancement of the NAS CO<sub>2</sub> Capture Process

- Increase solvent performance
- Design and build unique process modifications for Tiller
- Perform pilot testing of NAS on coal-derived flue gas
- Techno-economic and EHS evaluation

## **Timeframe:**

<b>BP</b>	<b>Timeframe</b>	<b>Months</b>	<b>Proposed Budget</b>	<b>Actual Budget</b>
1	10/01/15 – 12/31/2016	15 months	\$1,670,000	\$1,532,330
2	01/01/17 – 09/30/2018	21 months	\$3,000,322	\$3,000,322

- NAS Process testing at Tiller using propane + coal-derived flue gas
- Reduce the parasitic energy penalty to  $< 2.0 \text{ GJ}_t/\text{tonne of CO}_2$  captured

## **Other goals and objectives:**

- Conduct baseline testing of MEA
- Measure NAS solvent degradation and material compatibility
- Design Regenerator and Absorber wash section
- Improve the physical properties of NAS
- Improve NAS formulations and plan for Scale-up

# Bench-Scale Testing of Refined Solvents

## Absorber

3" Sch. 10 SS316 (8.5 m)  
Mellapak 350X  
Temp: 30-55° C  
Pressure: Up to 200 kPa  
Gas Vel: 0.33-1.5 m/s  
L: 15-75 kg/h

## Regenerator

3" Sch. 10 SS316 (7.1 m)  
Mellapak 350x  
Temp: Up to 150° C  
Pressure: Up to 1MPa  
3 kW ~185 kg CO<sub>2</sub>/day

## Simulated Flue Gas Properties



FG Flow Rate:	100 to 485 SLPM
CO <sub>2</sub> Feed Rate:	1.8 to 8.6 kg/h
Feed Temp.:	30 to 50°C
Target Comp:	CO <sub>2</sub> : 13.3%; H <sub>2</sub> O: 6.1%; O <sub>2</sub> : 2.35%; N <sub>2</sub> : bal.
CO <sub>2</sub> Content:	up to 20% vol
Water Content:	~0 to 12.3% vol

## Conditions for Experimental Data

- Absorber: 37-40° C
- Regenerator: 87-98° C
- Pressure: 2.5 bar
- Interstage Heater Regeneration



45 Liter Solvent



# BP-1 Baseline Testing of NAS in Tiller Pilot Plant

## Objectives:

- Compare MEA and NAS in conventional system
- Water balance
- Confirm reboiler heat duty
- Emission measurement

## Results:

- MEA baseline testing completed at Tiller plant
- NAS baseline testing completed
  - 350 hours of testing with propane + 50 hours with coal flue gas
  - Confirmed the reduction in reboiler duty




# Design Improvements for NAS-based Process

Design improvements (e.g. interstage coolers, new Regenerator packing section, rich solvent preheater) have been incorporated in the process engineering for a NAS-based CO<sub>2</sub> capture system

## Result Highlights:

- Interstage heaters: 2.19 (all) to 2.86 (none) GJ/tonne-CO<sub>2</sub>
- Interstage coolers: 2.19 (all) to 3.23 (none) GJ/tonne-CO<sub>2</sub>
- The use of preheater (HX-305) lowers the SRD





# BP1 Milestones

Milestone	Description	Completion	Status
A	Kick-off Meeting	12/31/15	<b>Milestone Achieved.</b> Kick-off meeting held at DOE/NETL site on 12/17/2015.
B	Updated project management plan	5/5/16	<b>Milestone Achieved.</b> Revision 1 of PMP was approved by DOE/NETL on 6/27/2016.
C	Completion of 250 hours baseline testing at SINTEF Tiller plant	3/20/17	<b>Milestone Achieved.</b> Performed MEA baseline testing at SINTEF and verified 3.6 GJ/tonne-CO <sub>2</sub> reboiler heat duty consistent with values reported in literature. NAS testing is planned for November 2016.
D	Engineering design package for Regenerator delivered to SINTEF	10/31/16	<b>Milestone Achieved.</b> A final design and engineering package has been delivered and included updated P&IDs, stream tables, and bill of materials for modification recommendations to SINTEF for their CO <sub>2</sub> capture unit at the Tiller plant.
E	Experimental data from formulation improvement confirming that the NAS solvents absorb less than 5 wt% water	12/31/16	<b>Milestone Achieved.</b> Some NAS formulations are able to achieve the < 5 wt% target, however, the optimal formulations have a preferred water absorption target between 5 to 10 wt%.
Success Criteria Description		Status / BP1 Achievement	
Completion of 250 hours baseline testing at Tiller plant on coal-derived flue gas		<b>Completed.</b> NAS testing in the Tiller plant facility followed SINTEF's testing of the NAS in their lab pilot system. NAS testing was conducted on propane-fired flue gas, and coal-fired boiler. A total of 405 hours of testing was completed.	
Regenerator design package completed and agreed upon by project team		<b>Completed.</b> See "Milestone D" description. RTI and SINTEF have agreed on Tiller plant design modifications. These recommended design changes will be implemented in BP2.	

# BP-2 Progress and Accomplishments Summary

- Modifications at Tiller led to NAS-optimized absorption process, capturing 90% of CO<sub>2</sub> with the SRD < 2.4 GJ/tonne-CO<sub>2</sub> under realistic process conditions (coal-fired and NG FG)
- **Completed** – Comprehensive parametric testing with 40+ trial conditions
- **Completed** – 1,500+ hours of testing under coal-fired flue gas
- **Ongoing** – Update process simulation based on Tiller data
- **Ongoing** – Update techno-economic assessment with solvent reclaimer
- **Completed** – NAS testing at NCCC

Task	Milestone Description	Planned Completion	Verification
5	F. NAS-specific components installed and commissioned at SINTEF Tiller plant	<b>Completed</b>	Quarterly Report #8
6	G. Completion of 1,200 hours cumulative testing at SINTEF Tiller plant	<b>Completed</b>	Quarterly Report #9
7	H. Detailed techno-economic analysis report delivered to DOE	9/30/18	Quarterly Report #11

# Task 7 - Modifications at Tiller





Coal-fired Burner



Additional Water Wash column

## Realizing the NAS optimal performance through process modifications:

- Addition of:
  - 1 x regenerator preheater
  - 2 x interstage heaters
  - 2 x interstage cooler
  - 1 x water wash column
- Enlarge lean-rich heat exchanger
- Addition of coal-fired burner
- Timeline:
  - Sizing, Design, and Approval: 01/2017-03/2017
  - Procurement and site prep: 03/2017-07/2017
  - Installation and Shakedown: 08/2017-11/2017
  - Parametric and long-term test: 12/2017-03/2018



Regenerator's Interstage Heaters




# Parametric testing of NAS-5 – Testing Condition


## 19 steady-state runs performed with varied parameters:

- Flue gas velocity
- FG humidity
- Liquid circulation rate
- Heating duty and its distribution
- Cooling duty and its distribution
- Coal-fired vs. Natural Gas
- Water wash operating conditions
- Acid wash operating conditions


## Parametric Testing: 751 hours on stream



# Parametric testing of NAS-5 – SRD




# Long-term test of NAS-5



543 h on parametric testing and 1,043 h on stream for long-term testing, total of 1,587 h

# Parametric and long-term testing of NAS-5 – Corrosion

Low values of metals  
(Fe, Cr, Ni) < 2 mg/l



## Corrosion at Tiller

- No corrosion issues encountered at Tiller
- PP liner evaluated at Tiller and result shows good compatibility

## Material Compatibility

- Excellent compatibility
  - SS316
  - PTFE
- Good compatibility
  - EPDM
- Corrosion coupon testing being undertaken at National Carbon Capture Center (NCCC) in June-August
  - Carbon steel
  - SS304
  - PP




# Parametric testing of NAS-5 - Degradation

- Ammonia
  - Controlled well by water wash and acid wash
- Methylamine
  - Manual samples taken near the end of the campaign before and after the water and acid washes to evaluate the mitigation approach
- Nitrosamine
  - Larger increase in nitrosamine seen during this campaign compared to the baseline campaign

- Risk Mitigation
  - Methylamine
    - Awaiting results of measurements after acid wash
  - Nitrosamine
    - Currently studying nitrosamine destruction using thermal degradation
    - Reclaimer at 150°C of a slipstream of lean solvent at the reboiler outlet can reduce nitrosamine levels
    - HSS reclaimer could be used for this purpose

Table 4.2 Determined alkylamines by LC-MS in Lean NAS solvent samples.

Journal no	RUN No	Time on stream [hrs]	NH <sub>3</sub> [mg/L]	Dimethyl-amine [µg/L]	Diethyl-amine [µg/L]	Methyl-amine [µg/L]	Ethyl-amine [µg/L]	Ethylmethyl-amine [µg/L]	Propyl-amine [µg/L]	Dipropyl-amine [µg/L]
P161252	0	0	109	130	< 100	64300	< 100	< 100	< 100	< 100
P161293	6	24	202	352	111	104114	< 100	< 100	< 100	< 100
P161365	12	124	33	700	165	83577	< 100	< 100	< 100	< 100
P17010	13	151	< 10	324	106	93767	< 100	< 100	< 100	< 100
P17046	17	245	25	208	< 100	81761	< 100	< 100	< 100	< 100



# Parametric testing of NAS-5 – Heat-Stable Salts (HSS)

- HSS formation
  - Low levels of HSS measured in baseline campaign
- Phase separation
  - No issues or indication of phase separation during baseline or modified test campaign
  - A second liquid phase will form when the water content is raised above 16%

HSS Formation vs. Time

Run No.	Time on Stream, hrs	HSS, ppm
0	0	0.25
6	24	0.38
12	124	0.32
13	151	0.32
17	245	0.32
22	381	0.45

# NAS Process Testing at NCCC and Cost/Benefit Analysis

- Scheduled for 3 months of testing, starting in late May through August
- Expose NAS with power plant's flue gas
- Further reduce the deployment risk, particularly on fugitive emissions and solvent degradation
- Tested NAS at NCCC using the SSTU
- Test advanced NAS-5 formulation at NCCC to determine:
  - operating windows
  - solvent degradation
  - water balance
  - emissions
  - amine loss
  - other operational issues
- Continuous run of NAS-5 using coal-derived flue gas for at least two months
- Recently completed with 570 hours on stream, data is being analyzed



# Next Steps: Project Closeout/Pilot-scale Testing/Emission Mitigation

- Update process simulation with Tiller data to predict emission and waste generation
  - Refine TEA with the additional solvent reclaimer unit
  - EHS assessment
  - Site preparation and solvent manufacturing for TCM testing
- Large pilot testing for non-aqueous solvent technology at Technology Center Mongstad (TCM) under DE-FE0031590
    - Under contract negotiation, project starts in May 2018
    - 10 MW equivalent
    - Range of flue gas compositions (including coal, NGCC, etc.)
    - Extended operation with finalized NAS formulation and process design
  - Ongoing discussion with TCM on testing schedule, site preparation, operational experience from BstU and Tiller



CO<sub>2</sub> Technology Centre Mongstad (TCM), Mongstad, Norway


# Next Steps: Project Closeout/Pilot-scale Testing/Emission Mitigation

- Bench-scale testing for Water-Lean Solvent systems (WLSs) at RTI and SINTEF's Tiller under DE-FE0031660

The specific goals of this project are to:

- Characterize and understand the emission produced by water-lean solvent
- Develop an empirically derived emission model based on the solvent physical properties and on critical operating parameters from the absorber and wash section
- Evaluate suitable process arrangement for emission reduction BACT devices
- Demonstrate the effectiveness of these emission mitigation devices on the bench-scale system optimized for water-lean solvent

**More Detail: Poster Presentation**



**Potential emissions control technologies for WLS systems to be incorporated at the CO<sub>2</sub> capture plant**

# Acknowledgments

- Financial support provided by DOE NETL under DE-FE0026466



- DOE Project Manager: Steve Mascaro
- RTI cost share and project partner SINTEF

